

NIST SPECIAL PUBLICATION 793

Report of the 75th National Conference on Weights and Measures

1990



Report of the

75th National Conference on Weights and Measures 1990

*Sponsored by the National Institute
of Standards and Technology,
Attended by Officials from the
Various States, Counties, and Cities, and
Representatives from U.S. Government,
Industry, and Consumer Organizations
Washington, DC July 9-13, 1990*

Report Editors:

Albert D. Tholen
Carroll S. Brickenkamp
Ann H. Turner



U.S. Department of Commerce
Robert A. Mosbacher, Secretary

National Institute of Standards and Technology
John W. Lyons, Director

Issued September 1990

Natl. Inst. Stand. Technol. Spec. Publ. 793, 242 pages (Sept. 1990)
CODEN: NSPUE2

U.S. GOVERNMENT PRINTING OFFICE
WASHINGTON: 1990

For sale by the Superintendent of Documents, U.S. Government Printing Office,
Washington, DC 20402-9325

Abstract

The 75th Annual Meeting of the National Conference on Weights and Measures (NCWM) was held at the J. W. Marriott Hotel in Washington, D. C. during the week of July 9 through 13, 1990. The theme of the meeting was "Progress Through Consensus Among Consumers, Regulators, & Industry."

In his address to the delegates, Chairman Fred Gerk of New Mexico reflected on the progress made by the NCWM in the past year. In his address, Conference President John Lyons, Director, National Institute of Standards and Technology, provided a history of the founding of the National Bureau of Standards and the NCWM. In his keynote address, Congressman Tim Valentine noted the challenges to be met by the NCWM in the future.

The Conference set standards for equipment and sales practices in the area of cash/credit pricing of retail motor fuel and compressed gas cylinders. Progress in training program development and standards for moisture loss were also reported upon.

Special meetings included those of the Metrologists, the Associate Membership Committee, the Retired Officials Committee, the Scale Manufacturers' Association, the American Petroleum Institute, the Industry Committee on Packaging and Labeling, the State regional weights and measures associations, and the National Association of State Departments of Agriculture Weights and Measures Division.

Reports by the standing and annual committees of the Conference comprise the major portion of this publication, along with the addresses delivered by Conference officials and other authorities from government and industry.

Key words: motor fuel dispensers; legal metrology; railroad track scales; safety; specifications and tolerances; training; type evaluation; uniform laws and regulation; weights and measures.

Library of Congress Catalog Card Number 26-27766.

Note: Opinions expressed in non-NIST papers are those of the authors and not necessarily those of the National Institute of Standards and Technology. Non-NIST speakers are solely responsible for the content and quality of their material.

Contents

	Page
Abstract	2
Past Chairmen of the Conference	5
State Representatives	6
Organization Chart	8
President Bush's Greetings	10
 General Session	 11
A National Need...Looking to the 21st Century	13
Dr. John Lyons, Director, National Institute of Standards and Technology	
 Chairman's Address	 16
Fred A. Gerk, New Mexico	
 Keynote Address	 19
U.S. Representative Tim Valentine, North Carolina	
 Honor Awards Presentations	 21
Certificates of Appreciation	22
President's Award	23
President's Certificate Award	23
 Standing Committee Reports	 25
 Report of the Executive Committee	 27
Appendix A - Policy, Interpretations, and Guidelines	47
Appendix B - Proposed Changes to NTEP Administrative Procedures, Technical Policy, Checklists, and Test Procedures	52
Appendix C - Report on OI ML to the Interim Meeting	55
Appendix D - Operating Budget 90/91	59
Appendix E - NCWM Task Force on Safety Meeting (January 1990)	62
Appendix F - Summary, Questionnaire on Conference Costs and Locations	69
Appendix G - Treasurer's Interim Report Fiscal Year 74 (1989-1990)	73
 Report of the Laws and Regulations Committee	 75
Appendix A - Uniform Weighmaster Law	109
Appendix B - 2.3.2. Fresh Fruits and Vegetables	116
Appendix C - Meat and Poultry Products A Consumer Guide to Content and Labeling Requirements	119
Appendix D - Test Method for Compressed Gases	127

Contents (Continued)

	Page
Report of the Specifications and Tolerances Committee	131
Report of the Committee on Education, Administration, and Consumer Affairs	177
Appendix A - NTP Certification Summary	187
Appendix B - NTP Registry Summary of Activity	191
Appendix C - The NCWM Training Needs Survey	197
Appendix D - Outlines of Parts I and II of Module 23	205
Report of the Committee on Liaison	213
Annual Committee Reports	221
Report of the Resolutions Committee	223
Report of the Nominating Committee	225
Report of the Auditing Committee	226
Treasurer's Report	227
New Chairman's Message	231
Registration List	236

Past Chairmen of the Conference

CONFERENCE	YEAR	CHAIRMAN
43rd	1958	J. P. McBride, MA
44th	1959	C. M. Fuller, CA
45th	1960	H. E. Crawford, FL
46th	1961	R. E. Meek, IN
47th	1962	Robert Williams, NY
48th	1963	C. H. Stender, SC
49th	1964	D. M. Turnbull, WA
50th	1965	V. D. Campbell, OH
51st	1966	J. F. True, KS
52nd	1967	J. E. Bowen, MA
53rd	1968	C. C. Morgan, IN
54th	1969	S. H. Christie, NJ
55th	1970	R. W. Searles, OH
56th	1971	M. Jennings, TN
57th	1972	E. H. Black, CA
58th	1973	George L. Johnson, KY
59th	1974	John H. Lewis, WA
60th	1975	Sydney D. Andrews, FL
61st	1976	Richard Thompson, MD
62nd	1977	Earl Prideaux, CO
63rd	1978	James F. Lyles, VA
64th	1979	Kendrick J. Simila, OR
65th	1980	Charles H. Vincent, TX
66th	1981	Edward H. Stadolnik, MA
67th	1982	Edward C. Heffron, MI
68th	1983	Charles H. Greene, NM
69th	1984	Sam F. Hindsman, AR
70th	1985	Ezio F. Delfino, CA
71st	1986	George E. Mattimoe, HI
72nd	1987	Frank Nagele, MI
73rd	1988	Darrell A. Guensler, CA
74th	1989	John J. Bartfai, NY

State Representatives

The following designated State representatives were present and voted on reports presented by the Conference standing and annual committees:

STATE	REPRESENTATIVE	ALTERNATE
Alabama	Don E. Stagg	John B. Rabb
Alaska	Aves Thompson	David Cavender
American Samoa	Arthur L. Young	None
Arizona	Raymond Helmick	Calvin F. Vance
Arkansas	Sam Hindsman	None
California	Darrell Guensler	Barbara Bloch
Colorado	David Wallace	None
Connecticut	Allan Nelson	Raymond Kalentkowski
Delaware	Eugene Keeley	None
District of Columbia	None	None
Florida	Maxwell Gray	Jack Jeffries
Georgia	Martin Coile	George E. Jones
Guam	None	None
Hawaii	James E. Maka	None
Idaho	Glen Jex	Thomas Schafer
Illinois	Sid Colbrook	Steve McGuire
Indiana	Sharon Rhoades	None
Iowa	Jerry L. Bane	None
Kansas	DeVern H. Phillips	Carl Gile
Kentucky	Victor Page	Randy Wise
Louisiana	Melvin Lyons, Jr.	None
Maine	Stanley K. Millay	None
Maryland	M. Richard Shockley	Louis E. Straub
Massachusetts	Charles H. Carroll	None
Michigan	Edward Heffron	Celeste Bennett
Minnesota	Michael F. Blacik	None
Mississippi	William P. Eldridge	None
Missouri	Lester H. Barrows	R. Wittenberger
Montana	None	None
Nebraska	Steven A. Malone	Michael Diesley
Nevada	None	None
New Hampshire	None	None
New Jersey	Carl P. Conrad, Jr.	Joseph Silvestro
New Mexico	Fred Gerk	Charles H. Greene
New York	John Bartfai	Ross Andersen

STATE	REPRESENTATIVE	ALTERNATE
North Carolina	N. David Smith	Ronald Murdock
North Dakota	None	None
Ohio	James C. Truex	None
Oklahoma	O. Ray Elliott	Charles Carter
Oregon	Kendrick J. Simila	None
Pennsylvania	Dean F. Ely	None
Puerto Rico	Heliodoro Lopez-Torres	Jose A. Torres-Ferrer
Rhode Island	None	None
South Carolina	Carol P. Fulmer	John V. Pugh
South Dakota	James A. Melgaard	None
Tennessee	Cathryn Pittman	None
Texas	Edwin J. Price	James H. Eskew
Utah	Robert Smoot	None
Vermont	Bruce Martell	None
Virginia	J. Alan Rogers	G. Wes Diggs
Virgin Islands	None	None
Washington	Sterling McFarlane	None
West Virginia	None	None
Wisconsin	Donald J. Soberg	Alan Porter
Wyoming	Victor Gerber	None

Organization Chart of the 75th National Conference on Weights and Measures

Operating Committees

Auditing Committee	
Chairman:	G. Hanson, CA (1)
Members:	Carol Fulmer, SC R. Davis, James River Corp.

Resolutions Committee	
Chairman:	O. R. Elliott, OK (1)
Members:	D. Ely, PA (2) S. McFarlane, WA (1) S. McGuire, IL (1) C. Pittman, TN (3) A. Thompson, AK (3)

Sergeants-At-Arms	
	R. Gunja, KS S. Milay, ME

Credentials Committee	
Chairman:	J. Silvestro, NJ (3)
Members:	D. Wallace, CO (2) E. Keeley, DE

Nominating Committee	
Chairman:	J. Bartfai, NY ^e
Members:	F. Clem, OH L. DeGrange, MD C. Greene, NM D. Guensler, CA E. Keeley, DE T. Kelly, NJ

Budget Review Committee	
Chairman:	F. Gerk, NM
Members:	C. Fulmer, SC (1) D. Guensler, CA (2) R. Wells, Sensitive Meas. (2) A. Tholen, NIST ^e

Standing Committees

Specifications & Tolerances Committee	
Chairman:	D. Watson, TX (1)
Members:	C. Carroll, MA (4) R. Helmick, AZ (3) J. Jeffries, FL (5) J. Truex, OH (2)
Tech Advisor:	H. Oppermann, NIST

Education, Administration, & Consumer Affairs Committee	
Chairman:	G. W. Diggs, VA (1)
Members:	M. Gray, FL (3) C. Greene, NM (5) R. Kalendkowski, CT (4) S. Malone, NE (2)
Tech Advisor:	J. Koenig, NIST

Laws and Regulations Committee	
Chairman:	S. Colbrook, IL (1)
Members:	B. Bloch, CA (5) F. Clem, OH (4) A. Nelson, CT (3) L. Straub, MD (2)
Tech Advisor:	C. Brickenkamp, NIST

Liaison Committee	
Chairman:	P. Adams, PA (4)
Members:	J. Akey, KS (1) R. Davis, James River Corp. (3) J. McCutcheon, USDA (5) K. Thuner, CA (2)
Tech Advisor:	K. Newell, NIST


Executive Committee and NTEP Board of Governors	
Chairman: ^e	F. Gerk, NM
Chairman-Elect: ^e	N. David Smith, NC
Past-Chairman: ^e	J. Bartfai, NY
Treasurer: ^e	C. Gardner, Jr., NY
One Year:	S. Hindsman, AR D. Stagg, AL
Two Year:	T. Geiler, MA E. Heffron, MI
Three Year:	L. DeGrange, MD K. Simila, OR
President: ^{f,e}	J. Lyons, NIST
Executive Secretary: ^{f,e}	A. Tholen, NIST

Conference Coordinator	
	A. Turner, NIST

Other Elected Officers	
Vice-Chairmen:	R. Andersen, NY L. Barrows, MO C. Fulmer, SC A. Thompson, AK

Appointed Officials	
Chaplain:	M. Cole, GA
Parliamentarian:	K. Simila, OR
Assistant Treasurer:	G. Hanson, CA
OIML Representatives:	
PS 7/RS 5:	R. Helmick, AZ
PS 5D/RS 10:	K. Butcher, MD
PS 7/RS 4:	D. Watson, TX

Weights and Measures Week Subcommittee	
Chairman:	P. Adams, PA



THE WHITE HOUSE

WASHINGTON


May 7, 1990

I am pleased to send my greetings to all those gathered in Washington, D.C., for the 75th Annual Meeting of the National Conference of Weights and Measures.

For three-quarters of a century, the National Conference has played a vital role in our marketplace by protecting the rights of consumers and business owners alike; by establishing uniform standards for retail trade; by promoting fair competition among businesses; and by facilitating trade across state and national borders. Today, the consensus-building approach taken by the regulatory officials and industry representatives participating in this conference is helping to assure an efficient and fair marketplace without excessive restrictions on technology or business operations.

The National Conference of Weights and Measures provides a model of cooperation between Federal, state, and local governments and the private sector. I applaud your efforts to promote equity in trade at both the national and international levels. With more free market systems emerging around the world, your work will continue to grow in importance. You have made significant contributions to the growth of American commerce since your first meeting in 1905, and I look forward to your continued success.

Barbara joins me in congratulating you on your Diamond Anniversary and in sending best wishes for a productive Annual Meeting.

A handwritten signature in dark ink, appearing to read "G. Bush". The signature is fluid and cursive, with a large initial "G" and a stylized "Bush".

General Session

A National Need....Looking to the 21st Century

Dr. John Lyons

Director, National Institute of Standards and Technology

I am very pleased to be here today to participate in celebrating the 75th Annual Meeting of this Conference. On this occasion, it is useful to revisit the origins of the National Institute of Standards and Technology (formerly the National Bureau of Standards) and the National Conference on Weights and Measures to gain important perspectives of the relative changes of our organizations in response to National needs in commerce and industry in the United States in the intervening 85 years. Of course, the evolution of the Conference has been, and remains today, inseparable from the historic changes to the National Institute of Standards and Technology during that same 85 years.

As the United States entered the 20th century, neither the National Institute of Standards and Technology nor the National Conference on Weights and Measures existed.

Quoting from "Measure for Progress, A History of the National Bureau of Standards,"

"A Federal Standards laboratory had been under discussion for almost 20 years before the burst of nationalism at the turn of the century and the surging growth of American industry together conspired to assure its serious consideration. As a result of the Spanish-American War we had, in a few short months, become a world power, intensely proud of the new respect with which the nations of the world now dealt with us. Our foreign and domestic commerce flourished as never before. In the decade before 1900 the export of American manufacturers almost doubled. Only Germany's overseas trade had exceeded this rate of increase in the same period, largely because, as our manufacturing and trade associations pointed out, she was able to guarantee the uniformity and quality of her exported goods."

Fortunately, the U.S. Congress responded to the rapid changes taking place a century ago. One of its responses was the establishment of the National Bureau of Standards (NBS) in 1901. Most of you know that the Office of Standard Weights and Measures, that had been established in 1836, was incorporated into the NBS.

Shortly after the establishment of the NBS, steps were taken to address a national problem that was getting in the way of growth in commerce among the States; this was, in the words of Dr. Stratton, first Director of the NBS, the need

"to bring about uniformity in the State laws referring to weights and measures, and also to effect a close cooperation between the State inspection services and the National Bureau of Standards."

These words are from his letter sent to each State in 1904 in which he invited representatives of the States to meet at the NBS to address this need. The first meeting in response to that letter was in 1905. In 1906, the holding of annual meetings was formalized under the name "The National Conference on Weights and Measures."

This week, we are holding the 75th such annual meeting. We, the National Institute of Standards and Technology (NIST) and the Conference, continue the work started nearly a century ago to ensure the integrity of the U.S. marketplace through foresight and hard work. I understand that you all received a special souvenir reproduction of the proceedings of that first meeting in 1905. Later, after all of the speeches this afternoon, you will see a filming of portions of that first meeting based on those proceedings. That was a truly historic meeting called and chaired by the first Director of the National Bureau of Standards.

As the first Director of the National Institute of Standards and Technology, I want to lay the groundwork for what I hope will be an equally successful future for joint NIST/Conference cooperation.

In the 85 years since that first, historic Annual Meeting, the Office of Weights and Measures (OWM), hand-in-glove with the National Conference on Weights and Measures (NCWM), has continued to support that role of the NBS related to working with the States and business, first in establishing a uniform basis for regulation of the marketplace to all the States, and second, ensuring that the laws, regulations, codes, and standards continue to meet the needs of the marketplace. To say that we, together, have succeeded is a gross understatement. We should be proud of our achievements.

While the OWM and the NCWM continued to address their responsibilities, the National Bureau of Standards was constantly being challenged to serve the Nation's rapidly expanding scientific development. That challenge was described in a letter from the then Secretary of the Treasury Lyman Gage to the Congress in 1900. He stated that:

"The establishment of uniform standards, their maintenance, and the solution of problems connected with them, has until recent years been confined to standards of length, mass, capacity, and temperature; but the increased order of accuracy demanded in scientific and commercial measurements and the exceedingly rapid progress of pure and applied science have increased the scope of such work until it includes many important branches of physical and chemical research."

The National Bureau of Standards has met its many challenges since its creation. In fact, as the world moves toward the dawn of the 21st century, the challenges we are facing are, perhaps, more serious than those faced in 1900. In 1900, the United States was emerging onto the world arena as a strong aggressive trading competitor. Today, we are facing increasing competition from other countries that are emerging as strong aggressive trading competitors.

Again, as it did nearly a century ago, the U.S. Congress has expressed its concern for the economic future of our country. Again, as in 1901, the Congress concluded that the National Bureau of Standards should play a major role in addressing the new challenges. In 1988, the Congress passed the "Omnibus Trade and Competitiveness Act of 1988." Several features of that Bill affect us. Ray Kammer described the nature of the legislation to you last year in Seattle, including the change in our name to the National Institute of Standards and Technology.

He noted that while major concerns were discussed about the competitiveness of the U.S. industry, a healthy science and creativity continue to be U.S. strengths. Our problems are based on the fact that we are not meeting the competition of other nations in translating that science and creativity to products in the marketplace. Our competitors are viewed as introducing new products into commerce faster than we do, and their products are considered to be of higher quality and lower cost. Based on this evaluation of our competitiveness problem, the Omnibus Trade Bill assigns new tasks to the NIST.

We at NIST are responding to the need:

"To modernize and restructure (NIST) to augment its unique ability to enhance the competitiveness of American Industry while maintaining its traditional function as lead National Laboratory for providing the measurements, calibrations, and quality assurance techniques which underpin United States commerce, technological progress, improved product reliability and manufacturing processes, and public safety."

As stated here, I am committed to maintaining our traditional functions which include our support of the States, business and this Conference through the programs of the Office of Weights and Measures, the Force Division, and other NIST research efforts.

In the new NIST role in the enhancement of competitiveness, we:

- must build on our strengths;
- continue our supporting services to the public and the private sectors;
- tie our programs to emerging technologies; and
- put growing emphasis on industrial processing, concurrent engineering, and ever improving quality.

As you can see, NIST has a broad range of new scientific research to address. We want to succeed; we need to succeed. Progress on our part is a major key to the economic health of the United States.

We also must be vigilant and protect the resources needed to keep our traditional work healthy. We intend to work closely with you through the National Conference to ensure that the U.S. marketplace keeps pace with the rapid changes appearing there constantly. We at NIST and you in the weights and measures community cannot sit on our hands, because important segments of the Nation's future are in our hands.

At the end of the 19th Century, our Nation had serious needs. We were given important work to do then. We did succeed.

At the end of this, the 20th Century, our Nation again has serious needs. We again have been given important work to do. We again intend to succeed.

Let us get on with this work, with the expectation that History will record that we also succeeded as did the National Bureau of Standards and the National Conference on Weights and Measures since their creations nearly a hundred years ago.

Thank you.

Chairman's Address

Fred A. Gerk, Chairman
Director, New Mexico Division of Standards & Consumer Services

Thank you Ladies and Gentlemen for being here this week and allowing me to be before you today. I am most pleased that Dr. Lyons is here with us today and is continuing the support for the National Conference on Weights and Measures that we have enjoyed for many years with Dr. Ambler at the helm of the National Institute of Standards and Technology. Dr. Lyons, I want to publicly thank you on behalf of the Conference for appointing Dr. Heffron to the NIST Visiting Committee. We in the Conference feel that his appointment will be of great benefit to the weights and measures community, the state and local businesses, and the government community in general. I think you will find him to be a valuable addition to the committee.

I hope you will take an active role in the conference in years to come and I assure you that you have the support of the NCWM.

I see today as "report card day" for the "Ol' Country Boy from New Mexico." I have found that the job of Chairman can be accomplished in half days, and it doesn't make any difference whether it's the first twelve hours or the last twelve hours. So please, judge me not only on what I did, but on what I didn't do. I am glad to report that when I told you last year, "if all else fails lower your standards," I don't feel we had to lower our standards. If I failed as Chairman, I will assume full responsibility. If I passed your standards as Chairman, many people are responsible. If you look in your conference announcement on the third and fourth pages, which is the organizational chart of the Conference, you will see a list of those people.

The NCWM has become such a dynamic organization, it is approaching perpetual motion status and its current 3,021 members are the driving force.

This year, our 75th Anniversary, was an exciting and fulfilling year for me as Chairman, speaking conservatively, I feel I have visited one on one with over 700 of our members. I have given advice and counsel and, you can be assured, I have received plenty of advice and counsel.

The staff at the Office of Weights and Measures has been enormously helpful and, I might add, very understanding. Carroll Brickenkamp was always ready and willing to pitch in when needed, and has served on many occasions as my personal counselor. Henry Oppermann's expertise and support was there as usual. He is one of the hardest working and brightest young men in the weights and measures profession. Joan Koenig in her usual professional manner was there to help and, I might add, keep my handwriting in order. Her job requires more signatures than a famous movie star! Computer whiz Karl Newell did his thing over and above, as you will see later on during our feature film. Tina Butcher, in her sweet quiet way, has come on like "gangbusters" in her role as advisor to the Task Force on Safety and numerous other duties. Joan Mindte did great all year -- she even scheduled a 7:00 A.M. breakfast in my suite this week and didn't tell me about it. The new kid on the block, Georgia Harris, has already taken the metrologist programs to the forefront and is accomplishing great things. I have to say something good about my two girlfriends in the Office of Weights and Measures, Elizabeth Begosh and Terry Grimes, better known as Trixi. Without question, they do the work and the rest of the OWM staff takes the credit.

I can't say enough about Ann Turner or, as she is sometimes called, "Crash Turner." She took care of every little detail in impeccable fashion and almost kept me on the straight and narrow.

Al Tholen always had a solution for any dilemma I encountered and was very responsive to my thoughts regardless of how "country" they were. He constantly strives to make the NCWM a better organization. His ideas are unlimited. The only fault I find with him is that his normal attire does not go well with "western boots."

I owe a special thanks for all the guidance I received from my very good friend Otto Warnlof. He and Irene have tutored well. Otto has a philosophy that I learned early on in my years on the S & T Committee. Do everything right and, if that's not good enough, do it again -- That's why I served two years as Chairman of that Committee.

I must also mention the outstanding work our metrologists have done this year. They are now formally organized and have become a positive contributory factor to the conference.

Charlie Greene has been my personal shrink for many years and has been extremely helpful this year. His brains and my B.S. have made us known as the "G-men of New Mexico."

My staff at home has been very understanding, and to them I owe much gratitude - without them I wouldn't be here today! Pat Avalos, my head secretary of 17+ years, probably worked harder for the Conference this year than I did.

Last, but not least, a big thank you to my wife Verna; she kept my clothes clean, my bags packed, and my tummy full and was always there to listen and support!

This year's theme of "Progress through Consensus Among Consumers, Regulators and Industry," I feel, became a reality. As your Chairman, I traveled to all of the regional conferences, two meetings of the Scale Manufacturer's Association, a meeting of National Type Evaluation Technical Committee and the Board of Governors, and several meetings of the Retail Grocers Association, and the Petroleum Marketers. Consumers and industry were heavily involved in all of these meetings and played a key role in reaching consensus solutions.

I mentioned attending all four regional conferences. I can truly state that I was thoroughly impressed by each of the regional meetings. They are becoming more and more of a driving force for the National Conference. We still need a little more coordination between the regionals and the National to finalize the proper relationship, but I think the regionals are really moving forward in the right direction. They have convinced me that weights and measures is not only a profession, but has become a way of life! I might mention that on my trip to the Northeastern Conference, I was made a member of the airlines 100,000 mile club, and at the same time my luggage became a member of the 150,000 mile club!

To quote from the famous acceptance speech given by Fred A. Gerk on July 1989, "I didn't campaign for this office; thus, I didn't make any campaign promises." Therefore, I must have fulfilled all my campaign promises.

Seriously, I think the Conference had a great year and is alive and well.

The National Type Evaluation Program received considerable attention this year. For the first time ever, a certificate of conformance was revoked, others have been challenged. Many questions have been raised about how far NTEP goes, what changes need to be made and how NTEP effects weighing in the real world. Some solutions have been reached, others are under study. NTEP is in place and fine tuning has begun. The National Type Evaluation Technical Committee Chaired by John Elengo for the Weighing Industry Sector, Richard Whipple for the Measuring Industry Sector, and Peter Perino for the Belt Conveyor Sector are spending much time and effort in this fine tuning and they are to be commended for their efforts. NCWM Publication 5 that has recently been published, should be a real asset to the field inspector.

Next, the National Training Program has matured. All but one state have now signed up for the program and that one is coming around. Megabucks, namely over \$500,000, have been spent on module development, and 13 modules are currently in place. To date over 582 people have received formal training with these modules. This year we took it a step further and provided funding for regional "Train the Trainer" programs. Just two months ago the Northeastern Weights and Measures Association finalized plans for "train the trainer" courses for their members. They have contracted with the Institute for Weights and Measures to provide this training. This, hopefully, is another step in implementing our training program nationally for the benefit of both industry and regulators. We next have to look at ways of quickly revising the modules to track annual changes made to Handbooks 44 and 130. We are even experimenting with training delivery sponsored by NCWM.

General Session

The Task Force on Safety, formed just one year ago this month, hit the deck "a-running." Under the guidance of the incomparable Charles Gardner, of Suffolk County, New York, much has been accomplished. The Task Force has developed an outstanding library of safety material available to anyone interested. This will be the first comprehensive national effort in the safety arena and I think it will benefit the entire weights and measures community immensely. I strongly urge all weights and measures officials in attendance here today to take a look at the Task Force work and take it home with you and implement it. If we prevent one accident, it will be well worth our effort.

Next, if you look at the Conference announcement and read the committee reports, you will see full agendas for each committee. Much work and effort has gone into the development of each of the committee reports. I urge you to become familiar with each of the issues and vote your conscience the rest of the week.

One of my philosophies throughout my year as Chairman has been to try, during my travels, to take the Conference to the people that do not have the privilege or the resources to attend the Conference. My good friend, and our Chairman-Elect David Smith from North Carolina, and I have hosted a breakfast at each regional for persons that normally do not attend the Conference, the guys and gals in the trenches, so to speak. At these regional breakfasts, we have asked Daryl Tonini of Scale Manufacturers' Association, Dick Whipple of Gasoline Pump Manufacturers' Association, and Mike Belue of American Petroleum Institute to explain the role and functions of their respective organizations and how they interact with the NCWM. This has proven to be very informative and interesting and, as a result, I think the conference is better understood outside the realm of the regular attendees. I would be remiss if I didn't tell you more about your incoming Chairman. Dave and I have worked very closely together this year in representing the Conference. Dave has been a real asset and true ally during my term as Chairman. And as a result of his involvement, I can assure you, he is ready and competent to take over as Chairman later this week. You can rest assured anything I've broken, Dave will fix. Anything I accomplished Dave will make better. I only ask that you give him the enthusiastic support you gave me.

I will conclude with that positive note and bid you "Vaya Con Dios."

Thank You.

Keynote Address

Honorable Tim Valentine (D-NC)
U.S. House of Representatives

Chairman, Subcommittee on Science, Research and Technology

It is an honor for me to appear before your organization, the National Conference on Weights and Measures, on the occasion of your diamond anniversary meeting. Your organization has a prestigious past and much to accomplish in the future. I also wish to compliment you on your farsightedness in choosing David Smith, the Director of North Carolina's Standards Division, as your chairman-elect. David is known in North Carolina as a highly able administrator and as one of our most dedicated public servants. I am sure that your organization will be as well-served by David as we in North Carolina have been.

The National Conference on Weights and Measures is one of our nation's best kept secrets, and I hope it remains that way. You are the reason that American customers get fair measure wherever and whenever we make purchases. When we buy 10 gallons of gasoline or five pounds of roast beef, whether we do it in Alaska or North Carolina, there is never any question that we are getting the volume or the mass we are paying for. You and the professionals you work with have done such a good job of standardizing weights and measures in American commerce that we can take for granted that we are being treated fairly.

The U.S. economy has come a long way in the seventy-five years since the National Conference on Weights and Measures was formed and in the 79 years since the National Bureau of Standards became the U.S.'s first national laboratory. At the turn of the century, the United States had the potential for greatness, but we were not there yet. Our country then stretched from coast to coast, but we were not unified. Not much time had passed since the Civil War, the closing of the frontier, or the establishment of rail service from coast to coast. This was a time of excitement and vision, a time of reformers, a time when there was great interest in building a society where all who would put forth the effort could prosper and enjoy the great natural wealth of our nation.

What more appropriate time could there be to establish a National Bureau of Standards and a National Conference on Weights and Measures to standardize weights and measures within the United States and to provide a forum for accomplishing these goals. These organizations over the last 75 years have complemented our free market system by giving it the accurate measurement framework it needs to exist. In a very real way, the National Bureau of Standards and the National Conference on Weights and Measures have provided the uniformity necessary for the United States to become one big marketplace. You have helped create and preserve a market system that is wide open to good ideas and products by providing the means of assuring that transactions are fair both to buyers and sellers. It was the National Bureau of Standards' support to industry that led the subcommittee I now chair to promote the legislation which transformed NBS into the National Institute of Standards and Technology and expanded its role of promoting the competitiveness of American industry.

The events in Eastern Europe over the past couple years have shown us just how lucky we are that our predecessors chose a free market approach. 1905, when your organization began its work, is not that far from 1917 when communism, the other great economic experiment, began in another emerging country which also spanned a continent. Both systems made great promises regarding the well-being and prosperity of the average citizen. Both promised to make great leaps forward, but only one delivered. Democracy with its free market produced outstanding results because, under the free market system, the good ideas of all could be factored into the rules and standards of the market. Communism lost because it gave only lip service to the people and assumed the government knows best. Seventy-five years after your founding, the East is seeing the light. Our economy is finally viewed as a model by these countries and others around the world which now yearn for free markets and the efficiency that comes from them.

As your organization begins its second 75 years, measurements and standards are as important and newsworthy as they have been in recent memory. We are rapidly moving onto a world stage. More than ever before, the world is becoming one economy, and internationally-accepted measurements are the glue that will hold the world economy together. You are about to face challenges like never before, because traditional U.S. measurements are no longer accepted in the rest of the world, and because U.S. standards are being accepted as de facto world standards less and less. The metric systems of measurement is gaining international acceptance. International standards organizations are gaining new prominence. The European Community and other trading blocks are working towards integrated standards and systems of measurement. The world of measurement will never be the same again.

Some of the changes should be welcomed. Take metric, for instance. This system is inherently simpler and more rational. We are already used to thinking in terms of a width of 35 millimeters for film, a distance of 10 kilometers for a race, and a volume of two liters for Coke. The sooner we can do all our business in metric the better, because not being metric costs the United States dearly in world trade. The Federal Government is in the process of converting to metric over the next 3 years or so, and this change is bound to impact on your work as well.

Others of these changes present a challenge and will require patience and persistence on our part. The European Community's testing and certification procedures have the potential for limiting, at least temporarily, access of some American products to their markets. We are outvoted considerably in the international standards organizations. Other nations are aggressively promoting their standards to third world nations.

I am confident that we are now understanding the challenge we face and, as in the past, we will work to meet the challenge. We must make sure as a nation that any international system of measurement that we subscribe to makes sense, permits U.S. business to do business, and does not jeopardize the public health and safety aspects of our system. We will be challenged, but if we are vigilant and stick to our principles, we will help the world move towards a fairer and more efficient system for doing business worldwide and we will all be much the better for it.

We, of course, have much going for us in this endeavor. We can rely on the fact that our consensus system of establishing standards and our democratic ways of solving measurement issues are both rational and firmly grounded in the realities of the marketplace. We also have many outstanding men and women who, through organizations such as the National Conference on Weights and Measures, have dedicated their careers to making sure that commerce in America can run smoothly.

Therefore, I hope that business and government, at all levels, can continue to work together to meet the challenge. Let's begin now to lay the groundwork so that we have something really big to celebrate in 2015 at the centennial meeting of the National Conference on Weights and Measures.

Honor Awards Presentations

Dr. Donald Johnson, Director of Technology Services, NIST, presented Honor Awards to members of the Conference who, by attending the 75th Annual Meeting this year, reach one of the attendance categories for which recognition is given - attendance at 10, 15, 20, 25, 30, and 35 years.

10 YEARS

Don Stagg, State of Alabama
Thomas Morrow, Tec America
Martin Coile, State of Georgia
Joseph Nagy, City of South Bend, Indiana
Robert Fonger, Bennett Pump Co.
Walter Kupper, Mettler Instrument
Charles Gardner, Suffolk County, NY
Fred Clem, City of Columbus, OH
C. Thomas Picton, Conrail

15 YEARS

Darrell Guensler, State of California
Claude Parent, Consultant
Allan Nelson, State of Connecticut
John Robinson, Association of American Railroads
Austin Rhoads, Northeast Ice Cream Association
Steven Malone, State of Nebraska
Charles Greene, State of New Mexico
John Bartfai, State of New York

20 YEARS

Edwin Hanish, La Porte County, IN

25 YEARS

Eugene Keeley, State of Delaware
Thomas Stabler, Toledo Scale Co.

30 YEARS

James Bird, Retired, State of New Jersey
James Lyles, Retired, State of Virginia

Certificates of Appreciation

Fred Gerk, Conference Chairman, presented Certificates of Appreciation to members of standing committees and annual committees who had completed their tenure on the following committees:

Specifications and Tolerances Committee	David Watson, Fort Worth, Texas
Laws and Regulations Committee	Sidney Colbrook, State of Illinois
Liaison Committee	Peggy Adams, Bucks County, PA James Akey, State of Wisconsin
Education Committee	G. Wes Diggs, State of Virginia
Executive Committee	Sam Hindsman, State of Arkansas Don Stagg, State of Alabama
Budget Review Committee	Carol Fulmer, State of South Carolina
Associate Membership Committee	William Braun, Procter & Gamble Co.
Auditing Committee	Gerald Hanson, San Bernardino County, CA
Resolutions Committee	O. Ray Elliott, State of Oklahoma Sterling McFarlane, City of Seattle, WA Steve McGuire, State of Illinois

President's Award

This special award is a banner presented to the State Director of each state having 100% of its weights and measures officials as members of the National Conference on Weights and Measures for the membership year July 1, 1988 - June 30, 1989.

First Year Awards Banners

State of Iowa
State of Montana
State of Oregon
State of Texas
State of Utah
State of Washington
State of Wyoming

Streamers for Second Year 100% Membership

State of Arizona
State of Hawaii
State of Michigan
State of New Hampshire

Streamers for Third Year 100% Membership

State of New Mexico
State of Vermont

Streamers for Fourth Year 100% Membership

State of Alaska
State of Delaware
State of Idaho
State of Kansas
State of South Dakota

Streamers for Fifth Year 100% Membership

State of Arkansas
State of Nebraska

President's Certificate Award

This award is given to States with 100% of their State office staff as members for the 1989-90 year:

Colorado
Maine
Massachusetts
New York
Indiana
Wisconsin
Virginia

Standing Committee Reports

Report of the Executive Committee

Fred A. Gerik, Chairman
Director, Division of Standards & Consumer Services
New Mexico

100

Introduction

This is the Final Report of the Executive Committee for the 75th Annual Meeting of the National Conference on Weights and Measures (NCWM). The Report is based on the Interim Report offered in the Conference "Program and Committee Reports" (NCWM Publication 16), the Addendum Sheets issued at the Annual Meeting, and actions taken by the membership at the Voting Session.

Items are grouped into two parts: Part I - Executive Committee Business; and Part II - National Type Evaluation Program, Board of Governors' Business. Table A identifies all of the items contained in the Report by Reference Key Number, Item Title, and page number. Table B lists the Appendices to the Report. Table C reports the voting results.

Table A
Reference Key Items and Index

Reference Key No.		Title of Item	Page
PART I - EXECUTIVE COMMITTEE			
101-1	I	Publications, Sale/Distribution	29
101-2	I	Publications, Handbooks 44 and 130	30
101-2A	I	Publish NIST Handbook 130 in Even-Numbered Years	30
101-2B	I	Publish NIST Handbook 44 in Odd-Numbered Years	31
101-3	I	Mailing to Local Jurisdictions	31
101-4	I	Membership, Status Report	31
101-5	V	Membership, Categories	31
101-6	I	Organization, Appointments and Assignments	31
101-7	I	Organization, Role of Metrologists	33
101-8	I	Organization, Canadian Representation	34
101-9	I	Organization, Change Name of NCWM	34
101-10	I	Finances, Treasurer's Report	34
101-11	I	Finances, Expenses of Conference Members	35
101-12	I	Meetings, Annual & Interim, Work Schedule	35
101-13	I	Meetings, Annual, Time of Year	36
101-14	I	Meetings, Annual, President's Award	36
101-15	I	Meeting, Annual, 75th	37
101-16	I	Meeting, Annual, 76th	38
101-17	I	Meeting, Annual, 77th	39
101-18	I	Program, National Training	39
101-19	I	Program, Task Force on Energy Allocation Systems	40
101-20	I	Program, Task Force on Workplace Safety	40
101-21	I	Program, International Organization of Legal Metrology	40
101-22	I	Program, Office of Weights and Measures	40
101-23	I	Program, National Uniformity	40

Table A (Continued)

Reference Key No.		Title of Item	Page
PART II - BOARD OF GOVERNORS			
102-1	I	Publications, Status Report	41
102-2	I	Program, Acceptance by the States	41
102-3	I	Program, Participating Laboratories/Evaluation Report	42
102-4	I	Financial, Funding Resolution of Appeals	44
102-5	I	Financial, NIST Administrative Expenses	45
102-6	I	Financial, Funding Meetings of NTEP Laboratory Representatives	45
102-7	I	Policy, Labeling Requirements	45
102-8	I	Policy, Type Evaluation Criteria for Computers	45
102-9	I	Policy, Load Cell Testing	46
102-10	I	Policy, Belt-Conveyor Scales, Test Procedures	46
102-11	I	Appeals	46

**Table B
Appendices**

Appendix	Title	Reference Key No.	Page
Appendix A	Policy, Weights & Measures Publications	101- 1	47
Appendix B	Proposed Changes to NTEP Administrative Procedures, Technical, Policy, Checklists, and Test Procedures	102- 4	52
Appendix C	Report on OIML to the Interim Meeting	101-21	55
Appendix D	Operating Budget 90/91	101-10	59
Appendix E	Task Force on Safety - Meetings Held During Interim Meetings, January 14-18, 1990	101-20	62
Appendix F	Summary of Questionnaire on Conference Costs and Locations	101-16	69
Appendix G	Treasurer's Interim Report	101-10	73

Order of Presentation

The Report was presented to the membership for voting as follows:

1. A separate vote was taken on the one voting item:
101-5 V Membership Categories
2. A vote was taken on the entire Report with editorial privileges accorded to the Executive Secretary.

Table C
Voting Results

Reference Key No. or Subject	House of State Representatives		House of Delegates		Results
	Yes	No	Yes	No	
101-5	44	0	71	0	Passed
Report in its entirety	44	0	73	0	Passed

Detail of All Items

Part I - Executive Committee

101-1 I Publications, Sale/Distribution

As described in the membership brochure, NCWM members may receive complimentary copies of selected NIST and NCWM publications. Taking account of costs and availability of publications, a formal policy, 1.4.9, "Publications, Weights and Measures, Distribution Policy" has been implemented (See Appendix A).

Members. Members may, at their option, receive a complimentary copy of the latest version of any of the following publications that they need.

COMPLIMENTARY PUBLICATIONS FOR MEMBERS

\$15.00	NIST Handbook 44, Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices, H. V. Oppermann, editor
\$10.00	NIST Handbook 130, Uniform Laws and Regulations, C. S. Brickenkamp, editor
\$16.00	NBS Handbook 133, - Checking the Net Contents of Packaged Goods, C.S. Brickenkamp, S. Hasko, and M.G. Natrella, editors
\$10.00	NIST Special Publication 793, Report of the Conference on Weights and Measures
\$30.00	NCWM Pub 2, Directories of State and Local Weights & Measures Officials and All Members of the NCWM
\$10.00	NCWM Pub 15, Interim Meeting Agenda
\$37.50	NCWM Pub 16, Announcement Book
\$128.50	Cost to non-members for all of the above

Executive Committee

Members may purchase additional copies of the: (1) NIST publications listed above from the Government Printing Office; and (2) NCWM publications from the NCWM at the reduced prices listed in Appendix A.

The notice for renewal for membership in the Spring of 1990 provided a check list for use by members to identify the publications they desire. Many members have forgone requesting one or more publications (e.g., Associate Members who work in the commodity area do not need or use NIST Handbook 44). This is one of the benefits of the new policy that will accomplish two important objectives: (1) provide the documents needed by each member; and (2) avoid distribution of documents that are not needed, thereby helping to control the expenses associated with the printing and distribution of unneeded documents.

Non-Members. Non-members must purchase the documents from the Government Printing Office (GPO), the National Technical Information Service (NTIS), or the National Conference on Weights and Measures (NCWM) at the prices shown above or in Appendix A.

101-2 I Publications, Handbooks 44 and 130

This item was divided into three items prior to the Annual Meeting: (1) Item 101-2, a general discussion of the subject; (2) Item 101-2A, a voting item, that, if adopted, would have resulted in publication of NIST Handbook 130 every other year (in the even-numbered years); and (3) Item 101-2B, a voting item, that, if adopted, would have resulted in publication of NIST Handbook 44 every other year (in the odd-numbered years). The Executive Committee changed items 101-2A and 101-2B from voting to informational items prior to the Annual Meeting based on the conclusion that the pros and cons were not yet adequately understood by the membership. The impact of the proposed changes to the current procedures of the Standing Committees needs to be analyzed further.

Publication of NIST Handbooks 44 and 130 every 2 years (instead of annually) was proposed to provide the following benefits:

1. the States would have 2 years to adopt the changes and train their staffs;
2. the Regional and State Associations would have 2 years to address issues more thoroughly;
3. the industry would have more time to make product and marketing changes;
4. the training modules would go to a 2-year updating cycle; and
5. the OWM would reduce its publishing budget and redirect staff effort towards updating the modules.

An annual publishing cycle imposes demands on the membership and the NIST that seriously strain the system. Changes to the handbooks directly require that the training modules be updated (for example, seven modules must be updated whenever general requirements in the Scales Code change). This in turn leads to the need to publish updated training modules annually, as well as ensure that all instructors are conversant with the changes. Printing costs are escalating, overly taxing the OWM publishing budget and the NCWM budget for updating training modules.

Many States do not adopt the changes to the handbooks annually; it is impossible to update annually those officials who have taken the training modules; and almost all changes adopted by the NCWM could readily be delayed for 1 year.

101-2A I Publish NIST Handbook 130 in Even-Numbered Years

If this item had remained a voting item and were to have been adopted, NIST Handbook 130 would have been published following the 75th Annual Meeting (1990 Edition) and republished every second year thereafter instead of annually. The next edition would have been published following the 77th Annual Meeting (1992 Edition).

101-2B I Publish NIST Handbook 44 in Odd-Numbered Years

If this item had remained a voting item and were to have had been adopted, NIST Handbook 44 would have been published following the 76th Annual Meeting (1991 Edition) and republished every second year thereafter instead of annually. The next edition would have been published following the 78th Annual Meeting (1993 Edition).

101-3 I Mailing to Local Jurisdictions

This item was printed as a voting item in the agenda for the Annual Meeting. Prior to the Annual Meeting, the OWM reworked the NCWM mailing list to accomplish the aims described in the proposal. It was therefore changed to an Informational Item.

The Northeastern Weights and Measures Association requested the Executive Committee to add major local jurisdictions to the Director's mailing list. They stated that: (1) many county and city jurisdictions have more equipment, personnel, problems, programs, and population than some States; (2) that these jurisdictions need to receive the informational reports, questionnaires, surveys, and decisions that the NCWM mails to State directors; and, (3) that many States do not automatically send this information to their local jurisdictions.

101-4 I Membership, Status Report

The membership of the NCWM at the end of June, 1990 was 2983, nearly 120% growth in the past two years. This large increase resulted from an intensive mailing campaign to potential members identified by the States and the OWM. Even with this increase, less than half of the weights and measures officials in the country are members; a far smaller percentage of potential private sector representation are members.

The directors of State and local jurisdictions are requested to: (1) work toward 100% membership of all officials in their jurisdictions, and (2) provide to the Executive Secretary the identity of potential private sector members (i.e., lists of licensees, sales and service employees, etc.). Associate members are requested to provide similar identification of their associates and organizations.

101-5 V Membership, Categories

(This item was adopted.)

Recommendation: Reclassify State and local government members (other than active weights and measures officials) and foreign government members from Associate to Advisory members by changing Article III of the Constitution to read as follows:

ADVISORY MEMBERSHIP. - Advisory membership is open to (1) representatives of agencies of the Federal Government ~~who are concerned in any way with regulatory weights and measures officers or their official activities or who are interested in the objectives and activities of the Conference;~~ (2) representatives of State and local governments other than weights and measures officials, (3) foreign government members, and (4) persons who have retired from Federal, State, county, or city weights and measures employment who are concerned in any way with regulatory weights and measures officers or their official activities or who are interested in the objectives and activities of the Conference.

Discussion. The use of the NCWM mailing list suggested the need to change the classification of some State and local members, such as State police and department of agriculture employees other than weights and measures officials, from Associate to Advisory members. This reserves the Associate membership classification for business, industry, and consumer members and simplifies the decisions regarding mailing of materials of interest to each classification of membership.

101-6 I Organization, Appointments and Assignments

In the original Committee report, Chairman Gerk announced the following appointments.

Parliamentarian: Clayton F. Davis, State of Maine

Executive Committee

Task Force on Safety: Charles Gardner, Jr., Chairman

L. F. Eason, North Carolina
Jean Johnson, American Petroleum Institute

James D. Harnett, California
Donald Soberg, Wisconsin

Technical Committee on National Type Evaluation: John Elengo, Jr., Chairman

Public Members:	R. Andersen, NY D. Guensler, CA H. Oppermann, NIST K. Yee, NIST	T. Butcher, NIST J. Lacy, USDA/P&S J. Truex, OH	C. Conrad, Jr., NJ D. Mahoney, USDA/FGIS O. Warnlof, NIST
-----------------	--	---	---

Belt Conveyor Sector: P. Perino, Revere Transducers, Inc., Chairman

Public Members:	F. Gerk, NM J. Rabb, AL	R. Helmick, AZ R. Miller, CO	H. Oppermann, NIST O. Warnlof, NIST
-----------------	----------------------------	---------------------------------	--

Private Sector:	J. Berger, Technetics Industries M. Casanova, Ramsey Technology, Inc. R. Desollar, Central IL Public Service J. Giannina, Port of Corpus Christi T. Johnson, Sensortronics K. Knapp, Milltronics J. MacFarlane, Auto Weight Co. J. Robinson, Assoc. of American RRs W. Thurman, Southern Co. Services, Inc. C. Toombs, Stock Equipment Corp.	G. Burger, Consultant D. Cockrell, Weighing & Control Systems, Inc. S. Gibson, ABC Scale N. Johnson, Merrick Corp. G. Kachel, Riede Systems, Inc. F. Joe Loyd, CSX Transportation N. Ortyl, III, Dresser Industries J. Oliver, Virginia Power D. Tonini, Scale Manufacturers Assoc.
-----------------	---	---

Weighing Industry Sector: J. Elengo, Jr., Revere Transducers, Inc., Chairman

M. Adams, Fairbanks Scales J. Giannina, Port of Corpus Christi K. Haker, BLH Electronics J. MacDonald, Howe Richardson W. Paull, Hobart Corp. T. Stabler, Toledo Scale Corp. T. Johnson, Sensortronics	J. Antkowiak, Hottinger Baldwin Measurements W. Goodpaster, Cardinal Scale Co. H. Lockery, Lockery Assoc. R. McCarty, NCR Corp. J. Robinson, Assoc. of American Railroads D. Tonini, Scale Manufacturers Assoc.
--	--

Measuring Industry Sector: R. Whipple, Gilbarco, Inc., Chairman

F. M. Belue, Belue Associates M. Hankel, Liquid Controls R. McCarty, NCR Corp. L. Murray, Dresser Industries, Inc. J. Skuce, Smith Meter, Inc. R. Tucker, Tokheim Corp.	R. Fonger, Bennett Pump J. Harshman, Daniel Flow Products, Inc. T. McDonald, Mobil Oil Corp. R. Shields, Southwest Pump D. Smith, William M. Wilson's Sons
--	--

At the Annual Meeting, Chairman Gerk announced the following additional appointments:

Acting Parliamentarian: Mr. Ken Simila, OR appointed for the 75th Annual Meeting, substituting for Mr. Clayton Davis, ME who could not attend the meeting because of personal reasons.

Acting Chaplain: Mr. Martin Coile, GA appointed for the 75th Annual Meeting, substituting for Mr. Cordell Robinson, who did not attend the meeting.

Task Force on Safety: Mr. Hap Thompson, API appointed to replace Ms. Jean Johnson, API based on reassignments of responsibilities within API.

101-7 I Organization, Role of Metrologists

At the Interim and Annual Meetings, Ross Andersen, NY reported on the progress made by the metrologists at the 74th Annual Meeting and on present and future activities as follows.

The metrologists have tried to make better use of the Metrology Workshop time at the Conference by structuring their activities and using a steering committee to guide their work in relation to the NCWM, the NIST Office of Weights and Measures, and the Regional Measurement Assurance Programs (RMAs).

The Steering Committee is made up of one representative from each of the five RMAs. The Chairmanship of this Committee will rotate through the Regionals. The Committee will report to the Executive Committee and work closely with Georgia Harris, the OWM staff member in charge of the State Standards Program.

The metrologists are working toward changing their primary objective for the Workshops from training to a combination of training and planning, coordination and completion of projects in the following areas:

1. Plan Metrology Workshops - Work with OWM staff and the Executive Committee to plan the agenda for the workshops.
2. Liaison with the NCWM - Work with the committees and task forces to provide information and assistance where their expertise is beneficial.
3. Liaison with OWM - Work with OWM staff to improve the State Standards Program, particularly in the areas of metrologist training, the LAP program and laboratory certification, and review and revision of NIST handbooks used by metrologists (e.g., Handbooks 145, the 105 series, etc.) to keep them current with today's technology.
4. Coordination of RMMP Activities - Work with the RMMPs, much as the NCWM does with the regional associations, to resolve technical issues, share knowledge and experience and encourage interaction among metrologists.
5. Other Projects - Cover appropriate topics not included above.

The metrologists will identify needs and select a few priority projects for work each year. For 1989-90 the projects included:

1. Review of Handbook 105-3 on Metal Volumetric Field Standards. This handbook covers specifications and tolerances for test measures and provers used in the enforcement of Handbook 44. This handbook is out of date and in need of revision. All five of the RMMPs reviewed the document in 1989 at the regional meetings. The OWM compiled the comments and has sent them to API and industry representatives for additional comment prior to preparing a draft revision.
2. Jim Clifford, metrologist (OR), has prepared a draft of a new handbook in the 105 series to cover specifications and tolerances for LPG provers. The draft has been reviewed by a group of metrologists and a third draft has been submitted to the OWM and circulated to State directors, metrologists, API, and industry for review.
3. The metrologists are working to validate computer software developed in the metrology laboratories. Because of the wide variability in computer hardware and software, a decision was made to define standard data sets so that metrologists can readily verify their own programs. A draft Quality Assurance Program was developed for computer systems and software, and initial data sets for air density calculations were presented at the Annual Meeting by Georgia Harris.
4. A narrative procedure for testing large capacity platform scales is being drafted for review by the S&T Committee. It parallels Handbook 94 and reflects the recent changes regarding nominal and concentrated load capacities and test patterns. This draft, written by Ross Andersen, was presented to the S&T Committee before the 75th Annual Meeting.

5. The metrologists are working with the Education Committee to assist in the development of a new training module on weights and measures administration (Module 23). An outline covering the laboratory and its role in weights and measures enforcement was provided to the Education Committee. The writing of the metrology section is an ongoing project and Ross Andersen, metrologist (NY), has volunteered to write the first draft for review by the regional representatives and OWM.
6. L.F. Eason, metrologist (NC), was appointed to the Safety Task Force in 1989. He has assisted in collecting and organizing safety material from many sources including material from the metrologists. This is an ongoing project.

101-8 I Organization, Canadian Representation

Three representatives of the Canadian Government attended and participated in the Annual Meeting: Mr. Robert Bruce, Mr. Renald Marceau, and Mr. Gilles Vinet.

Senior representatives of the Canadian Weights and Measures Office have been members of the NCWM for several years. The NIST Office of Weights and Measures, has recently been working with its Canadian counterparts to harmonize legal requirements. More recently, OWM staff have attended meetings of the Canadians as their guests to: (1) gain understanding of the Canadian program and (2) contribute technically and administratively to the Canadian program. In October and November of 1989, Canadian representatives attended meetings of the NTEP Technical Committee and the Committee on Specifications and Tolerances. Two Canadian representatives attended the Interim Meeting in January, 1990 and worked with the Committee on Specifications and Tolerances and the Committee on Laws and Regulations. The Executive Committee complimented the OWM for arranging this cooperative effort and endorsed the continuing coordination between the two countries.

101-9 I Organization, Change Name of NCWM

Mr. Louis Sokol, NCWM member and metrication consultant, advocated changing the name of the Conference because the use of the term "weights and measures" is an anachronism and should be replaced. Of special significance is the misuse of the term "weight." Mr. Sokol reminded the Committee that "weight" is gravity force and use of the word "weight" instead of "mass" is scientifically and technically incorrect. He pointed out that many alternatives to the current name of the Conference are available, and that the name of the National Bureau of Standards has been changed to the National Institute of Standards and Technology without any apparent negative consequences. In more specific terms, Mr. Sokol provided a copy of NIST HB 44 which he had marked up to provide consistency and accuracy. The Committee expressed its appreciation to Mr. Sokol for the hard work and time spent to edit the handbook; they also expressed their understanding of his advocacy for changing the name of the Conference.

The Executive Committee discussed Mr. Sokol's recommendation and decided not to change the name of the Conference. They concluded that the current name has too much intrinsic importance and value derived from 85 years of exposure nationally and internationally to change now, especially with all of the changes occurring at NIST and the U.S. Department of Commerce. The current name also enjoys high visibility among the States and the National Association of State Departments of Agriculture.

101-10 I Finances, Treasurer's Report

The Treasurer reported on the end-of-year status of the budget. (See separate Treasurer's Report for details.) Primarily as a result of the growth in membership, (1) actual receipts exceeded budgeted receipts by \$ 36,000; (2) actual disbursements exceeded budgeted disbursements by \$ 22,000. Net assets therefore increased by approximately \$ 14,000 over the previous year-end balance.

The Treasurer and the Executive Secretary emphasized the growing resources of the NCWM resulting from the greatly increased membership. The proposed budget for FY 90-91 is \$158,000, a significant increase from the \$113,000 for FY 89-90. The income from membership fees is projected to rise from \$67,550 (FY 89-90) to \$92,500 (FY 90-91). A \$15,000 reimbursable item reflects the anticipated income from the processing of NTEP appeals: this item is offset by a budget expense of \$15,000 to cover the anticipated cost of processing appeals.

At the Interim Meeting, after making a few changes, the Executive Committee adopted the budget. (See Appendix D.) At the Annual Meeting, the Executive Committee authorized the Executive Secretary to purchase another Certificate of Deposit after all expenses of the Annual Meeting have been paid, requesting that the purchase and renewal of Certificates of Deposits be planned so that the maturity dates will be spread out during the year.

101-11 I Finances, Expenses of Conference Members

Over the past 10 years an informal policy has been followed to reimburse members for expenses incurred when on travel for the conduct of NCWM business. As the activity of the NCWM has grown, this expense continues to increase and now accounts for a large portion of the operating budget.

The Executive Committee established a subcommittee to draft a policy for reimbursing of members' expenses when they are on Conference business. The Executive Committee suggested guidelines for the subcommittee:

1. Travel qualifying for reimbursement should be held to the minimum consistent with the requirements of the business to be transacted.
2. The need for travel should be established only after alternative means for accomplishing the business (e.g., telephone, FAX) has been deemed inadequate.
3. The NCWM should be the reimbursor of last resort (i.e., after it has been determined that the member's organization can not reimburse the individual fully or partially).

The policy should include the following topics: (1) what travel is authorized; (2) who has the authority to approve travel; (3) what expenses are reimbursable under what conditions; (4) specific allowances, such as per diem, hotel costs, transportation, advances, etc.; (4) and procedures for claiming and processing reimbursement.

The subcommittee was asked to evaluate related issues that affect the costs to the NCWM for travel, such as:

- To what extent are the increasing costs due to the inability of jurisdictions to pay these expenses?
- Should only the active members be reimbursed?
- Can more of the committee business be conducted by phone/FAX/mail ballot as is done by many standards bodies (e.g., ASTM, ANSI)?
- Should candidates for committee assignments determine the willingness of their jurisdictions to reimburse them for travel expenses before accepting assignment?
- Should consideration be given to combining the Annual and Interim Meetings into a once-a-year occasion if enough jurisdictions are able to fund attendance at only one NCWM meeting per year?

The Chairman appointed the following members to the subcommittee: Ken Simila, OR, Chairman; Ed Heffron, MI; Tom Geiler, MA. The Subcommittee has developed a first draft document which will be refined and presented for consideration by the Executive Committee at the Interim Meeting in January 1991.

101-12 I Meetings, Annual & Interim, Work Schedule

Length of Meeting. Some members are concerned about the expenses associated with attending the Annual Meeting. The NCWM is incurring increasing costs for the reimbursement of members attending the Interim Meeting. Shortening each meeting by one day would save money for members, their jurisdictions, and the NCWM.

Days of Meeting. Increasingly, more members arrive on Saturday to get better air fares. Committees meet on Sunday to review/organize agendas. Members formerly arrived on Sunday and Monday was the first full work day. For the past several years, the Conference has officially ended on Thursday morning, followed by the "outing" and committee planning sessions on Friday morning. However, the attendance at the Friday meetings has been steadily dropping.

Executive Committee

It was suggested that the Annual Meeting could be rescheduled by making Sunday a full day (agenda review in the morning and sessions in the afternoon), thus saving at least a half day. All voting sessions could be held on Wednesday (since a half day was gained on Sunday), and the Conference work could be completed by close of business on Wednesday, eliminating the need for meetings on Friday. The Meeting would be 4 full days (arrival Saturday, work days Sunday through Wednesday, departure Thursday) instead of stretching nearly 7 days, from Saturday (arrival of many) through Friday noon (for committee members). A similar plan was proposed for the Interim Meeting.

The Executive Committee decided to continue the currently followed schedule for the Interim and Annual Meetings. The consensus is that the present format and schedule has worked extremely well and that individual members are free to adjust their attendance to meet their personal agendas.

101-13 I Meetings, Annual, Time of Year

The most intensive work period of the year for the staff of the OWM is the month following the Annual Meeting. There are only 5 weeks (end of Annual Meeting in July until September 1) to make all of the changes in NIST handbooks and complete the Proceedings in order for these publications to be printed and distributed prior to January 1 of the year in which the Handbook requirements become effective. Holding the Annual Meeting one month earlier would provide four additional weeks to get this work done.

The Executive Committee decided to continue to hold the Annual Meeting in July for the following reasons:

- The January/July meeting weeks are well known and accepted by the membership in general; changing would add a measure of confusion;
- Moving the Annual meeting into June or earlier would (1) result in having two Annual Meetings in the same year (in the first year of change); (2) interfere with school graduation ceremonies; and (3) adversely affect the ability of guests to attend.

101-14 I Meetings, Annual, President's Award

The President's Award was established by NIST and announced at the 71st Annual Meeting (See Proceedings, 71st Annual Meeting.) Two levels of recognition were included in the award:

- *1. Banner. The top award will be a banner presented to any State in which all of the weights and measures officials (State and local jurisdictions) are members of the Conference. The banner will be accompanied with a certificate for a State to post in the office. The banner will be brought to the Annual Meeting each year to be displayed at the front of the general session room. A ribbon will be added each succeeding year that a State qualifies for this award.
2. Certificate. A certificate will be presented to any State in which all of the weights and measures officials on the State staff are members of the Conference. That State will become eligible for award of a banner when all of the members of its local jurisdictions become Conference members."

It has been stated that it is difficult for States with multiple jurisdictions, (such as California, Massachusetts, New York, and Pennsylvania,) to win this award, thereby diminishing the significance of the award. The Northeastern Weights and Measures Association recommended, for those states having both State and local jurisdictions, that a banner be presented if (a) all of the State staff and (b) at least one of the staff of every local jurisdiction are members.

NIST Position

1. NIST opposes this recommendation; the NIST goal was, and continues to be, 100% membership in the NCWM of EVERY weights and measures official in the United States. NIST does not wish to back off from that goal.

2. NIST believes that each State Director should be committed to 100% membership in the NCWM of every weights and measures official in his/her State, just as the NIST Director is committed to 100% membership of all weights and measures officials in the United States.

Qualifying for the Award is a lofty goal, but one on which we should set our sights. To the extent membership is expanded, the effectiveness of State programs will be increased. Uniformity will spread, and equity will benefit because EVERY official will get the same information in a timely manner and will feel that he/she is "a part of the action."

The Facts.

The Award is achieving the intended goals!

Twenty States will have qualified for banner awards for the July 1, 1989 through June 30, 1990 membership year. They are: Alaska, Arizona, Arkansas, Delaware, Hawaii, Idaho, Iowa, Kansas, Michigan, Montana, Nebraska, New Hampshire, New Mexico, Oregon, South Dakota, Texas, Utah, Vermont, Washington, and Wyoming

In addition, the first certificate awards will be presented for 100% membership of the State office this year to Colorado, Indiana, Maine, Massachusetts, New York, Virginia, and Wisconsin.

This means that 27 States are eligible for one of the two levels of the President's Award for the 1989-90 membership year. This is extraordinary in the days of tight budgets for government programs across the Nation, and in only 5 years since the introduction of the President's Award!

NIST believes that changing the President's Award sends the wrong message to State and local officials alike. It implies that it is not as important for local officials to become members of the NCWM as for State employees. Yet, the message from Chairman Gerk is that there is a need for all weights and measures officials to become members. The proposal may also imply that it is not the responsibility for the State office to sell the need for membership in the NCWM.

NCWM data base records indicate:

- 54 out of 55 State directors are NCWM members;
- only 49% of State weights and measures officials are members;
- only 35% of county weights and measures officials are members; and
- only 38% of city officials are members.

101-15 I Meeting, Annual, 75th

The 75th Anniversary Meeting of the National Conference on Weights and Measures was held at the J. W. Marriott Hotel, Washington, DC July 8 - 13, 1990. The meeting included a special celebration of the first weights and measures meeting held at the Bureau of Standards on January 16 and 17, 1905. A videotaped re-enactment of that first meeting (produced by the Liaison Committee) was played at the Opening General Session on Tuesday. A souvenir edition of the proceedings of the first conference was given to each delegate.

A total of 318 delegates were in attendance and 123 guests. There were 45 States represented, plus American Samoa and Puerto Rico. Not present were the District of Columbia, Guam, Montana, Nevada, New Hampshire, North Dakota, Rhode Island, Virgin Islands and West Virginia. Delegates from Belgium and Canada also attended.

This year, seven States received first year banners for 100% membership of their State and local weights and measures officials in the NCWM. This brings the total to 20 States that have 100% membership in the NCWM.

The "President's Certificate Award" was presented this year for the first time to seven States with 100% of their state office staff as members for the 1989-90 conference year.

Executive Committee

Chairman Gerk Says "Vaya con Dios"

In his address to the Conference, Chairman Gerk reflected on his year as chairman. He reported that "the job of Chairman can be accomplished in half days and it doesn't make any difference whether it's the first twelve hours or the last twelve hours." He said that the 75th anniversary year was exciting and fulfilling. During his year, the membership reached new heights - now exceeding 3,000. He asked that the members give Dave Smith the same enthusiastic support that he received, then bid the audience "Vaya con Dios." To Fred we say "muchas gracias" for a great job as Chairman.

76th Theme: Weights and Measures for the 21st Century

Chairman Smith has chosen "Weights and Measures for the 21st Century" as this year's theme. He also announced his appointments. (See Smith's address for details.)

Chairman Smith asked Darrell Guensler of California to chair a task force of wild-eyed dreamers. Their goal is to rock the boat and not be satisfied with the status quo, but to envision the future. Joining Darrell in this assignment are Bruce Martell of Vermont, Tom Geiler of the Town of Barnstable, MA, Chip Kloos of Beatrice/Hunt Wesson Foods, Inc., and a yet to be named representative from the Department of Commerce.

At the conclusion of a meeting, the usual ending is "sine die." Chairman Smith, with his North Carolina southern hospitality, preferred to end this meeting with "Y'all come back!"

101-16 I Meeting, Annual, 76th

The 76th Annual Meeting will be held in Philadelphia at the Four Seasons Hotel. Room rates are \$90.00 single, and \$115.00 double. It is appropriate to hold the 76th Annual Meeting in Philadelphia, the birthplace of the Declaration of Independence and the Constitution. The 76th can be linked with 1776, and the fact of Constitutional recognition of weights and measures will provide the basis for a very special meeting. Planning includes inviting participation of the ASTM whose offices are across the street from the hotel.

Albany, New York, Original Choice

Albany, NY had originally been selected by the Executive Committee as the location for the 76th Annual Meeting. As previously reported by the Committee, the Executive Secretary encountered difficulties in finding a hotel that combined the quality, sleeping rooms, and meeting space needed for the meeting. In terms of quality, the Marriott near the Albany airport was the best. However, the Marriott was not willing to block the sleeping rooms required; additionally, it lacked adequate meeting room facilities. The Executive Secretary began exploring alternative cities. Later, the Marriott announced plans to expand both its meeting space and the number of sleeping rooms.

Individual Conference members voiced dissatisfaction with Albany for the Annual Meeting. Other comments were made regarding the increasing costs associated with the Annual Meeting, especially room rates. The Executive Committee instructed the Executive Secretary to develop a questionnaire for completion by those attending the Tuesday General Session of the 74th Annual Meeting to "solicit opinions about site selection and costs related to attendance at the Annual Meetings." The questionnaire was developed and distributed to the membership at the General Session. The change of the meeting site from Albany to Philadelphia and the results of the membership questionnaire on meeting planning were reviewed. Mr. Bartfai requested that the results of the Survey be published in the proceedings of the 75th Annual Meeting. The Executive Committee concurred with Mr. Bartfai's request. A copy of the summary of the results is contained in Appendix F.

Question 6 asked the members to rate thirteen "possible" locations for future meetings on a scale of 1 to 5. The results, extracted below, quite conclusively confirmed the comments that had been made regarding Albany.

The following cities are being considered for the Annual Meeting. On a scale of 1 to 5, where 1 = avoid and 5 = excellent choice, rate the following possible locations for future meetings. (For purposes of the ranking reported below, the scorers gave the following values to the 1 through 5 ratings; 1 = -10 points, 2 = -5 points, 3 = +5 points, 4 = +10 points, 5 = +15 points).

New Orleans, Louisiana	1580 points	Indianapolis, Indiana	910 points
Orlando, Florida	1540 points	Chicago, Illinois	675 points
Phoenix, Arizona	1525 points	Kansas City, Missouri	620 points
Nashville, Tennessee	1510 points	Hartford, Connecticut	595 points
District of Columbia	1320 points	Columbus, Ohio	350 points
Philadelphia, PA	1295 points	Albany, New York	- 24 points
Hawaii (non specific)	1020 points		

Based on the results of the questionnaire and the general comments received, the Executive Committee decided: (1) against Albany, directing the Executive Secretary to proceed with Philadelphia, PA as the site for the 76th Annual Meeting; (2) to explore the possibilities of holding the January 1990 Interim Meetings in Phoenix, AZ; and (3) to continue efforts to hold the 77th Annual Meeting in Nashville.

101-17 I Meeting, Annual, 77th

The tentative plan for the 77th Annual Meeting was to hold a joint meeting of the National Conference on Weights and Measures and the International Society of Weighing and Measuring (ISWM).

The Opryland Hotel in Nashville, Tennessee, was selected as the location of the 77th Annual Meeting. The ISWM signed a contract with the Opryland Hotel at rates that were unacceptably high for the NCWM. The two organizations agreed to drop the plans for a joint meeting. Subsequently, the ISWM made arrangements with the Opryland Hotel to reschedule its 1992 meeting to May, its normal month.

The Executive Committee restated its desire to hold the 1992 meeting in Nashville, and requested the Executive Secretary to explore the possibilities of negotiating acceptable rates with a Nashville hotel.

101-18 I Program, National Training

Wes Diggs, Chairman of the Committee on Education, Administration, and Consumer Affairs reported on the work and program of the Committee in a joint session with the Executive Committee. He reviewed the status of many of the items contained in their report. (See report of the Committee on Education, Administration, and Consumer Affairs.) The joint session focused on the development and revisions of the Modules. Regarding module revisions, the current activities were reviewed. (See Table D of the Education Committee's report.) Wes Diggs emphasized the need to keep the existing modules as current as possible and offered the assistance of the Education Committee in that objective.

Chairman Gerk reported that he had written letters to the four states that had not signed an agreement to participate in the National Training Program. Three have responded by signing agreements; only Rhode Island has not signed up. [Editor's Note: On August 7, 1990, Rhode Island signed a letter of agreement.]

The Executive Committee provided \$10,000 for the Education Committee to use to establish "train-the-trainer" programs in each regional area. The Northeastern Weights and Measures Association has recommended approval of an Institute of Weights and Measures proposal to conduct two training sessions funded under this allocation. The other Regionals are making plans for the establishment of training sessions.

The Executive Committee expressed its collective appreciation to the Education Committee for its continuing hard work, dedication, and notable achievements.

101-19 I Program, Task Force on Energy Allocation Systems

The wrap-up work of this Task Force was reported to the Committee at the Interim Meeting by Mr. Pat Nichols, CA, Chairman of the Task Force. The work of the Task Force has been completed, and the Committee on Liaison is going forward with the assignments made to them by the Executive Committee. See the Report of the Committee on Liaison for follow-up work to the Task Force.

101-20 I Program, Task Force on Workplace Safety

Mr. Charles Gardner, NY, Chairman of the newly established Task Force on Workplace Safety reported on the work plan of the Task Force. The Task Force has established a very ambitious plan. The Executive Committee was impressed with the accomplishments to date in defining the goals of the Task Force and emphasized its belief that safety is an issue of importance to every field inspector and laboratory metrologist in the country. (See Appendix E for detailed Report.)

101-21 I Program, International Organization of Legal Metrology

Sam Chappell, NIST, updated the Committee on the activities of OIML. He highlighted planned and anticipated activities during the next calendar year. (See Appendix C for the detailed report.) The next year will be a very busy one for OIML as it works toward special accomplishments in order to meet the needs of the European Community under the EC92 timetable.

101-22 I Program, Office of Weights and Measures

NIST Update. At the Interim Meeting, Dave Edgerly, Deputy Director of Technology Services, described reorganization activities at NIST, highlighting the change in the organizational positioning of OWM. He emphasized that OWM would not be affected in any negative manner as a result of the realignment. Dave also announced that NIST had awarded an additional \$60,000 add-on to the Grant to the NCWM. This is the third and last \$60,000 increment of the commitment made by Dr. Ambler.

OWM Update. Al Tholen, Chief of the Office of Weights and Measures, updated the Executive Committee on the status of the OWM Program, including the recent changes in staffing resulting from the retirement of Paul Krupenie and Dick Smith. OWM recruited Georgia Harris, the Minnesota State metrologist, to fill the Krupenie vacancy. The vacancy created by the retirement of Mr. Richard Smith has not been filled. A decision in this regard will not be made until the beginning of the next fiscal year (October, 1990). The NIST is meanwhile planning to upgrade the OWM computer system network to increase its overall efficiency and versatility.

The Executive Committee considers it urgent to fill the Smith vacancy as soon as possible. A reduction in the training program has already become evident.

Visiting Committee. Dr. Heffron reported on his participation on the NIST Visiting Committee. He expressed his appreciation for the support of the NCWM in gaining his appointment to the Committee. He said that he was very impressed with the other members of the Committee and their seriousness to make the Committee effective. He also concluded that the constituency of the NCWM is considered important to the Committee and that his participation will be active.

101-23 I Program, National Uniformity

Results of a recent questionnaire on the adoption of Handbook 44 and the NTEP Regulation reflected the fact that Handbook 44 has not been uniformly adopted by the States. Further review of the information in Handbook 130 provides evidence that much remains to be done regarding state adoption of the uniform laws and regulations recommended by the conference.

During the discussion of the results obtained from the questionnaire, several points were made, including one that the answers to the questionnaire do not necessarily report reality because the system in each State is often complicated and, consequently, that direct parallels cannot be drawn to the Uniform Laws and Regulations. It was the consensus

of the Executive Committee that a State-by-State examination would lead to the conclusion that there is a far larger degree of uniformity than indicated by the table in NIST HB 130.

A recommendation was made that OWM identify those states that seem to be lagging in adopting the results of NCWM voting; determine whether these States are, in fact, lagging; and identify available options to assist these States in updating their statutes.

Part II - NTEP Board of Governors

102-1 I Publications, Status Report

NCWM Publication 14 "NTEP - Administrative Procedures, Technical Policy, Checklist, and Test Procedures." NTEP laboratories, State offices, and industry must have the latest NTEP policies, decisions, test criteria and procedures. OWM has updated this publication to include the changes reported at the 74th Annual Meeting. The OWM will continue to update Publication #14 annually following the Annual Meeting. Reports of decisions by the Board of Governors between Annual Meetings will be mailed to interested parties as they are completed.

NCWM Publication 5 "NTEP Index of Evaluations." Since NTEP became operational, NBS Reports of Test and NTEP Certificates of Conformance (CofC) issued have been compiled in several documents (NCWM Publication 5 plus separate annual supplements). Since a single integrated report was needed by the States and industry, OWM updated NCWM Pub 5 to include records of all NBS Reports of Test and Certificates of Conformance issued through the end of December, 1989. Quarterly updates will be provided on the WAMIS Bulletin Board and by FAX to State Directors beginning October 1, 1990.

The updated Publication #5 has been published and is being distributed: it is available in 8 1/2" by 11" format, 4" by 5 1/2" (pocket) format, and on floppy disk (if customer provides one high density formatted disk or three low density formatted disks).

102-2 I Program, Acceptance by the States

The Board of Governors strongly urges that: (1) all states adopt the Uniform Regulation for National Type Evaluation; (2) all field inspectors be trained to enforce the code in the latest edition of Handbook 44; and (3) field inspectors routinely verify that all inspected devices have been issued a CofC.

Position of Board of Governors. The Board of Governors is very concerned about the reported lack of uniformity among the States in the enforcement of Handbook 44 and use of NTEP Certificates of Conformance as evidence that the devices under inspection meet the performance requirements under temperature variation. It was noted that no States other than those with NTEP laboratories have the capability to determine conformance of devices with temperature requirements.

Survey Results. In response to earlier reports of the industry, the Board of Governors requested that a survey "Questionnaire on Device Regulation" be sent to the fifty States, the District of Columbia, Puerto Rico, and the Virgin Islands on July 27, 1988. (Copies of the Survey results are available from the OWM.) The survey was conducted to determine: (1) the latest version of NIST Handbook 44 adopted by each State and (2) the status of adoption by each State of the Uniform Regulation for National Type Evaluation. The survey was remailed to the States following the Interim Meetings in January, 1989. A telephone follow-up was conducted by OWM in July, 1989. Results were:

Handbook 44. Forty-four jurisdictions had adopted the most current version of Handbook (1989). Nine jurisdictions were operating under the 1988 or earlier version. Nineteen jurisdictions reported that they automatically adopt the latest edition of Handbook 44 by reference. (Subsequent study of State laws and regulations by OWM staff indicates that as many as 36 States automatically adopt the most recent version of Handbook 44.)

Uniform Regulation on NTE. Although fifty jurisdictions reported that they recognize the NTEP Certificate of Conformance as proof of type evaluation, only twelve jurisdictions have adopted the Uniform Regulation for National Type Evaluation. (Subsequent study of State laws and regulations by OWM staff indicates that 19 States

have adopted regulations consistent with the Uniform Regulation.) Thirty-one jurisdictions have no type evaluation requirements.

Some State directors mistakenly thought that a State is expected to adopt the Uniform Regulation only if the State intends to operate an NTEP laboratory. Other reasons for not adopting the Uniform Regulation included: (1) it is too difficult to process it through the State system considering the slowness of the legislative process; and, (2) the NTEP did not meet all of the regulatory requirements of the States.

Position of Industry. Industry representatives met with the Board of Governors to reemphasize their earlier observations that enforcement of Handbook 44 code was far from uniform among the States. Their experience is that many field inspectors are not knowledgeable about the current requirements. Some industry members believe that those in industry who have attempted to meet the requirements of the Handbook and NTEP often discover that, in many jurisdictions, the code is not being enforced. They believe that this situation is unfair, putting them at a cost disadvantage with competitors who do not invest in facilities to meet the requirements.

Their comments are summarized below.

The NTEP Process. The front end of the system (i.e., NTEP evaluation) works well and the results are credible. A general erosion of industry respect for NTEP was reported because of the perception that there are no "teeth" in the process of revocation of Certificates of Conformance and improper advertising of products.

State Enforcement. Field enforcement is now being perceived as the weak link in the system.

1. Thirty-one States are not enforcing NTEP. This situation must be changed if participation by the industry in NTEP is to be meaningful.
2. The States are not getting the information on NTEP Certificates of Conformance to the field inspectors, nor are they training their staffs adequately regarding the requirements of NIST HB 44 and the criteria under NTEP.
3. Lack of enforcement undermines the investment of manufacturers (since it costs more to build NTEP equipment), resulting in unfair competition in favor of the manufacturers who do not build to NTEP criteria.

102-3 I Program, Participating Laboratories/Evaluation Report

Participating Laboratories and Evaluation Authority. The Participating Laboratories are authorized to conduct evaluations in the following areas:

Laboratory	Areas of Authorization
California	Design and performance evaluation of scales, cash registers, metering devices, service station consoles, and taximeters.
Kansas	Performance evaluation of large-capacity scales.
New York	Design and performance evaluation of scales and cash registers. Expansion into liquid measuring devices is under discussion.
North Carolina	Performance testing of liquid-measuring devices.
NIST	All NTEP evaluations, including load cells (NIST Force Group).
Ohio	Design and performance evaluation of scales and cash registers.
USDA/Federal Grain Inspection Service (FGIS)	Design and performance evaluation of automatic bulk-weighing systems, grain test scales, and performance testing of railway track scales.

Past Workload. The workload for the years 1985 through 1989 is shown in the following table.

CERTIFICATES OF CONFORMANCE ISSUED

	1985	1986	1987	1988	1989
Total number of CofCs	127	46	123	313	454
Full CofCs	127	37	80	227	319
Provisional CofCs		9 ¹	43 ²	21 ³	50
Load cells		9 ¹	43 ²	20 ⁴	73 ⁵
Pre-NTEP CofCs				45	12

¹ Six provisional CofCs (all for load cells) upgraded to full in 1987 and 1988.

² Sixteen provisional CofCs upgraded to full in 1988.

³ Excludes Load Cells.

⁴ Thirteen provisional and seven full CofCs.

⁵ Included in totals for Full and Provisional CofCs.

About one third of the CofCs issued in 1989 were updates of CofCs issued in previous years, as shown below:

New Certificates	1989	303
Updated Certificates	1989	6
	1988	95
	1987	45
	1986	5
Total		454

Analysis of Workload Trends. The total workload of the Participating Laboratories has not changed much; the major change in the evaluation process has been associated with evaluation of load cells by the NIST Force Group. The Board expects the rate of growth in requests for evaluations to increase as additional States adopt the Uniform Regulation and require that devices installed for use have been issued CofCs. More businesses will need to conform with the latest version of Handbook 44 and obtain CofCs. In anticipation of growth, the Board plans to add one Participating Laboratory within the next 12 months. The OWM is working with other jurisdictions in order to add NTEP evaluation capability to their laboratories. An announcement will be made whenever a new Participating Laboratory is added to NTEP.

The Executive Secretary reported the following fee schedules of the NTEP Participating Laboratories.

Fee Schedules, Participating Laboratories

	NIST	CA	NY	OH	FGIS
Hourly Rate	\$70.00	\$50.00	\$50.00	\$60.00	\$38.80
Per Diem	U.S. Govt. Rate	\$82.00	U.S. Govt. Rate	\$75.00	None
Environmental Chamber	\$250.00	\$250.00	*	\$250.00	
Water Meter Test Bench		\$ 26.50			
Weight Truck (per day)		\$150.00	\$150.00	\$150.00	
Small Truck (pending)			\$ 15.00		
Mileage					
Large Truck (per mile)		\$ 1.50	\$ 2.00	\$ 1.00	
Small Truck (per mile)		\$ 1.00	\$.23	\$.75	
* Charge for chamber included in hourly charges.					

102-4 I Financial, Funding Resolution of Appeals

The NTEP has no policy or budget for meeting the expenses incurred in the resolution of appeals. The Executive Secretary drafted and proposed a policy to the Board of Governors in May 1989 (Appendix B). Although the proposal was adopted by the Board by letter ballot, it was not implemented because neither the Scale Manufacturers

Association nor the Gas Pump Manufacturers Association fully agreed with the proposal of the Board of Governors. The Board has requested the two associations to provide their recommendations for the resolution of this problem.

The OWM has paid the appeal expenses when they occurred. However, the OWM is not budgeted for NTEP expenses and will no longer fund such activities. The Board anticipates that processing new appeals will require significant funding.

102-5 I Financial, NIST Administrative Expenses

Administrative expenses incurred by NTEP must be reimbursed. The following fees were established to cover expenses for processing NTEP applications, reviewing test results from participating laboratories, and processing of Certificates of Conformance.

\$250.00 per application if the Certificate of Conformance is prepared by OWM; or

\$125.00 per application if the Certificate of Conformance is prepared by another NTEP Participating Laboratory.

102-6 I Financial, Funding Meetings of NTEP Laboratory Representatives

The evolution of the NTEP technical capability, including the development of checklists and procedures, has been very intensive over the past 4 years. Much was done through the NTEP Technical Committee, but some decisions must still be made on an ad hoc basis. The details of new technology and the rationale for the ad hoc decisions must be uniformly understood by the staff working in NTEP laboratories. The NTEP laboratories recommended that provisions be made to fund meetings of the participating laboratories representatives (at least annually) to ensure that NTEP criteria and procedures are understood and applied uniformly in all of the laboratories.

The Executive Committee: (1) approved the request; (2) recommended that \$3000.00 be added to the FY 90-91 budget for this purpose; and (3) requested that these special meetings be held in conjunction with the meetings of the NTEP Technical Committee meetings. The Laboratory Representatives held one meeting in conjunction with the NTEC meeting in June 1990.

102-7 I Policy, Labeling Requirements

Handbook 130 defines requirements for labeling prepackaged standard pack and random weight items. These labels are generated by printers interfaced with computing scales used in direct sale and in prepackaging operations. The question has been raised: "Shouldn't these requirements be included in the NTEP checklist so that the Handbook 130 requirements can be evaluated at the same time as are the Handbook 44 requirements?"

Some reservations were raised about including the Handbook 130 requirements in the NTEP evaluation including the opinion that NTEP evaluations should be limited to requirements in Handbook 44. Offsetting this opinion is the efficiency of considering Handbook 130 requirements in the NTEP evaluation, thus avoiding problems "downstream" if the Handbook 130 requirements were not met.

The Board voted to: (1) include the legal requirements contained in Handbook 130 and other NIST and NCWM publications in the test procedures of NTEP Publication 14; (2) evaluate devices for all legal requirements at the time of the type evaluation; and (3) include appropriate comments on the Certificate of Conformance issued.

102-8 I Policy, Type Evaluation Criteria for Computers

Computers are being used more frequently as integral elements in weighing and measuring systems. Agreement is needed on the procedures and criteria the NTEP is to follow when evaluating computers and their effects on the performance of systems being evaluated.

The Board decided that this issue is too complex to resolve now. The basic question is: "How far beyond the device should weights and measures regulation go?" The item was referred to the OWM for further development.

102-9 I Policy, Load Cell Testing

As planned for in the NTEP administrative policy, the permanent program for evaluation of load cells has been implemented for load cells in the range from 30,000 lbf to 100,000 lbf.

Mr. Oppermann, NIST, reported on the NIST experience and results of testing load cells under the NTEP. NIST has evaluated: (1) load cells provided by manufacturers for use by the NTEP in evaluation for issuance of CofCs; and (2) load cells procured from inventories of suppliers for comparison of performance with those provided by manufacturers. Generally, the load cells provided by manufacturers perform better than do those procured from inventories. These results cause questions to be raised, such as: (1) "Are production cells of equal quality to manufacturers' hand-picked cells?; or (2) "Is there a problem faced by NTEP related to the issuance of CofCs based on hand-picked cells if the production cells are proven to be inferior?"

The Board discussed the results developed by the NIST and expressed a general concern about the presented evidence. The Board of Governors voted to "authorize the Executive Secretary to spend up to \$15,000 to procure and test additional production cells off the shelf to gather additional information on this question." The Board further "encouraged the Executive Secretary to procure such cells on a loan basis to the extent possible in order to conserve the funds for use in reimbursement of the NIST Force Division's costs for evaluation."

102-10 I Policy, Belt-Conveyor Scales, Test Procedures

The draft belt-conveyor test procedures have been completed. A meeting of the National Type Evaluation Technical Committee (NTETC) Belt-Conveyor Sector was held on June 28, 1990, to review the latest draft. Issues remaining to be resolved before the initiation of type evaluation of belt-conveyor scales were addressed at that meeting.

The Belt-Conveyor Sector has completed all of the work it is able to do prior to initiating the actual type evaluation of belt-conveyor scales. The Sector members recommend that NTEP implement the type evaluation of belt-conveyor scales gradually as the work schedule of the NTEP laboratories permits. If issues and problems are identified during type evaluation, they will be addressed at future meetings of the Belt-Conveyor Scale Sector. It is expected that annual meetings of the Belt-Conveyor Scale Sector will be sufficient to resolve issues as they arise.

The Board of Governors concurs with this approach, and an announcement of the initiation of this program will be made when laboratories are prepared. First priority for type evaluation will be given to those companies that have requested type evaluations on belt-conveyor scales in the past. It is expected that two (perhaps three) evaluations will be conducted initially to test the procedure and determine the problems (if any) that may develop in the process.

102-11 I Appeals

The Board of Governors has met during the year to handle two appeals that it received. Final action was taken on both appeals and State Directors and the involved companies have been notified of the outcome.

F. Gerk, New Mexico, Chairman
N. David Smith, North Carolina, Chairman-Elect

J. Bartfai, New York, Past Chairman
L. DeGrange, Maryland
T. Geiler, Barnstable, Massachusetts
E. Heffron, Michigan
S. Hindsman, Arkansas
K. Simila, Oregon
D. Stagg, Alabama

C. Gardner, Suffolk County, NY, Treasurer
A. Tholen, NIST, Executive Secretary

Executive Committee



Appendix A National Conference on Weights and Measures

POLICY, INTERPRETATIONS, AND GUIDELINES

SECTION 1 - NCWM Management

SUBSECTION 4 - Publications

1.4.9. Publications, Weights and Measures, Distribution Policy

Weights and measures publications will be sold and/or distributed according to this policy.

A. SPECIAL PROVISIONS FOR MEMBERS OF THE NATIONAL CONFERENCE. Members of the National Conference on Weights and Measures may elect to receive single copies of the most current editions of the following publications from the National Institute of Standards and Technology (NIST) and/or the National Conference on Weights and Measures (NCWM) at no cost. (Additional copies are available at the prices shown in Paragraph B, below.)

NIST Handbook 44, Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices, H. V. Oppermann, editor

NIST Handbook 130, Uniform Laws and Regulations, C. S. Brickenkamp, editor

NBS Handbook 133, - Checking the Net Contents of Packaged Goods, C.S. Brickenkamp, S. Hasko, and M.G. Natrella, editors

NIST Special Publication xxx, Report of the Conference on Weights and Measures

NCWM Pub 2, Directories, State and Local Weights & Measures Officials and All Members of the NCWM

NCWM Pub 15, Interim Meeting Agenda

NCWM Pub 16, Announcement Book

B. SOURCES OF PUBLICATIONS. Non-members (or members wanting additional copies) can purchase publications from the sources and at the prices noted below.

1. Superintendent of Documents, Government Printing Office, Washington, DC 20402 (202/783-3238).

\$15.00 NIST Handbook 44, Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices, H. V. Oppermann, editor, 1990 Edition (Sept. 1989) SN003-003-02964-5

\$10.00 NIST Handbook 130, Uniform Laws and Regulations, C. S. Brickenkamp, editor, 1990 Edition (Sept. 1989) SN003-003-02962-7

\$16.00 NBS Handbook 133, Third Edition - Checking the Net Contents of Packaged Goods, C.S. Brickenkamp, S. Hasko, and M.G. Natrella, editors SN003-003-02885-1

Executive Committee

Call the Government Printing Office for the availability and price of the following publications.

NBS Handbook 105-3, Specifications and Tolerances for Graduated Neck Type Volumetric Field Standards - SN003-003-02044-3

NBS Special Publication 304, Metric Chart - SN003-003-02365-5

NBS Special Publication 304A, Brief History of Measurement Systems - SN003-003-02366-3

NBS Special Publication 345, A Metric America - A Decision Whose Time Has Come - SN003-003-00884-2

NBS Special Publication 430, Household Weights and Measures - SN003-003-01542-3

NBS Special Publication 442, Report of the 60th National Conference on Weights and Measures (1975) - SN003-003-01614-4

NBS Special Publication 471, Report of the 61st National Conference on Weights and Measures (1976) - SN003-003-01806-6

NBS Special Publication 517, Report of the 62nd National Conference on Weights and Measures (1977) - SN003-003-01966-1

NBS Special Publication 532, Report of the 63rd National Conference on weights and Measures (1978) - SN003-003-02045-1

NBS Special Publication 566, Report of the 64th National Conference on Weights and Measures (1979) - SN003-003-02147-4

NBS Special Publication 599, Report of the 65th National Conference on Weights and Measures (1980) - SN003-003-02286-1

NBS Special Publication 684, Report of the 69th National Conference on Weights and Measures (1984) - SN003-003-02637-9

NBS Special Publication 704, Report of the 70th National Conference on Weights and Measures (1985) - SN003-003-02702-2

NBS Special Publication 725, Report of the 71st National Conference on Weights and Measures, A. D. Tholen, C. S. Brickenkamp, and A. P. Heffernan, editors, (1986) - SN003-003-02765-1

NBS Special Publication 734, Report of the 72nd National Conference on Weights and Measures, A. D. Tholen, C. S. Brickenkamp, and A. P. Heffernan, editors, (1987) - SN003-003-02828-2

NBS Special Publication 750, Report of the 73rd National Conference on Weights and Measures, A. D. Tholen, C.S. Brickenkamp, and A. P. Heffernan, editors, (1988) - SN003-003-02900-9

NIST Special Publication 771, Report of the 74th National Conference on Weights and Measures, A. D. Tholen, C. S. Brickenkamp, and A. H. Turner, editors, (1989) - 003-003-02977-7

NIST Special Publication 769, INDEX to the REPORTS of the National Conference on Weights and Measures - From the First to the Seventy-third (1905-1988), F. C. Bell, W. G. Mott, N. Chaconas, editors, (1989) - SN003-003-02649-2

2. The National Conference on Weights and Measures, P.O. Box 4025, Gaithersburg, MD 20885 is the source for the following publications.

Number	Title	Price	
		<u>Members</u>	<u>Non-members</u>
Pub 1.	NCWM Constitution and Bylaws, 1987	no cost	5.00
Pub 2.	Directories, State and Local Weights & Measures, 1989 Edition	10.00	25.00
Pub 3.	NCWM Policy and Guidelines	15.00	32.00
Pub 4.	National Type Evaluation Program - Administrative Procedures	2.00	5.00
Pub 5.	National Type Evaluation Program - Index of Evaluations (through 1988)	15.00	30.00
Pub 6.	Brochure, NCWM Organization, Procedures, and Membership Plan Brochure, 1989	no cost	no cost
Pub 7.	Weights & Measures Week Guide	12.00	20.00
Pub 8.	National Type Evaluation Program and Its Relationship to the Weights & Measures Law, NBS Handbook 44, and the New Scales Code	2.00	5.00
Pub 9.	Directory, Associate Members, 1989	6.00	15.00
Pub 10.	Guide for Conduct of Annual Meeting	(not available; for Officers only)	
Pub 11.	National Training Program 1989	5.00	10.00
Pub 12.	Examination Procedure Outlines, 1989	10.00	20.00
Pub 13.	Weights and Measures Information System (WAMIS) Guide	5.00	10.00
Pub 14.	National Type Evaluation Program - Administrative Procedures, Technical Policy, Checklists, and Test Procedures	15.00	30.00
Pub 15.	Interim Meeting Agenda - Prepared annually	5.00	10.00
Pub 16.	Announcement Book - Prepared Annually	10.00	37.50
Pub 17.	Report, Task Force on Prevention of Fraud	5.00	10.00
Pub 18.	National Training Program - Directory 1988	5.00	10.00

3. National Institute of Standards and Technology, Office of Weights and Measures, Administration Building A617, Gaithersburg, MD 20899. Telephone: (301) 975 4004. There is no charge for these publications as long as supplies remain.

NBS Handbook 105-1, Specifications and Tolerances for Field Standard Weights

NBS Handbook 105-2, Specifications and Tolerances for Field Measuring Flasks

NBS Handbook 137, Examination of Distance Measuring Devices

NBS Special Publication 447, Weights and Measures Standards of the United States, A Brief History

Letter Circular 1035, Units and Systems of Weights and Measures, Their Origin, Development, and Present Status

4. National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161 (703/487-4780 or 4650).

The proceedings of the first through the sixteenth NCWM annual meetings are available in paper copy form or in microfiche. The titles, prices, and NTIS accession numbers of all of the early proceedings that are currently available are listed below.

<u>TITLE</u>	<u>NTIS PRICES</u>		<u>Accession no.</u>
	<u>Paper Copy</u>	<u>Microfiche</u>	
First Conference on the Weights and Measures of the U.S.-1905 (NBS Misc. Pub. 4)	\$12.95	\$6.95	PB87-232427
Second Conference on the Weights and Measures of the U.S.-1906 (NBS Misc. Pub. 5)	\$14.95	\$6.95	PB87-232435
Third Conference on the Weights and Measures of the U.S.-1907 (NBS Misc. Pub. 6)	\$19.95	\$6.95	PB87-232443
Fourth Conference on the Weights and Measures of the U.S.-1908 (NBS Misc. Pub. 7)	\$14.95	\$6.95	PB87-232450
Fifth Conference on the Weights and Measures of the U.S.-1910 (NBS Misc. Pub. 8)	\$19.95	\$6.95	PB87-232468
Sixth Conference on the Weights and Measures of the U.S.-1911 (NBS Misc. Pub. 9)	\$19.95	\$6.95	PB88-124219
Seventh Conference on the Weights and Measures of the U.S.-1912 (NBS Misc. Pub. 10)	\$19.95	\$6.95	PB88-124227
Eighth Conference on the Weights and Measures of the U.S.-1913 (NBS Misc. Pub. 11)	\$25.95	\$6.95	PB88-124201
Ninth Conference on the Weights and Measures of the U.S.-1914 (NBS Misc. Pub. 12)	\$19.95	\$6.95	PB88-124235
Tenth Conference on the Weights and Measures of the U.S.-1915 (NBS Misc. Pub. 13)	\$25.95	\$6.95	PB89-122055
Eleventh Conference on the Weights and Measures of the U.S.-1916 (NBS Misc. Pub. 14)	\$32.95	\$6.95	PB89-122063

Twelfth Conference on the Weights and Measures of the U.S.-1919 (NBS Misc. Pub. 41)	\$25.95	\$6.95	PB89-122071
Thirteenth Conference on the Weights and Measures of the U.S.-1920 (NBS Misc. Pub. 43)	\$25.95	\$6.95	PB89-12208
Fourteenth Conference on the Weights and Measures of the U.S.-1921 (NBS Misc. Pub. 48)	\$19.95	\$6.95	PB89-122097
Fifteenth Conference on the Weights and Measures of the U.S.-1922 (NBS Misc. Pub. 51)	\$19.95	\$6.95	PB89-122105
Sixteenth Conference on the Weights and Measures of the U.S.-1923 (NBS Misc. Pub. 55)	\$19.95	\$6.95	PB89-122113

Contact NTIS for current price information on the following publications; there is a charge per page for paper copies.

NBS Handbook 98, The Examination of Farm Milk Tanks - COM. No. 72-10619 (May 1964)

NBS Handbook 99, The Examination of Liquefied Petroleum Gas Liquid-Measuring Devices -- this has recently been replaced by National Training Program Module 21.

NBS Handbook 112, Examination Procedure Outlines for Commercial Weighing and Measuring Devices - COM. No. 73-50836

NBS Handbook 117, Examination of Vapor-Measuring Devices for Liquefied Petroleum Gas, S. Hasko, - PB 248987

NBS Handbook 143, State Weights and Measures Laboratory Program Handbook, H. V. Oppermann and J. K. Taylor, (Feb. 1985) - PB85-183358

NBS Handbook 145, Handbook for the Quality Assurance of Metrological Measurements (1986) - PB87140422NBS Handbook 94, The Examination of Weighing Equipment - COM. No. 73-10635

NBSIR 85-3172, Package Checking Field Manual, to accompany NBS Handbook 133, Checking the Net Contents of Packaged Goods, C. S. Brickenkamp, S. Hasko, and M. G. Natrella, editors, (Aug. 1985) - PB86-108776/AS

NBS Special Publication 629, Report of the 66th National Conference on Weights and Measures (1981) - PB821-78997

NBS Special Publication 645, Report of the 67th National Conference on Weights and Measures (1982) - PB831-67148

NBS Special Publication 663, Report of the 68th National Conference on Weights and Measures (1983) - PB841-10998

NBS Special Publication 686, State Weights and Measures Laboratories Program Description and Directory, H. V. Oppermann, (Jan. 1985) - PB85-137651

Appendix B

Proposed Changes to

NTEP ADMINISTRATIVE PROCEDURES, TECHNICAL POLICY, CHECKLISTS, AND TEST PROCEDURES

Add the following paragraph to Section D. REQUEST FOR TYPE EVALUATION.

To obtain a type evaluation, the applicant shall:

1. ----
2. ----
3. ----
4. ----
5. *submit a filing fee of \$100.00 payable to the National Conference on Weights and Measures. The filing fees will be deposited in a reserve account for use in offsetting unreimbursed costs incurred by the NTEP in the resolution of appeals.*

Replace existing Section "O. APPEALS PROCESS" with the following.

O. APPEALS PROCESS

At any stage in the evaluation process, an appeal may be filed with the Board of Governors (hereafter referred to as "the Board").

This policy addresses three distinct appeals situations:

1. ***Applicant Appeal.** In this case, the NTEP has concluded that a "type" does not meet the requirements and has decided not to issue either a Full or a Provisional Certificate of Conformance (hereafter referred to as a "Certificate"), or the NTEP has decided to withdraw for cause a previously issued Certificate. The manufacturer (applicant for NTEP evaluation) then files an appeal to either of these decisions.*
2. ***Third Party Appeal.** In this case, a third party (other than the holder of the Certificate or the NTEP) files an appeal of the issuance of a Certificate based on evidence that the "type" does not conform with Handbook 44.*
3. ***Regulatory Agency.** This is a variation of the Third Party Appeal in which a Weights and Measures authority files an appeal of the issuance of a Certificate based on evidence that the "type" does not conform with Handbook 44 or has a history of unacceptable performance in use.*

1. APPLICANT APPEAL

If a manufacturer appeals a decision of the NTEP NOT to issue a certificate or of the Board to WITHDRAW a Certificate, the steps in the appeals process follow.

- a. *A manufacturer (the applicant for a Certificate) files an appeal with the Board. The appeal must include (1) justification for reconsideration, (2) payment of a non-refundable \$100.00 filing fee, and (3) payment of a deposit prescribed by the NTEP based on its estimate of the expense for conducting a review of the Board's decision, including additional testing if required.*

- b1. Board rejects appeal as not justified. The Board may decide that the appeal has inadequate justification for further action.

The original NTEP decision is reaffirmed and the deposit is returned to the applicant. The applicant may appeal to the National Institute of Standards and Technology (hereafter referred to as NIST), the next level of appeal.

- b2. Board accepts justification as adequate. The Board may decide that the appeal is convincing enough to uphold the appeal without additional testing.

The original NTEP decision is reversed, a Certificate is issued, and the applicant's deposit is returned.

- b3. Board decides reevaluation is needed. If the justification provided by the applicant is not, in itself, convincing, the Board may request NTEP to reevaluate the "type."

If the "type" does not meet the requirements, the original decision of the NTEP is affirmed, and any part of the deposit remaining after costs have been offset will be returned to the applicant. In this case the applicant may still appeal to the NIST.

If the type meets the requirements, the original NTEP decision will be reversed, a Certificate will be issued, and any part of the deposit remaining after costs have been offset will be returned to the applicant.

2 THIRD PARTY APPEAL

If a Certificate has been issued by the NTEP and a third party (other than a Regulatory Agency) believes that the "type" does not meet the requirements of Handbook 44, that party (Appellant) may appeal the issuance of a Certificate to the Board. The steps in the appeals process follow.

- a. A third party (hereafter referred to as the Appellant) other than a Regulatory Agency files an appeal with the Board. The appeal must include (1) justification for reconsideration, (2) payment of a non-refundable \$100.00 filing fee, and (3) payment of a deposit prescribed by the NTEP based on its estimate of the expense for conducting a review including additional testing.

- b1. Board rejects appeal as not justified. The Board may decide that the appeal has inadequate justification for further action.

The original NTEP decision is reaffirmed and the deposit is returned to the appellant.

The appellant may appeal to the National Institute of Standards and Technology, the next level of appeal.

- b2. Board accepts justification as adequate. The Board may decide that the appeal is convincing.

The Board will advise the holder of the Certificate of the pending action and offer the opportunity to present a defense to the Board.

If, after consideration of the defense, the Board concludes that the "type" does not meet requirements, it will withdraw the Certificate and return the appellant's deposit.

The Certificate holder may appeal to the NIST.

If the defense convinces the Board that the "type" meets requirements, the original Certificate will remain in effect, and the deposit of the appellant will be returned.

The appellant may appeal to the NIST.

- b3. Board decides reevaluation is needed. If the justification provided by either the appellant or Certificate holder is not, in itself, convincing, the Board will request NTEP to reevaluate the "type."

Before the NTEP proceeds, the Certificate holder must make a deposit prescribed by the NTEP based on its estimate of the expense for conducting a review including additional testing.

If the holder of the Certificate refuses to make the deposit, the Board will conclude that the "type," ipso facto, does not meet the requirements, will uphold the appeal, withdraw the Certificate, and return the appellant's deposit.

If the holder of the Certificate makes the deposit, the "type" will be reevaluated.

If the "type" meets the requirements, the original decision of the NTEP is affirmed, and any part of the appellant's deposit remaining after costs have been offset will be returned. All monies deposited by the holder of the Certificate will be returned.

The appellant may appeal to the NIST.

If the type does not meet the requirements, the original NTEP decision will be reversed, the Certificate will be withdrawn, and any monies deposited by the holder of the Certificate, after costs have been offset, will be returned. The appellant's entire deposit will be returned.

3. REGULATORY AGENCY APPEAL

If a Certificate has been issued by the NTEP and a Weights and Measures authority believes that the "type" does not meet the requirements of Handbook 44 or has a history of unacceptable performance in use, that party may appeal the issuance of a Certificate to the Board. The steps in the appeal process follow the same sequence as that for the Third Party Appeal except that the regulatory official will not be subject to any filing fees or deposit.

4. SUBSEQUENT APPEAL OPTIONS

If the resolution of the appeal by the Board is not acceptable by any party to the appeal, that party may appeal to the NIST. The NIST serves as a second level of review in its role as the issuer of NTEP Certificates of Conformance.

If the resolution of the appeal by the NIST is not acceptable to any party to the appeal, that party may appeal to the Federal Trade Commission through the established Federal Government process.

5. RESERVE FUND

Any unreimbursed expenses incurred by the NTEP in the resolution of appeals will be paid out of the NTEP Reserve Fund. (See Section D. REQUEST FOR TYPE EVALUATION, Paragraph 5.)

Appendix C

Report on OIML

Samuel Chappell, NIST

CIML Meeting

A meeting of the International Committee of Legal Metrology (CIML) was held in Paris in September 1989.

OIML Certificate System for Measuring Instruments. Three drafts of this proposal had been prepared, and it was the intention to approve the proposal at this CIML meeting. Objections led by the United States and a few other CIML members were convincing enough to postpone the vote on it. Our main objection was that the proposal needed further clarification in order to be properly interpreted and implemented. All the latest drafts of this proposal have been sent to the members of the NCWM's Executive Committee for review, including the draft sent out officially to CIML members for review and vote by June 30, 1990. The major elements of the proposal are as follows:

- o It is voluntary.
- o An Issuing Authority for each category of instruments will be established in participating member nations.
- o Testing will be carried out at officially recognized laboratories according to the metrological and technical requirements of relevant OIML recommendations.
- o The test report, which will accompany a Certificate, will be prepared according to the format prescribed in OIML recommendations.
- o An owner of a Certificate may use it and the test report in support of an application for type approval of the instrument in any nation and may refer to the Certificate in marketing literature.
- o A participating member nation must have an appeals process whereby its decisions may be challenged by a participating manufacturer, importer, or distributor of a measuring instrument affected. This appeals process is established according to national laws.

This proposal has implications for the NCWM. Through NTEP, the NCWM, if it chooses to participate, could become an Issuing Authority for instruments mutually covered by Handbook 44 and OIML Recommendations. On the other hand, it is a tacit assumption that OIML member states should consider OIML Certificates and accompanying test reports in their type approval programs. NCWM might therefore have to decide on what recognition would be given to such Certificates and test reports when presented by instrument manufacturers prior to type evaluation.

The benefits of the Certificate System for manufacturers could be a saving in time and expense in getting the approval in various nations in which they choose to market their products. The benefits to the legal authorities could also be in reduced time and expense associated with carrying out type evaluations of measuring instruments.

Evidence strongly indicates that this Certificate system will have a significant influence on the harmonization taking place in the European Community and subsequently in all of Europe. Further information on this point can be provided upon request.

Other Activities. Under the new authority provided to CIML by the International Conference of Legal Metrology, three Recommendations were approved covering the following topics: "Volume of Ships' Tanks," "Barometers," and "Volume of Measuring Bottles."

Executive Committee

A report was given by the Swedish CIML member on an intercomparison among the Nordic member Nations of tests of nonautomatic weighing instruments according to the requirements of OIML Recommendation 76. The results of this intercomparison may be helpful in the revision of that recommendation which is underway. OIML Recommendation 76 was approved at the last Conference in Sydney, Australia in October 1988.

The next CIML meeting is scheduled to be held in Porto, Portugal in October 1990.

Presidential Council of CIML

A meeting of the Presidential Council of CIML was held in February at BIML in Paris. Sam Chappell, Vice President of CIML, participated. The primary subjects of discussion were: (1) the new draft of the proposed "OIML Certificate System for Measuring Instruments;" (2) a review of the quality of OIML recommendations with regard to their being included in the Certificate System; and (3) a revision of the "Working Methods of OIML Secretariats." An important aspect of the last subject is to provide a uniform style and content for OIML recommendations. At present, only a few of the existing OIML recommendations meet the requirements for being included in the proposed "Certificate System."

Activities of OIML Secretariats

This part of the report: (1) lists the Secretariats of interest to the NCWM and identifies draft recommendations and documents being developed; (2) provides a schedule of International Working Group (IWG) meetings completed or planned for that work (dates for U.S. National Working Group (USNWG) meetings for the work, which are more flexible, are not provided). More details on many of these activities were reported by Otto Warnlof to the Specifications and Tolerances Committee.

o PS5D "Dynamic Measurement of Liquids."

- RS1 on "Meters with Measuring Chambers or Turbines" (France). A second preliminary draft of a combined recommendation on this subject was distributed to the USNWG for comment. Comments were submitted in March 1990. An IWG meeting is scheduled at NIST during the week of October 22, 1990 to discuss this work.
- RS3 on "Water Meters" (U.K.). A second preliminary draft recommendation on the subject was received and reviewed. Comments were sent in December 1989. An IWG meeting is scheduled to be held in West Berlin in October 1990.
- RS6 on "Electronic Devices" (France). A first draft recommendation on this subject was distributed in June 1989 to the USNWG. Vote and comments were sent to the Secretariat in September. The U.S. voted no. This draft recommendation will also be discussed at the IWG meeting to be held at NIST in October 1990.
- RS7 and RS9 on "Methods and Devices for Verification" and "Vortex Meters," respectively (Japan). Meetings of these two RSs were held in Japan in November 1989. The U.S. did not participate but did contribute comments on the following three preliminary drafts discussed at the meeting: (1) "Test Procedures for Gas Pumps," (2) "Pipe Provers," and (3) "Vortex Meters."
- RS10 on "Direct Mass Flow Meters" (U.S.A.). A second preliminary draft prepared by the USNWG has been distributed to the IWG for review and comment. An IWG meeting is scheduled to be held at NIST during the week of October 22, 1990.

o PS5S on "Static Measurement of Liquids."

- RS12 "Static Direct Mass Measurement of Quantities of Liquids" (Australia). A first preliminary draft was received and distributed for review by the USNWG. Comments are requested by July 1990.

o PS6 on "Measurement of Gas."

- RS4 "Measurement of Hydrocarbon Gases Distributed by Pipeline" (U.S.S.R.). A second preliminary draft was distributed to the USNWG in August 1989. Comments were sent to the Secretariat in October 1989.

o PS7 on "Measurement of Mass."

- RS2 on "General Problems" (U.S.A.). R74 on "Electronic Weighing Instruments" is being revised and has been distributed for review. Comments were received from members of the USNWG and also from some OIML member nations participating in the IWG. A meeting of the IWG to discuss the revised R74 will be held at NIST during the week beginning July 16, 1990.

- RS4 on "Non-Automatic Weighing Instruments" (France-West Germany). A revision of R76 on the subject is being carried out by the Secretariat. The USNWG commented on proposals by the Secretariat in May 1989, and subsequently a draft revision of R74 was distributed. Comments by the USNWG were sent to the Secretariat in March 1990. A meeting of PS7/RS4 was held in Braunschweig in May 1990 in which the U.S. participated. This meeting preceded by an OIML Seminar "Non-automatic Weighing Instruments." Two U.S. scale manufacturers presented papers at that Seminar.

- RS5 on "Automatic Weighing Instruments." Four draft recommendations are in various stages of development: (1.) 1st draft on "Hoppers Scales" has been approved recently by vote; (2.) 1st draft on "Rail Road Track Scales" was distributed for vote on which the U.S. voted no with all votes being 7 yes, 2 no, and 1 abstention; (3.) 3rd draft revision of R50 on "Belt Weighers" was reviewed by the USNWG with comments being submitted in March 1990; and (4.) 1st draft revision of R61 on "Gravimetric Filling Machines" was reviewed by the USNWG with comments being sent to the Secretariat March 1990. All four draft recommendations were discussed at an IWG meeting in the U.K. in May 1990 in which the U.S. participated.

- RS8 on "Load Cells." The revised R60 on "Load Cells" was prepared by the USNWG and submitted to CIML for vote. The votes were 30 yes and 1 no (FRG) with 6 countries providing comments. The Secretariat has responded to all comments. This revised R60 is expected to be considered for approval at the next CIML meeting in October 1990.

o PS8 "Weights."

- Belgium has prepared a combined draft recommendation on "Weights" that was distributed for review and comment to the USNWG in October 1989. Comments were sent to Secretariat in December 1990. A meeting is scheduled to discuss this combined draft recommendation on July 19, 1990 at NIST.

o PS20 on "Packaged Products."

- A draft recommendation was prepared by West Germany on "Drained Weight" of packaged goods. It was distributed to the USNWG and IWG for review and comment. A meeting of the Secretariat was held in Wabern, Switzerland in June 1990 to discuss this draft along with an IWG meeting of PS2/RS5 on "Sampling." The U.S. was represented at these meetings at which the decision was to take no further action on the proposed draft recommendation on the "Drained Weight." In addition, no new work was proposed for "sampling."

o PS22 on "Metrological Controls" (U.S.A.).

- RS4 on "Initial and Subsequent Verification" (U.S.A.). A draft document is being prepared on "Quality Assurance as Applied to Metrological Controls." This has been distributed to the USNWG and IWG for review and comment. Briefly, this document outlines procedures whereby legal officials may allow a manufacturer, which has obtained pattern approval, to declare that instruments produced meet the requirements for initial verification based on quality control procedures used in production. An IWG meeting to discuss this draft document is scheduled to be held at BIML in Paris in October 1990. At the same meeting, an effort to combine other documents on metrological control produced under PS22 will be discussed.

Summary

The overall activity of OIML has increased significantly. A similar increase in work is being experienced by other national and international standardization organizations. Much of this increase reflects the impact of the globalization of trade on measuring instruments and related products along with the need or requirement for testing and certification of products. In addition, regional economic and trade agreements and arrangements among various nations are having an influence. Most notable is the agreement within the European Community (EC) to harmonize administrative and technical requirements for products traded within the EC by the end of 1992. This will directly affect the 12 member nations of the EC; however, close cooperation of the EC with the nations of European Free Trade Association (EFTA) will in effect include six more nations for a combination of 18 nations in this regional agreement. All of Western Europe would therefore be affected by this harmonization within the EC. As we watch the news of the demise of the existing communist governments in the Eastern European block nations, it appears evident that stronger commercial ties will soon be established between those nations and Western Europe. These efforts have already begun; therefore, the principles of EC92 are spreading throughout Europe and, in time, may include the Soviet Union.

Appendix D

Operating Budget 90/91

(July 1, 1990 to June 30, 1991)

The major change occurring with respect to the budget is the growth in membership. At this time, the membership is over 2600. The 90-91 budget is based on a membership of 2643.

Several items on the Executive Committee Agenda are related to expenses:

- 101-1 Publications, Sale/Distribution (Account # 8.0 and new Account # 1.8)
- 101-11 Finances, Expenses of Committee Members (Account #'s 4.0 and 5.0)
- 101-18 Program, National Training (Account # 12)
- 102-4 Financial, Funding Resolution of Appeals (new Account #'s 1.X and 5.3)
- 102-6 Financial, Funding Meetings of NTEP Laboratory Representatives (new Account # 5.2)

INCOME

Number (a)	Name (b)	FY90-91 Proposed (c)	FY89-90 Budget (d)	FY88-89 Actual (e)	FY87-88 Actual (f)
1.1	Registration Fees	\$30,000	\$30,000	\$28,265	\$31,305
1.2	Membership Fees	92,500	67,550	73,650	61,402
1.3	Training Modules	6,500	6,500	3,805	7,420
1.3	NTP Modules				
1.3a	HB 133 Field				
1.4	Interest	3,700	3,000	4,506	3,192
1.5	Promotional	1,000	1,000	361	668
1.6	Special Events	8,000	5,000	7,696	3,790
1.8	Publications, Sale	1,000			
1.9	Miscellaneous	300	300	25	250
1.X	NTEP, Operations	15,000			
Total		\$158,000	\$113,350	\$118,308	\$108,027

Footnotes (INCOME):

- 1.1 No change. Based on registration of 300 @ \$100.
- 1.2 As noted above; 2643 @ \$35 (rounded to \$92,500).
- 1.3 No change.
- 1.4 Higher because of purchase of an additional Certificate of Deposit
- 1.5 No change.
- 1.6 Estimate based on 88-89 actual.
- 1.8 Estimate based on implementation of new policy (Item 101-1)
- 1.X Based on costs incurred with one load cell appeal.

Executive Committee

Expenses

Number (a)	Name (b)	FY90-91 Budget (c)	FY89-90 Budget (d)	FY88-89 Actual (e)	FY87-88 Actual (f)
2.0	Annual Meeting	\$15,000	\$14,000	\$13,627	\$ 9,880
3.0	Interim Meeting	5,000	4,000	2,672	2,383
4.0	Committee Meetings	20,000	20,000	24,344	19,242
4.1	Executive	[5,000]	[5,000]	[7,406]	[3,690]
4.2	Laws and Regs	[3,000]	[3,000]	[3,361]	[5,920]
4.3	Specs & Tol	[3,500]	[3,500]	[4,753]	[1,639]
4.4	Education	[3,500]	[3,500]	[6,112]	[1,606]
4.5	Liaison	[3,000]	[3,000]	[2,101]	[1,059]
4.6	Resolutions			[298]	
4.7	Nominations			[312]	
4.9	Misc	[2,000]	[2,000]		[5,328]
5.0	Special Programs	43,000	18,000	14,633	16,060
5.1	NTEP, Bd of Governors	[7,000]	[6,000]	[8,074]	[7,400]
5.2	NTEP, Coordination	[3,000]			
5.3	NTEP, Operations	[15,000]			
5.4	OIML	[5,000]	[4,000]		[1,432]
5.7	TF on Belt Conveyor	[2,000]	[2,000]		[1,192]
5.8	TF on Energy Systems		[2,000]	[5,841]	[1,996]
5.9	TF on Safety	[7,000]	[4,000]		
5.X	TF on Commodity Rqmnts			[717]	
5.XX	TF on 21ST Century	[4,000]			
6.0	Chairman/Chairman Elect	12,500	12,550	13,852	7,972
7.0	Membership Program	6,000	6,000	9,321	7,106
8.0	Printing/Pubs	12,000	6,000	5,345	3,859
9.0	Administration	10,500	12,500	4,555	10,203
10.0	Special Events	8,000	5,000	9,793	6,058
11.0	Promotion	2,000	1,300	1,151	962
12.0	Training Modules	24,000	14,000	4,117	3,958
12.4	Printing Existing	[4,000]	[4,000]		
12.5	Materials, Module Implementation	[20,000]	[10,000]		
	Total Disbursements	\$158,000	\$113,550	\$103,410	\$87,683
	Surplus:			14,898	20,344
	Totals	\$158,000	\$113,550	\$118,308	\$108,027

Footnotes (EXPENSES):

2.0 Inflation, mostly hotel costs.

3.0 Inflation, mostly hotel costs.

4.0 This is primarily the expenses of committee members attending the Interim Meeting.

5.0 Increases include: (1) \$3,000 for travel expenses of NTEP lab chiefs to hold one meeting for cross training; (2) \$15,000 to cover expenses incurred in resolving appeals - this is a wash with 1.X on the assumption that the NCWM will establish a policy to provide needed appeals testing funds, (3) increase for operation of TF on Safety, and (4) provision of \$4,000 for additional Task Force.

- 6.0 6.01 - Chairman \$8,000
 6.02 - Chairman-Elect 4,500
- 7.0 The significant reduction from the 88-89 year is due to moving the Conference database in-house at OWM, thereby saving contract costs for services.
- 8.0 Larger number of NCWM publications results in added expenses to provide to members.
- 9.0 The significant increase over the 88-89 year is due to the success of the Training Program, which adds expenses of registering participants in the National Register. The National Register maintains the records of the modules taken, completed, and the CEUs awarded by individual.
- 10.0 This is a wash with 1.6 above.
- 11.0 Increase to provide ability to promote new members.
- 12.0 Provides funding for conversion of modules into a common format for updating.

Appendix E

National Conference on Weights and Measures Task Force on Safety

Progress Report

This report is in two sections: (1) January 1990 meeting; and (2) April 1990 Meeting.

January 1990 Meeting.

The Task Force on Safety held its first meetings during the National Conference on Weights and Measures (NCWM) Interim Meetings in Scottsdale, Arizona. The Task Force was able to establish its objectives and identify specific tasks to be accomplished by the group.

Primary Objectives.

1. Update each Examination Procedure Outline (EPO) found in NCWM Publication 12 (EPO's for Weighing and Measuring Devices) to include basic safety information.
2. Incorporate safety information into the training modules of the National Training Program (NTP).
3. Make additions to National Institute of Standards and Technology (NIST) Handbook 145 to include safety information for the metrology laboratories.
4. Establish a library of safety information.
5. Establish an NCWM Subcommittee on Safety when the Task Force is disbanded and encourage similar subcommittees at the regional level.
6. Develop a separate publication detailing the work of the Task Force upon completion of its work.

The Task Force also met with the NCWM Liaison, Education, and Executive Committees. During its meetings with each standing Committee, the Task Force presented its goals and requested appropriate support from each Committee.

The Task Force recognizes that safety in the work place is an important issue which affects everyone, especially those individuals who handle heavy weights and equipment on a routine basis. Weights and measures field inspectors and laboratory metrologists are routinely exposed to potential safety hazards: these hazards are present in the equipment they use, the products with which they work, and the locations in which they work. The Task Force believes that dangerous situations can be avoided only through recognition of these potential hazards and the establishment of good safety practices.

While a number of weights and measures jurisdictions already have safety programs in place, many other jurisdictions have few or no established safety policies or procedures. The Task Force recognizes that the establishment of a safety program in a jurisdiction that has no safety program in place may seem overwhelming in terms of time and staff. The Task Force hopes that the objectives outlined above will facilitate incorporation of safety practices into all phases of weights and measures activities.

The First Priority -- EPO's

The Task Force recognizes that a step-by-step approach is the most effective means to ensure the promotion of safety awareness in routine weights and measures activities. Training modules are often presented only to inspectors who are just beginning to learn about a particular testing activity and not to those inspectors who have actively performed that type of testing for a long period of time. Because the issue of safety should reach all inspectors, not just beginners to a test procedure, the Task Force targeted the EPO's as its first priority in getting safety information out

to the various States. Almost every weights and measures inspector has access to and regularly makes use of the Examination Procedure Outlines (EPO's) found in NCWM Publication 12. Similarly, laboratory metrologists make frequent use and reference to the Standard Operations Procedures (SOP's), Good Laboratory Practices (GLP's), and Good Measurement Practices (GMP's) found in NCWM Handbook 145. By incorporating safety information into the EPO's and equivalent procedures in HB 145, the Task Force hopes to reach both lab and field personnel and to raise the level of safety consciousness in the everyday routine of weights and measures activities.

Each Task Force member will review the EPO's in NCWM Publication 12 prior to the next meeting of the Task Force to identify safety considerations which should be incorporated. At its next meeting the Task Force will discuss the work done by the members and will review the EPO's to summarize the safety information to be included. At the beginning of each EPO, a list of potential safety hazards will be identified using key words such as "electrical hazards," "location of testing," or "toxic substances." These key words will serve to warn the inspector prior to beginning an inspection of the potential safety hazards involved and of the preventive measures which can be taken. The Task Force will also incorporate safety information into the body of the EPO when a particular aspect of safety must be emphasized. For example, in the EPO for testing LPG meters, the need for protective gloves will be noted by use of a key word at the beginning and emphasized again in the body at the point that the inspector begins to set up the testing equipment.

The Task Force will develop a glossary containing the key words used at the beginning of each EPO. The glossary will be included in the back of Publication 12 and will define and elaborate on each key word, giving examples of the potential safety hazards implied by each term. For example, the glossary might include the following:

This glossary defines the key words which are used at the beginning of each EPO to identify potential safety hazards. Following each key word is a brief list of the most common hazards associated with that particular category of safety risk; the inspector is reminded that other associated hazards may exist and should be considered for each individual device and installation. Inspectors should follow those safety procedures established by their jurisdiction, including use of protective clothing and equipment. In all examination procedures, care should be taken to minimize safety risks and to remove potential safety hazards before the inspection begins.

electrical hazards

- improper maintenance of equipment such as:
- worn or faulty electrical cords
- faulty electrical outlets
- too many extension cords
- exposed or loose electrical wiring or circuitry, especially when sealing the device
- scale not designed for wet environments being used in an area frequently exposed to water or used to weigh wet products.

location of testing

grain mills or elevators:

- inhalation of airborne grain dust -- use of dust masks
- overhead bins -- use of hard hats
- slick floor surfaces due to dust -- proper footwear with adequate traction and protection from falling objects; caution when moving about facility

chemical plants:

- check with plant manager to determine products to which you will be exposed and what precautions must be taken
- exposure to chemicals and caustic materials -- proper protective clothing and equipment such as coveralls, respirators, gloves, eye protection, protective shoes

slaughterhouse/meat packing facility:

- slick, wet surfaces -- proper footwear with adequate traction and protection from falling objects; caution when moving about facility
- hanging meat hooks with sharp prongs -- protective headgear and eye protection, caution when moving about facility...

Executive Committee

- hanging meat hooks with sharp prongs -- protective headgear and eye protection, caution when moving about facility...

An approach similar to that described for the EPO's might also be used in NIST Handbook 145. Prior to its next meeting, the Task Force will request assistance from NIST in incorporating safety information into the SOP's, GLP's, and GMP's of NIST Handbook 145.

Training Modules

In a meeting with the Education Committee, the Task Force suggested incorporating safety information into the modules of the NTP as each is updated and revised. The Education Committee responded favorably and agreed to assist the Task Force in this area by reviewing any suggested changes and additions to the EPO's and training modules.

The Task Force specifically requested that the Education Committee:

1. Incorporate the revised EPO's into appropriate training modules as each module is revised.

Upon completion of its review of the EPO's, the Task Force will provide members of the Education Committee with copies for their review and input. Once agreement on revisions has been reached, the Task Force will request that the EPO be incorporated into the next revision of the appropriate training module.

2. Include additional and detailed safety information in training modules as they are revised at the discretion of the Education Committee.

The Task Force believes that training modules should expand specific safety issues to review potential hazards and preventive measures in each module. A separate chapter on safety (such as is currently found in Module 21, LPG Liquid Measuring Devices) is most desirable to emphasize the importance of safety awareness as a routine part of inspection.

As it progresses in its work, the Task Force will make specific recommendations for the existing training modules. Upon completion of its work, the Task Force hopes to provide guidelines to the Committee for ensuring that appropriate safety information is incorporated into future modules.

3. Provide copies of revised EPO's to instructors and students participating in the presentation of a module which has not been revised to include extensive safety information. This will ensure that safety information is included in the instruction program until such time as the module is scheduled for revision.
4. Include in the NTP's current library of audiovisual materials (which are available to the State and local jurisdictions for training) any available audiovisual materials concerning safety.

The Task Force has already identified some available audiovisual materials concerning safety which can be provided to the Education Committee for inclusion in their audiovisual library. It is anticipated that additional sources of material will be identified as the Task Force develops its safety library. The Task Force will prepare a list of information concerning sources of this material and provide it to the Education Committee for review. The list might be used for purchasing or simply to serve as a source of information for additional audiovisual materials for inquiries received by the Education Committee.

Safety Library

A great deal of information about safety in the work place has been gathered by Task Force members and a great deal more information is available from sources such as the American Petroleum Institute, the National Propane Gas Association (NPGA), Occupational Safety and Health Association (OSHA), Consumer Product Safety Commission (CPSC), and industry groups. The Task Force will not make formal recommendations concerning safety to the NCWM until its work has been completed; however, until such time as recommendations are made, the Task Force believes that the information that has been gathered should be made easily accessible to weights and measures jurisdictions.

The Task Force believes that this information might be useful to weights and measures jurisdictions in establishing their own safety programs and can assist the weights and measures community in developing safe work habits. Although not expert in the area of safety, the Task Force does believe that it can assist jurisdictions in obtaining the information needed to implement safety practices in many of the routine activities of a weights and measures jurisdiction. By categorizing the information that is available and making it accessible to jurisdictions along with a list of expert contacts, the Task Force hopes to ease the burden of beginning a safety program from scratch, as well as providing an additional source of information for those jurisdictions with safety programs already in place.

The Task Force will organize the information that has been gathered into a "library" of safety information. A list of the information will be developed as the material is collected and will contain the title, a brief summary, the source, and the number of pages of each piece of information. The list will be divided into main subject categories (e.g., Safety Equipment and Clothing), with subcategories according to the type of inspection to which it applies. A preliminary list of categories is as follows:

1. Safety Philosophies and Good Work Practices
2. Safety Programs Already in Place
3. Safety Training and Education
4. Safety Gear and Clothing
5. Suitability of Vehicles for Weights and Measures Functions
6. Results of Tests To Establish Exposure Levels to Toxic Substances
7. Adaptation of Weights and Measures Equipment to Reduce Safety Risks
8. Accidents During Weights and Measures Testing
9. Changes to Policies and Procedures to Address Safety Concerns
10. Actions Taken by Federal, State, or Local OSHA Groups Relating to Weights and Measures Activities
11. Miscellaneous Safety Information

The Task Force will review the listing of information at its next meeting to determine if any revisions to the list of categories are required and will continue to develop the safety library as it proceeds with its work. At the present time the Task Force plans to have the NIST technical advisor to the Task Force maintain this "library" of safety information at NIST. A listing of information in the safety library will be distributed to NCWM members, along with instructions on how to obtain the information when the list has been further developed and the information catalogued.

The Task Force will continue to search for and gather information which might assist weights and measures jurisdictions in the area of safety. A letter will be sent to the State and active local weights and measures jurisdictions and to industry groups to request any additional safety information which they might provide to the Task Force. A similar letter will be sent to the chairperson of each regional weights and measures conference. Task Force members attending regional conferences will encourage members to submit information to the Task Force. An article has also been submitted for publication in the NCWM newsletter, W&M Today, requesting NCWM members to forward pertinent information to the Task Force. The Task Force also recognizes the importance of including information about means that inspectors have devised to address a particular safety concern in their everyday activity and about accidents which have occurred; issues such as these serve to provide examples of how some jurisdictions have responded to hazardous situations.

Safety Subcommittee

The Task Force discussed various means which might be used to ensure that the issue of safety will be carried on even after the Task Force is disbanded. It is hoped that the importance of safety will continue to be emphasized by the NCWM. The Task Force recognizes that a mechanism must be provided by which members will continue to be made

Executive Committee

aware of areas of safety concern, ways to improve safety practices, and means by which to obtain information about a specific area of safety.

It was initially suggested that a person be designated at NIST to receive inquiries and to provide assistance to Conference members in resolving safety concerns after the Task Force is disbanded. After discussion with the other Committees, it was determined that a more effective approach might be to establish a NCWM standing committee or subcommittee. A standing subcommittee will provide a permanent mechanism by which safety issues and concerns are reviewed by the NCWM on a regular basis. Such a subcommittee would also facilitate the submission of safety issues to the NCWM by providing a direction for Conference members to focus their questions and concerns about safety in the weights and measures community.

It was suggested that a subcommittee on safety under the Education, Administration, and Consumer Affairs Committee would be most appropriate since training provides an ideal mechanism for conveying the general importance of safety and specific safety precautions for inspection activities. The Task Force will complete its work prior to making specific recommendations to the NCWM concerning the establishment of a separate committee or subcommittee; the Task Force would be more informed and would be in a better position to evaluate the continued needs of NCWM members and to recommend the best way to meet those needs.

NCWM Publication on Safety

The Task Force discussed the various means by which safety information can be disseminated to the members of the NCWM. Inclusion of information in the EPO's, the procedures of Handbook 145, and the NTP Training Modules will provide a means to reach the field inspector and the laboratory metrologist. The library of safety information can be used by NCWM members to gain access to information in specific areas of safety. The Task Force also hopes to identify a means of incorporating safety information into the procedures for other weights and measures activities not identified in the EPO's or Handbook 145 (e.g., package checking, testing of grain moisture meters) and other areas of safety, such as in testing equipment (e.g., use of an explosion-proof pump or wiring on an LPG prover).

The objectives identified by the Task Force will serve to provide information concerning the incorporation of safety into weights and measures activities to specific groups of Conference members; however, there should be some source of information that presents an overview of the issue of the issue of safety as it applies to the weights and measures community. The Task Force determined that an effective approach might be to develop a separate NCWM publication that presents an overview of safety, discusses current methods for resolving safety concerns that might be associated with weights and measures activities, and indicates means to obtain information and assistance. The Task Force intends to develop this separate publication as it proceeds with its work and plans to complete the document upon the conclusion of its work.

Next Meeting

The Task Force plans to hold a meeting in April 1990 at NIST in Gaithersburg, Maryland. Prior to this meeting, members of the Task Force will review and summarize any gathered safety information and forward it to the Task Force technical advisor. Members will also study the existing EPO's in NCWM Publication 12 for inclusion of specific safety information. At its next meeting, the Task Force plans to review the EPO's to identify safety concerns for each EPO and to develop a glossary of key words for inclusion in NCWM Publication 12. The Task Force will also review the information that has been catalogued into the safety library up to that time, and will evaluate the list of categories to determine that it adequately presents the information. The Task Force also plans to investigate the legal ramifications of any recommendations made by the Task Force so that the legal concerns of the NCWM are adequately addressed.

April 1990 Meeting

The NCWM Task Force on Safety held meetings April 24-25, 1990 at the National Institute of Standards and Technology (NIST) in Gaithersburg, Maryland. Some of the activities during that meeting were as follows:

(1) Safety Library

The Task Force revised the main categories in the Safety Library from the original categories established during its January 1990 meetings. The categories were revised in accordance with the subject areas of the information received by the Task Force since January.

The Task Force continues to gather and compile information pertaining to safety in the workplace, particularly information pertaining to safety in the weights and measures workplace.

The Task Force plans to make a listing of the categories of information which will be distributed to NCWM members in September 1990 along with instructions on how to obtain the information.

(2) Examination Procedure Outlines

The Task Force performed a review of the EPO's found in NCWM Publication 12:

- Key areas of safety concern were identified in each EPO. Key words and phrases were developed to identify safety hazards/concerns; these key words will be included at the beginning of each EPO.
- A glossary of key words will be developed for inclusion at the back of Publication 12.
- A section will be included at the beginning of Publication 12 which will provide a basic safety reminder to the weights and measures official.
- A statement will be included at the beginning of each EPO to remind the inspector to read and be familiar with the safety section at the beginning of Publication 12.

The Task Force continues to work on the EPO's and plans to review final drafts at its next meeting in Fall 1990.

(3) Subcommittee on Safety

The Task Force believes that the most appropriate mechanism to ensure the continuance of safety awareness in the weights and measures community is to establish a permanent body within the NCWM to address safety. The Task Force will recommend that a subcommittee be established under the Education Committee to address safety concerns in the NCWM.

(4) Projected Lifespan of the Task Force

The projected lifespan of the Task Force remains consistent with that estimated in January 1990. The Task Force will hold a meeting in Fall 1990 and an additional meeting in Spring 1991. An update of the work of the Task Force will be provided for the interim meetings. The Task Force plans to finish its work by the July 1991 NCWM, at which time its final recommendations will be presented to the Executive Committee.

(5) Reference to Safety in NIST Handbook 44

The Task Force discussed the general lack of understanding of the weights and measures official of the safety regulations in place at a particular inspection location. By revising the EPO's to include safety information, the Task Force hopes to impress the importance of safety upon the weights and measures official. To further emphasize the importance of safe work practices and an awareness of existing safety requirements, the Task Force will recommend an addition to each code of Handbook 44, to consist of a brief statement to remind the inspector to review the safety procedures for the inspection process and to be aware of the safety regulations in place at the place of inspection.

Current Activities

At the request of the Task Force, the Liaison Committee arranged a meeting with a representative of the Occupational Safety and Health Administration. Representatives of the Task Force and the Liaison Committee met with OSHA representatives on July 9, 1990 at the Department of Labor. OSHA has indicated an initial willingness to provide assistance to the Task Force by providing input on the revisions of the EPO's. OSHA may send a representative to

Executive Committee

the next meeting of the Task Force. In addition to guidance in the revision of the EPO's, it is hoped that arrangements can be made with OSHA to perform an analysis of each inspection procedure.

The Task Force is pleased to note that interest and awareness in workplace safety continues to increase in the weights and measures community. Information pertaining to safety in the workplace continues to trickle in from various sources. The Task Force would like to make NCWM members aware that safety information is still welcome.

The Task Force plans to finalize the revisions to the EPO's and perform a review of the Standard Operating Procedures in NIST Handbook 145 at its meeting in Fall 1990.

Appendix F

SUMMARY, QUESTIONNAIRE ON CONFERENCE COSTS AND LOCATIONS

Responses to the questions in the Questionnaire may be generally summarized as follows:

Question #1 - Categories of respondents.

For purposes of analysis, four categories were considered: State Officials, Local Officials, Associate Members, and Guests.

The Guests' answers to questions #3, #4, and #5 were not included in the analysis.

Question #2 - Are you staying at the Westin?

In spite of the room rate, about 90% stayed at the Westin. We have no statistics on past years, but the data on the room pickup and registration (page seven) are fairly consistent.

Question #3 - If you are not staying at the Westin, why not?

In effect, the room rate was considered too high. However, the answers and comments on both the hotel and the city changed toward the end of the week. Written comments were to the effect that both choices were good, the hotel was first class, the lobby setup with lots of seating was great, lots to do in terms of restaurants and shopping.

Although Seattle was ranked fifth of the nine past meetings, the respondents who turned in their Questionnaires later in the week ranked Seattle 1st, 2nd, or 3rd in the past nine Annual meetings (there was a single low ranking). Had the earlier respondents' answers been similar to the later respondents, Seattle would have been second or third in the ranking.

Question #4 - Will you be reimbursed for expenses?

The vast majority of attenders are reimbursed for all expenses. The major problem seemed to be reimbursement for meals; however, those who answered "no" on this expense, the comments written in clearly showed that most attenders received \$20 or more per day.

Question #5 - Raise the registration fee as a step to getting lower room rates?

Nearly 62% answered no. Others wrote in comments to the effect that we should do what is best for the NCWM or continue doing what we are doing.

Question #6 - Rating of proposed future meeting locations - locations currently being considered.

Respondents appear to prefer popular tourist cities (e.g., Orlando, New Orleans, Nashville, Phoenix, D.C.) and generally rate northeastern cities low. It is clear that there is considerable opposition to Albany.

Hawaii was a dichotomy; it received either "excellent choice" or "avoid" votes. The comments clearly indicated that Hawaii is a preferred location except for the problems with cost (transportation) and perceived "vacation image as seen by bosses." "Avoids" tended to nullify "excellent choices."

What other locations do you recommend for future meetings?

This turned out to be a poor question because it was too general. The result is a scattering of selections with no clear "popular" locations unless the votes for Denver and San Diego are considered significant.

Question #7 - Rankings of past Annual Meeting locations/hotels.

Albuquerque came out clearly on top; sample comments included: a popular and unique vacation area, a very good hotel, and an interesting program.

Sacramento and Boston were close in second and third, followed by Washington and Seattle in fourth and fifth.

QUESTIONNAIRE ON CONFERENCE COSTS AND LOCATIONS
SUMMARY

		Yes	No
Are you staying at the Westin Hotel?	State Officials	45	12
	Local Officials	35	2
	Associate Members	76	3
	Subtotal	156	17
	Guests	19	17
	Total	175	20
Will you be reimbursed for the entire			
a. cost of your registration Fee?	State Officials	52	2
	Local Officials	34	2
	Associate Members	79	0
	Total	165	4
b. cost of your hotel?	State Officials	45	9
	Local Officials	28	9
	Associate Members	78	0
	Total	151	18
c. cost of meals/other?	State Officials	37	17
	Local Officials	28	8
	Associate Members	73	1
	Total	138	26
d. cost of transportation?	State Officials	50	4
	Local Officials	33	2
	Associate Members	78	0
	Total	161	6

In order to get a lower sleeping room rate for the meeting, the Conference would have to pay separately for the meeting room space. The cost for meeting rooms might approximate \$2000.00 per day. One way of offsetting the meeting room costs would be to raise the registration fee for the meeting.

		Yes	No
Raise the registration fee?	State Officials	20	33
	Local Officials	7	29
	Associate Members	35	38
	Total	62	100

The following cities are being considered for the Annual Meeting. On a scale of 1 to 5, where 1 = avoid and 5 = excellent choice, rate the following possible locations for future meetings. (For purposes of the ranking reported below, the scorers gave the following values to the 1 through 5 ratings; 1 = -10 points, 2 = -5 points, 3 = +5 points, 4 = +10 points, 5 = +15 points).

New Orleans, Louisiana	1580 points	Indianapolis, Indiana	910 points
Orlando, Florida	1540 points	Chicago, Illinois	675 points
Phoenix, Arizona	1525 points	Kansas City, Missouri	620 points
Nashville, Tennessee	1510 points	Hartford, Connecticut	595 points
District of Columbia	1320 points	Columbus, Ohio	350 points
Philadelphia, Penna	1295 points	Albany, New York	- 24 points
Hawaii (non specific)	1020 points		

Please rank the city/hotel combinations of past Annual Meetings. (For purposes of scoring, values were given to ranking as follows: #1 (best) = 40 points, 2 = 35 points, 3 = 30 points, 4 = 25 points, 5 = 20 points, 6 = 15 points, 7 = 10 points, 8 = 5 points, 9 = 0 points.

City *	1	2	3	4	5	6	7	8	9	Total points
Seattle, WA(140)	24	27	14	15	21	14	13	0	6	3490
Albuquerque, NM(104)	32	14	16	16	7	9	4	5	1	3365
Washington, DC (108)	22	20	14	15	10	13	7	5	2	2865
Grand Rapids, MI(139)	18	15	10	14	25	13	11	29	4	2795
Boston, MA(95)	30	24	16	8	5	4	3	3	2	2750
Sacramento, CA(85)	16	17	29	5	9	3	5	0	1	2505
Atlanta, GA(83)	1	2	7	16	12	16	12	16	1	1405
Little Rock, AK(117)	2	4	9	7	10	8	5	11	61	1090
St. Louis, MO(69)	4	2	3	5	6	14	13	12	10	1075

* Not all respondents were in attendance at all of the nine past Annual Meetings. Note that the number rating generally was less for each past year (i.e., 140 ranked Seattle, 139 ranked Grand Rapids, 117 ranked Little Rock, 108 ranked Washington, etc). If the rankings are adjusted to match the number of respondents ranking Seattle, 140, the relative rankings change. For example, since the total points for Seattle is 3490 based on 140 responders, the adjusted total points for Albuquerque is then 140/104 times 3365 = 4530. Making the same adjustments for the others, the adjusted rankings are:

1. Albuquerque	4530	4. Washington	3714	7. Atlanta	2370
2. Sacramento	4125	5. Seattle	3490	8. St. Louis	2181
3. Boston	4053	6. Grand Rapids	2815	9. Little Rock	1304

ADDITIONAL RECOMMENDED LOCATIONS FOR ANNUAL MEETING

Anchorage, AK	5	Jackson Hole, WY	2	Puerto Rico	2
Atlanta, GA	5	Kansas, MO	3	Reno, NV	1
Amelia Island, FL	1	Las Vegas, NV	4	Richmond, VA	1
Baltimore, MD	4	Little Rock	1	Salt Lake City, UT	3
Boise, ID	1	Los Angeles/ Anaheim, CA	1	San Antonio, TX	5
Boston, MA	8	Memphis, TN	1	San Diego, CA	17
Bozeman, MT	1	Milwaukee, WI	1	San Francisco, CA	5
Cape Cod, MA	2	Minneapolis, MN	6	Santa Fe, NM	5
Charlestown, SC	7	Monterey, CA	3	St. Louis, MO	1
Charlotte, NC	2	Nashville, TN	6	Tucson, AZ	1
Chicago, IL	3	New Orleans, LA	1	Virgin Islands	1
Cincinnati, OH	4	North Carolina	1	Washington, DC	5
Clearwater, FL	2	Nome, AK	2	Williamsburg, VA	3
Dallas/Ft. Worth	5	Omaha, NE	1		
Denver, CO	13	Orlando, FL	1		
Ft. Lauderdale, FL	1	Palm Springs, CA	1		
Hartford, CN	3	Phila., PA	2		
Hawaii	2	Phoenix, AZ	4		
Hilton Head, SC	3	Portland, ME	5		
Indianapolis, IN	2	Portland, OR	5		

January 16, 1990

Appendix G

TREASURER'S INTERIM REPORT FISCAL YEAR 74 (1989-1990)

CASH ON HAND	June 30, 1989	<u>\$ 90,942.70</u>
--------------	---------------	---------------------

BUDGET RECEIPTS:

\$ 30,000	1.1	Registrations	<u>\$17,385.00</u>	
67,550	1.2	Memberships	<u>46,520.00</u>	
6,500	1.3	Training Modules	<u>6,517.00</u>	
3,000	1.4	Interest	<u>2,089.69</u>	
1,000	1.5	Promotional	<u>-0-</u>	
5,000	1.6	Special Events	<u>5,777.00</u>	
300	1.9	Miscellaneous	<u>-0-</u>	
113,350		Total Receipts		<u>78,288.69</u>

Total Income	<u>\$ 169,231.39</u>
--------------	----------------------

DISBURSEMENTS:

\$14,000	2.0	Annual Meeting	<u>11,285.94</u>	
4,000	3.0	Interim Meeting	<u>329.00</u>	
20,000	4.0	Committee Ops.	<u>7,091.92</u>	
18,000	5.0	Special Programs	<u>6,326.16</u>	
12,550	6.0	Chmns. Expenses	<u>6,705.92</u>	
6,000	7.0	Membership Prog.	<u>1,900.65</u>	
6,000	8.0	Printing & Pubs.	<u>9,945.07</u>	
12,500	9.0	Administration	<u>4,060.49</u>	
5,000	10.0	Special Events	<u>8,036.18</u>	
1,300	11.0	Promotional	<u>684.25</u>	
14,000	12.0	Training Modules	<u>12,204.43</u>	
113,350		Total Disbursements		<u>\$ 68,570.01</u>

BALANCE	<u>\$ 100,661.38</u>
---------	----------------------

Bank Accounts

New York	<u>\$47,222.50</u>
Maryland	<u>314.24</u>
CD #1	<u>22,451.12</u>
CD #2	<u>10,673.52</u>
CD #3	<u>20,000.00</u>

BALANCE	<u>\$ 100,661.38</u>
---------	----------------------

GRANT ACCOUNT	<u>\$ 2,482.42</u>
---------------	--------------------

SUBMITTED: _____
Charles A. Gardner, Treasurer



Report of the Laws and Regulations Committee

Sidney A. Colbrook, Chairman
Weights and Measures Program Manager
Illinois Department of Agriculture

200

Introduction

This is the final report of the Laws and Regulations Committee for the 75th Annual Meeting of the National Conference on Weights and Measures (NCWM). It is based on the Interim Report (NCWM Publication 16), the Addendum Sheets issued at the meeting, and the actions taken by the membership at the meeting.

Table A identifies items in the Report by Reference Key Number, item title, and page number. The first three digits of the Reference Key Numbers of the items in the Committee's report are assigned from the subject series listed below. Not all subject series will appear in the report. The digits after the hyphen are assigned at the time of assembly of the Interim Meeting agenda in the order of the appearance of the subject of the proposal in the handbooks. Several item numbers are out of sequence with their appearance in the Final Report because the Committee recommended revisions or additions to sections or paragraphs other than those originally proposed. In addition, several items were divided into parts after their numbers were assigned: these are delineated with the letters "A," "B," and so on, after the number, for example "221-1A." The titles of voting items are indicated with a "V" after the item number. At the Annual Meeting, the committee grouped the less controversial voting items into a consent calendar. These are marked with "VC." In the Report, the key text upon which a vote is to be taken is also highlighted by **bold face print**. Items marked with an "I" after the reference key number are information items. The items marked with a "W" were withdrawn by the Committee.

The Committee was assisted by Ms. Janice Oliver, representing the U.S. Food and Drug Administration, and Mr. Bret Smart, representing the Federal Trade Commission. Mr. Gilles Vinet, from the Legal Metrology Branch of Canada's Consumer and Corporate Affairs, also participated in all the Committee's deliberations. The Committee wishes to express its appreciation for their contributions.

Much of the Report contains recommendations to revise or amend National Institute of Standards and Technology (NIST) Handbook 130, 1990 edition, "Uniform Laws and Regulations;" NIST Handbook 133, Third Edition, "Checking the Net Contents of Packaged Goods;" or NCWM Publication 3, "NCWM Policy, Interpretations, and Guidelines." Proposed revisions are shown in bold face print by crossing out (~~crossing-out~~) what is to be deleted, and underlining what is to be added. Entirely new paragraphs proposed are designated as such and also are shown in bold face print.

Subject Series

HANDBOOK 130 - General	210 Series
LAWS	220 Series
Uniform Weights & Measures Law (UWML)	221 Series
Uniform Weighmaster Law (UWL)	222 Series
Uniform Motor Fuel Inspection Law (UMFIL)	223 Series
REGULATIONS	230 Series
Uniform Packaging and Labeling Regulation (UPLR)	231 Series
Uniform Regulation for the Method of Sale of Commodities (UMSCR)	232 Series
Uniform Unit Pricing Regulation (UUPR)	233 Series
Uniform Regulation for the Voluntary Registration of Servicepersons & Service Agencies for Commercial Weighing & Measuring Devices (URVRS)	234 Series

Subject Series (Continued)

REGULATIONS

Uniform Open Dating Regulation (UODR)	235 Series
Uniform Regulation for National Type Evaluation (URNTE)	236 Series
Uniform Regulation for Motor Fuel (URMF)	237 Series

HANDBOOK 133	240 Series
--------------	------------

OTHER ITEMS	250 Series
-------------	------------

Table A
Reference Key Items and Index

Reference Key No.		Title of Item	Page
220		Handbook 130 - General	78
220-1	VC	Section V. Interpretations and Guidelines	78
221		Uniform Weights and Measures Law	79
221-1A	VC	1.2. Weight; Include Services in Definition	79
221-1B	I	Other Sections That Should Refer to Services	79
221-1C	VC	1.2. Weight; Drained Weight for Packages	80
221-1D	I	1.2. Weight; Wiping Cloths	80
221-1E	VC	1.2. Weight; Primary Mill Paper	81
221-2	VC	1.X. Random Weight Package	81
221-3	VC	15. Misrepresentation of Quantity	82
222	I	Uniform Weighmaster Law	82
231		Uniform Packaging and Labeling Regulation	82
231-1	I	2.X. Package	82
231-2	VC	2.X. Spot Label; 2.XX. Header Strip; 11.X. Spot Label; 11.XX. Header Strip	83
231-3	I	2.5. Label	85
231-4	I	2.8. Multi-Unit Package	85
231-5	VC	3.1. Declaration of Identity: Consumer Package; 4. Declaration of Identity: Nonconsumer Package; Clarification of "Identity"	85
231-7	VC	6.1. General	86
231-8	I	6.5.(b) Inch-Pound Units: Weight, Measure; Reference Temperature for Paint	86
231-9	VC	6.5.(b) Inch-Pound Units: Weight, Measure; Reference Temperature for Refrigerated Products	86
231-10	VC	6.5.1. Symbols and Abbreviations; Add Abbreviations	87
231-11A	I	6.11.3. Rounding; How to Round for the Net Weight Declaration	87
231-11B	VC	2.13.4. Declaration of Weight/Polyethylene Sheeting and Film	88
231-12	I	10.5. Combination Packages and 10.6. Variety Packages	89
231-13	I	10.X. Mechanical Pump Dispensers	89

Table A (Continued)

Reference Key No.		Title of Item	Page
231-14	VC	11.23. Camera Film	90
231-15	I	11.28. Commodities' Variable Weights and Sizes	91
231-16	VC	11.29. Packaged Commodities Sold by Count	92
232		Uniform Regulation for the Method of Sale of Commodities	92
232-1	I	1.1. Berries and Small Fruits; Define "Small Fruits"	92
232-2A	I	1.5.1. In Combination with Other Foods	93
232-2B	I	1.5.2.3. Fresh Oysters, Clams, Mussels, or Other Mollusks Removed from the Shell	93
232-3	I	1.5.X. Meat, Poultry, Fish, and Seafood -- Packaged with Other Packages of Food	94
232-4	V	1.7.1. Factory Packaged and Hand-Packed Ice Cream and Similar Frozen Products.	94
232-5	I	1.9. Advertising and Price Computing of Bulk Food Commodities	96
232-6	W	1.12. Ready-to-Eat Food	96
232-7	I	1.X. Method of Sale for Fresh Fruits and Vegetables	97
232-8	W	1.X. Method of Sale for Salads	97
232-9	W	1.X. Method of Sale for Bakery Items	97
232-10	I	Method of Sale Requirements in the U.S. and in Canada	97
232-11	I	Vacuum-Packaged Cans of Coffee	99
232-12	VC	2.10.3.(a) and (b) Quantity (of Softwood Lumber)	99
232-13	VC	2.14. Insulation	100
232-14	VC	2.16. Liquefied Petroleum Gas Cylinder Tare Weights; Compressed or Liquefied Gases in Cylinders	100
232-15	I	2.16. Liquefied Petroleum Gas Cylinder Tare Weights; Acetylene	102
232-16	I	2.20. Gasoline-Alcohol Blends; Add Labeling of All Oxygenates	102
232-17	I	2.22. Liquid Oxygen Used for Respiration	104
232-18	I	2.X. Products Dispensed from Mechanical Devices	104
232-19	VC	2.X. Animal Bedding	104
240		Handbook 133: Package Testing	105
240-1	I	Proposed Sampling Plans and Smaller MAV's	105
240-2	VC	3.11.4. Exhausting the Aerosol Container; Clarify Instructions	105
240-3	I	Moisture Loss for Ice-Packed Poultry and Other Meat and Poultry Items	106
240-4	I	Moisture Loss for Pet Foods	106
240-5	I	Moisture Loss for Pasta	107
240-6	I	Section 4.X. Hand-Packed Ice Cream	107
240-7	I	Polyethylene/Test Methods for Bags	108

**Table B
Appendices**

Appendix	Title	Reference Key No.	Page
A	Uniform Weighmaster Law	222	109
B	NCWM Publication 3, 2.3.2. Fresh Fruits and Vegetables	231-10, 232-1	116
C	Meat and Poultry Products	232-2A	119
D	Test Method for Compressed Gases	232-14	127

Order of Presentation

The report was presented to the membership as follows:

1. The Consent Calendar was presented. Item 232-4 had been proposed by the Committee as a Consent Calendar item, but was subsequently made a separate voting item by the Committee. The Consent Calendar was then adopted.
2. Item 232-4 was voted upon.
3. The report in its entirety was then ratified.

Table C

Voting Results

Reference Key No.	House of State Representatives		House of Delegates		Results
	Yes	No	Yes	No	
Consent Calendar	46	0	63	0	Passed
232-4	45	0	67	0	Passed
Entire Report	46	0	71	0	Passed

Details of All Items

- 220 Handbook 130 - General**
- 220-1 VC Section V. Interpretations and Guidelines**

(This item was adopted as part of the consent calendar.)

Background: The guidelines that appear as Section 2 of NCWM Publication 3 were originally part of H130. It had

been thought that States could adopt H130 in its entirety by reference (as States were already doing with Handbook 44) if it contained only legal requirements, not guidelines or interpretations. The guidelines section was therefore removed from H130. It was later determined that State executive agencies could not adopt laws by reference, but could adopt regulations by reference if a law permitted it. Several sections (rather than one encompassing section) were therefore added to the Uniform Weights and Measures Law in order to empower State Weights and Measures agencies to adopt specific regulations in H130 by reference. States do not adopt the entire Handbook 130 by reference because the document consists both of laws (needing legislative adoption) and regulations (which can be adopted by reference).

Having to consult Publication 3 for further information on legislative history or interpretation of specific sections is an unnecessary complication; ease of use and reference can be enhanced by including the guidelines in Handbook 130.

Committee Recommendation: Publish Section 2, "Uniform Laws, Regulations and Commodity Control," of NCWM Publication 3, "NCWM Policy, Interpretations, and Guidelines," as an appendix in NIST Handbook 130 (H130).

221 Uniform Weights and Measures Law

221-1A VC 1.2. Weight; Include Services in Definition

(This item was adopted as part of the consent calendar.)

Background: Section 1.2. is a fundamental definition in the Uniform Weights and Measure Law. It defines weight as meaning net weight "in connection with any commodity." The question has been asked whether this definition applies to services when charged on the basis of weight, for example, by moving companies, laundries, or package shippers. The Committee is unanimous in its opinion that this definition is also intended to encompass services. For example, if a laundry charges by weight, to be in compliance it may charge only for the weight of the clothing to be cleaned (and not for the wrapping or bag into which the clothes are placed). A moving service, when charging by weight, may charge only for the weight of the goods placed into the truck (and not for the tare weight of the truck). Similarly, a shipping or mailing service charging by weight may charge only for the weight of the package to be shipped.

The pricing practices of services are not required to be by weight, measure, or count. Furthermore, the term "net weight" when used in conjunction with services does not mean that a service (such as a shipper) may charge only for the goods inside a package: the service is the transportation of a total package, not just the goods inside the package; that is, the service of shipping includes the shipping of the packing materials. Charging for the total weight of the package does not mean that they are selling a service by gross weight.

Black's Law Dictionary (Fifth Edition) defines commodities as "those things which are useful or serviceable, particularly articles of merchandise movable in trade; goods, wares, and merchandise of any kind; movables, articles of trade or commerce; movable articles of value; things that are bought and sold..." Random House College Dictionary defines commodity as "1. something of use, advantage, or value; 2. an article or trade or commerce, esp. a product as distinguished from a service." These definitions require that the Committee specifically add the performance of labor (service) in all transactions by measure in the UWML. The Committee was not able to reach consensus on appropriate wording for sections other than 1.2. Therefore, see Item 221-1B, which reports on further work that the Committee intends to address at future meetings.

Committee Recommendation:

Revise the UWML to clarify that weights and measures regulation applies to both things and services, when a quantity is determined:

1.2. Weight. – The term "weight" as used in connection with any commodity or service means net weight.

221-1B I Other Sections That Should Refer to Services

In its study of the UWML, the Committee notes that several of its sections already specifically refer to "service":

Section 11.(b) "...unfair or deceptive dealing by weight or measure in any commodity or service..."

Section 12.(j)(1) "...in determining the weight, measure, or count of commodities or things sold..." (2) "...in computing the basic charge or payment for services..."

Section 16. "no person shall misrepresent the price of any commodity or service sold, offered,..."

Other sections are silent as to service, but have often been interpreted as including service even though not specifically mentioned. For example, Section 18. Sale from Bulk has been used to require a receipt in a waste-hauling service charging by weight when neither party to the transaction is present when the weighing is made.

In addition, Section 12. Powers and Duties of the Director is silent in subsection (n) concerning the power to prescribe by regulation methods of sale for services when those services are priced by weight, measure, or count.

The Committee will therefore discuss the following preliminary drafts of revisions to the UWML. Regional weights and measures associations are encouraged to provide their recommendations and suggestions.

1.8. Sale from Bulk. -- The term "sale from bulk" means the sale of commodities or services when the quantity is determined at the time of sale.

1.10. Net Weight. --

(a) Commodities. -- The term "net weight" means the weight of a commodity excluding any materials, substances, or items not considered to be part of the commodity. Materials, substances, or items not considered to be part of the commodity include, but are not limited to, containers, conveyances, bags, wrappers, packaging materials, labels, individual piece covering, decorative accompaniments, and coupons.

(b) Services. -- Materials considered to be part of a service may or may not include packaging materials, depending upon the type of service that is being purchased. It shall in no instance include the weight of the conveyance used to transport goods if the service is transportation of goods.

12(n) Prescribe, by regulation, the appropriate term or unit of weight or measure to be used, whenever he or she determines ~~in the case of a specific commodity~~ that an existing practice of declaring the quantity by weight, measure, numerical count, or combination thereof, does not facilitate value comparisons by consumer, or offers an opportunity for consumer confusion.

221-1C VC 1.2. Weight; Drained Weight for Packages

(This item was adopted as part of the consent calendar.)

Background: Section 1.2. needs clarification because it mixes the general concept of sale by net weight, which could be of a commodity or service (see Item 221-1A), with the concept of drained weight for packages. The clause beginning with "...except where..." should be separated from the first part of the sentence. After some study, the Committee believes that the term "label" in Section 1.2 defining "weight" makes this clause apply only to packaged products; however, items could be sold from bulk by drained weight.

Committee Recommendation: Revise Section 1.2. as follows:

1.2. Weight. -- The term "weight" as used in connection with any commodity means net weight. When a commodity except where the label declares that the product is sold by drained weight, the term means net drained weight.

221-1D I 1.2. Weight; Wiping Cloths

Background: The Conference has been on record since the 1950's concerning the illegal practice of selling wiping cloths by gross weight. Several State weights and measures agencies have recently discovered that the practice of selling wiping cloths by gross weight continues in this industry. Section 1.2. of the Uniform Weights and Measure Law defines weight as meaning net weight in any transaction. In addition, Section 7.2. of the UPLR requires that

nonconsumer packages bear a declaration of the net quantity of contents. All States have laws which similarly require net weight. The Committee has transmitted this information to the International Association of Wiping Cloth Manufacturers. The net weight of wiping cloths must appear on package labels, invoices, and any other sales literature that refer to the quantity of wiping cloths, if the quantity is by weight. (Some nonwoven wiping cloths are sold by count and dimensions.) It is not appropriate to label or sell by the gross weight of the box or bale (that is, the weight of the box or bale combining the weight of the wiping cloths with the weight of the container), nor to provide the percentage of the gross weight that is tare without also declaring the net weight of the wiping cloths.

Committee Recommendation: No change to existing requirements; transmit letter to wiping cloth manufacturers informing them of applicable State weights and measures requirements.

221-1E VC 1.2. Weight; Primary Mill Paper

(This item was adopted as part of the consent calendar.)

Interpretation: Nonconsumer sales of "primary mill paper" were discovered by weights and measures officials to be labeled and invoiced on what was called a "gross weight" basis. Primary mill paper is produced for commercial or industrial companies for subsequent additional processing, such as paper for newspaper or magazine publishers, or sanitary tissue manufacturers. The primary mill paper is cut from "parent rolls", but is still a commercial-sized item weighing from several hundred to several thousands of pounds.

The key to understanding the longstanding trade practice is that the purchaser of such paper specifies not only the quality of the paper being purchased, such as the thickness, surface coating, etc., but the purchaser also specifies the core around which the paper is to be wound, the type of overwrap, the number of overwraps, and such other requirements that will ensure receipt of the primary mill paper in proper condition for subsequent processing. The weight of the core and wrapping is approximately one percent of the gross weight. It is recycled by the purchaser in his own or other paper recovery or reuse systems.

Having reviewed the practices in the industry in the specification and purchasing of primary mill paper, the Committee concludes that the true product is the paper plus the packaging (in order to assure maintenance of quality) and an appropriate core (to ensure a fit on the recipient's equipment). Therefore, in the opinion of the Committee, the sale of primary mill paper is not at all on a gross weight basis. This is and has been a misnomer. The true identity of the purchased product has been misunderstood by weights and measures authorities and further compounded by industry use of the term "gross weight". The product is the primary mill paper plus the core and overwrap specified by the purchaser.

The Committee therefore believes that the industry should review its invoicing and labeling to clarify that the weight of the specified product is the weight of the primary mill paper, core, and overwrap. Although this weight is the gross weight of the entire item as produced and shipped, it is the net weight of the item as specified by the purchaser.

This interpretation applies only to primary mill paper and is not intended to be applied to other nonconsumer products ordered by specification: it is a narrow interpretation applying to the specific method of sale in this trade, where the service of packaging and the packaging is part of the purchase.

Committee Recommendation: Add the above interpretation to NCWM Publication 3, "Policy, Interpretations, and Guidelines."

221-2 VC 1.X. Random Weight Package

(This item was adopted as part of the consent calendar.)

Background: The term "random weight package" is used in UWML Section 20. Declarations of Unit Price on Random Weight Packages, but is not separately defined. (It is defined in Section 20 using the same words: "random weight.") There should be a definition for random weight package in the UWML and it should be consistent with that for "random package" in the UPLR. The definition for "random package" in the UPLR tracks federal regulations which define it only as applying to consumer packages.

Committee Recommendation: Add a definition for "random weight package" to the UWML using the definition of "random package" in the UPLR as its basis (but generalizing the definition to include more than consumer packages):

1.X. Random Weight Package. -- A package that is one of a lot, shipment, or delivery of packages of the same commodity with no fixed pattern of weights.

In addition, revise Section 2.4. of the UPLR editorially, to track the wording recommended above. Modification to Section 2.4. is as follows:

2.4. Random Package. -- A package that is one of a lot, shipment, or delivery of packages of the same consumer commodity with ~~various weights; that is, packages of the same consumer commodity with~~ no fixed pattern of weights.

221-3 VC 15. Misrepresentation of Quantity

(This item was adopted as part of the consent calendar.)

Background: Section 16. Misrepresentation of Pricing prohibits misrepresenting the price "in any manner calculated or tending to mislead or in any way deceive a person." This is important language that does not exist in Section 15. Many States have commented that Section 16 is much more useful to cite to prevent obviously misleading trade practices, and have said that it would be very useful to have this tool in Section 15, which is the section prohibiting misrepresentation of quantity.

Committee Recommendation: Amend Section 15 as follows:

No person shall:

(a) sell, offer, or expose for sale less than the quantity ~~he represents~~ represented, nor

(b) take any more than the represented quantity ~~he represents~~ when, as buyer, he/she ~~he~~ furnishes the weight or measure by means of which the quantity is determined, nor

(c) represent the quantity in any manner calculated or tending to mislead or in any way deceive another person.

222 I Uniform Weighmaster Law

Background: At the 74th Annual Meeting, the NCWM adopted a revised Uniform Weighmaster Law. The Executive Secretary, in his capacity as editor, subsequently recommended significant rewording of the rather archaic language that still remained. The Committee has reviewed these recommendations in detail and made a few necessary modifications to the Executive Secretary's draft so that the Uniform Weighmaster Law that appears in Appendix A is a significant editorial improvement, but represents no substantive change to the Law.

Committee Recommendation: Replace the Uniform Weighmaster Law as printed in the 1990 edition of Handbook 130 with the editorially revised version in Appendix A.

231 Uniform Packaging and Labeling Regulation

231-1 I 2.X. Package

Background: Although "commodity in package form" is defined in the UPLR, "package" is not. "Package" is defined in the UWML consistent with the definition of commodity in package form in the UPLR. However, weights and measures officials have found it difficult to guide the layman who must comply with the UPLR to look in several places for the definitions. It would be useful if the UPLR were a more self-contained document.

Committee Recommendation: As a result of the discussion at the Interim Meeting, it was the recommendation of the Committee to add the definition for "package" that appears in the Uniform Weights and Measures Law to the UPLR Section 2. Definitions as follows:

2.X. Package. -- Any commodity put up or packaged in any manner in advance of sale in units suitable for either wholesale or retail sale.

Material provided to the Committee before the Annual Meeting suggested that the definition in the Interim Report could be improved. For example, the Northeastern Weights and Measures Association recommended that the word "packaged" not be used in the definition for package. In addition, the Committee believes that the term "put up" needs defining. It was not the original intent of the Committee to revise the definition of package, but merely to add the definition from the Uniform Weights and Measures Law to the Uniform Packaging and Labeling Regulation. This item will therefore be carried over. Two recommendations have been provided. The Northeastern Weights and Measures Association suggested (and the Committee further revised) the following:

2.X. Package. -- Any commodity premeasured, wrapped or unwrapped, in any manner in advance of sale in units suitable for either wholesale or retail sale.

Ohio provided the following alternative:

2.X. Package. -- Any commodity whose quantity is determined in any manner in advance of sale in units suitable for either wholesale or retail sale.

Any changes in the definition would have to be incorporated in the Uniform Weights and Measures Law. The regional weights and measures associations are encouraged to discuss these alternatives and provide their own opinions concerning the best definition.

231-2 VC 2.X. Spot Label; 2.XX. Header Strip; 11.X. Spot Label; 11.XX. Header Strip

(This item was adopted as part of the consent calendar.)


Background: Both the Food and Drug Administration (FDA) and the Federal Trade Commission (FTC) have issued interpretations and guidelines concerning the special types of labels called "spot labels" and "header strips." The Committee recommends that the NCWM incorporate these interpretations into the UPLR so that States may also adopt these definitions for national uniformity. New paragraphs under Section 11. Exemptions are also proposed. These definitions have been reviewed by both FDA and FTC, to which the Committee wishes to express its appreciation for their assistance. The definition for spot label was editorially reworded by the Central Weights and Measures Association.

Committee Recommendation: Add definitions for spot label and header strip to Section 2. and labeling exemptions for spot labels and header strips to Section 11.:

2.X. Spot Label. -- A spot label is a label that covers only a small portion of the surface of a principal display panel of a package; the entire portion of the principal display panel outside the area of the label contains no printed or graphic matter of any kind. A spot label may contain all required labeling information on it (identity, responsibility, and net contents), but it must have the identity and net contents. See Section 11.X. for net contents placement exemption for a spot label. Also see figure below.

2.XX. Header Strip. -- A header label or header strip is a label that is attached across the top of a transparent or opaque bag or other container that bears no other printed or graphic material. See Section 11.XX. for net contents placement exemptions. See also the figure below.

11.X. Spot Label. -- The declaration of quantity of the contents of a package is exempt from Section 8.1.1. Location, requiring the quantity declaration to appear in the bottom 30 percent of the principal display panel, as long as the declaration of quantity appears in the lower 30 percent of the spot label. In no case may the size of the spot label be used to determine the minimum type size; see Section 8.2. for this determination.



11.XX. Header Strip. -- The declaration of quantity of the contents of a package is exempt from Section 8.1.1. Location, requiring the quantity declaration to appear in the bottom 30 percent of the principal display panel, as long as the declaration of quantity appears in the lower 30 percent of the header strip or header label. In no case may the size of the header strip be used to determine the minimum type size; see Section 8.2. for this determination.

231-3 I 2.5. Label

Background: The Northeastern Weights and Measures Association recommended that the definition of label be modified to remove the phrase "adjacent to:"

Label. -- Any written, printed, or graphic matter affixed to, applied to, attached to, blown into, formed, molded into, embossed on, or appearing upon ~~or adjacent to~~ a consumer commodity, or a package containing any consumer commodity...

The present definition permits a sign to be posted with required label information. The Association contended that it is not reasonable for required information to be separated from the commodity since the purchaser carries the package away from the sign. For example, the present definition allows a gift package to appear with a sign declaring the net contents, rather than requiring the net contents declaration to be affixed to the package.

Committee Recommendation: Although the criticism outlined by the Northeastern Association is valid, the Committee members recognize reasons to preserve the present definition. For example, farmers' markets vending produce in bags can post a sign with all required declarations, rather than affix a label to each bag. A department store selling linens can post a sign with dimensions and other label requirements without affixing a label to each linen item. Since the definition of commodity in package form encompasses items that are not enclosed in a package, there is a need to permit an adjacent label, not just one affixed to the item. The Committee believes that weights and measures officials would prefer the option of permitting additional signage with required labeling information, rather than have to declare a packaged product off-sale because its labeling is incomplete. The Committee therefore recommends no change.

231-4 I 2.8. Multi-Unit Package

This was Item 231-4 in the Report of the 74th NCWM 1989.

Background: Bags of Halloween candy containing multiple packages of single-serving candies are labeled by weight. At least one packager labels a count on the back of its packages as a supplemental statement of quantity. This permits the purchaser to know how many servings are contained in the package. These bags of candy are not multi-unit packages because the individual serving-size packages are not labeled for individual sale.

The Committee explored two possibilities: (1) require that a declaration of quantity in terms of weight be combined with an appropriate declaration of count unless a declaration of weight alone is fully informative (already in Section 6.4.1. of the UPLR). The argument in favor of this interpretation is that, since these candies are purchased to give away to numbers of children, count is required. However, since the packager controls the total package quantity by weight, only an approximate count can be provided; (2) petition the Food and Drug Administration to change the definition of multi-unit package.

It was generally agreed that the addition of count either as a net contents declaration on the principal display panel or as a supplemental statement should be encouraged, but should remain voluntary. Declaration by count is not required for sale of other foods competing for purchase for Halloween giving, such as oranges or apples. In addition, special labeling should not be required for the consumer for only one specific holiday. The Committee welcomes additional comments or consumer survey data suggesting whether additional net contents information is needed.

Committee Recommendation: No change to the existing definitions and requirements.

231-5 VC 3.1. Declaration of Identity: Consumer Package; 4. Declaration of Identity: Nonconsumer Package; Clarification of "Identity"

(This item was adopted as part of the consent calendar.)

Items 231-5 and 231-6 as they appeared in the agenda for the Interim Meeting have been combined into a single voting item. Therefore, there is no Item 231-6.

Background: At the present time, the UPLR only requires that a statement of identity appear on the principal display panel identifying the commodity "by its common or usual name, description, generic term, or the like." In order to specifically prohibit such practices as labeling a package containing a soil amendment with less than 5% cow manure as "cow manure," requirements such as those contained in FTC regulations (16CFR 500.4) prohibiting misleading or deceptive names should be incorporated.

Moreover, both FDA and FTC regulations for consumer commodities specify that the identity and quantity be declared separately. For example, if no change were made to State requirements, a problem might arise if a packager followed State requirements as presently written and listed both the identity and count of paper napkins in a single statement on the principal display panel, such as : "250 soft white paper napkins." This is prohibited under FTC requirements.

Committee Recommendation: Revise Sections 3.1. and 4. as follows:

3.1. Declaration of Identity: Consumer Package. -- A separate declaration of identity¹ on a consumer package shall appear on the principal display panel, and shall positively identify the commodity in the package by its common or usual name, description, generic term, or the like: not be misleading or deceptive. The identity shall be in terms of:

(a) the name specified in or required by any applicable Federal or State law or regulation, or in the absence of this,

(b) the common or usual name, or in the absence of this,

(c) the generic name or other appropriate description, including a statement of function (such as "cleaning powder").

4. Declaration of Identity; Nonconsumer Package. -- A declaration of identity¹ on a nonconsumer package shall appear on the outside of a package and shall ~~positively identify the commodity in the package by its common or usual name, description, generic term, or the like:~~ not be misleading or deceptive. The identity shall be in terms of:

(a) the name specified in or required by any applicable Federal or State law or regulation, or in the absence of this,

(b) the common or usual name, or in the absence of this,

(c) the generic name or other appropriate description, including a statement of function (such as "cleaning powder").

231-7 VC 6.1. General

(This item was adopted as part of the consent calendar.)

Background: A "dual declaration of quantity" in Section 6.1. is a misleading term since there is also a "dual quantity declaration" in other sections of the UPLR. A combined metric and inch-pound quantity statement is not a "dual quantity declaration" as described in other sections of the UPLR and in Federal requirements; therefore, the current terminology needs to be revised.

Committee Recommendation: Revise Section 6.1. as follows:

6.1. General. -- The metric and inch-pound systems of weights and measures are recognized as proper systems to be used in the declaration of quantity. Units of both systems may be presented in a ~~dual~~ declaration of quantity.

231-8 I 6.5.(b) Inch-Pound Units: Weight, Measure; Reference Temperature for Paint

Background: The Committee was informed that an ASTM standard D16-84, "Standard Definitions of Terms Relating to Paint, Varnish, Lacquer, and Related Products," has been developed by the paint industry, and that it defines the U.S. gallon as "a volume equal to 231 cu in. Paint, varnish, lacquer, and related products are measured at 77 °F (25 °C)." Section 6.5.(b) of the UPLR defines the declaration of quantity in terms of the U.S. gallon "...and shall express the volume at 68 °F" [(20 °C) in Section 6.6.(b)]. Forty-seven States have adopted these sections of the UPLR. Since this is a regulation in 47 States, any paint manufacturer who uses the ASTM D16-84 definition at 77 °F could find his product ordered off-sale for short measure. (As much as a 15 mL difference in volume will result for compounds formulated with certain solvents.)

Committee Recommendation: No change to the UPLR. The Committee's position has been transmitted to members of the National Paint and Coatings Association and the Chairman of ASTM D-1 Subcommittee on Definitions.

231-9 VC 6.5.(b) Inch-Pound Units: Weight, Measure; Reference Temperature for Refrigerated Products

(This item was adopted as part of the consent calendar.)

Background: The State of California and the Office of Weights and Measures requested an interpretation from the FDA concerning the meaning of the reference temperatures for refrigerated products [in Section 6.5.(b) and 6.6.(b) in the UPLR and 21CFR 101.105 (b)(2)(ii) in FDA regulations]. FDA's interpretation, with which the Committee concurs, is that the reference temperature of 40 °F (4 °C) applies only to products that must be refrigerated in order

to maintain product quality, rather than to items, such as carbonated soft drinks, that are refrigerated for the convenience of the purchaser.

Committee Recommendation: Revise Section 6.5.(b) and 6.6.(b) as follows:

...except also in the case of a commodity that is normally sold **must be maintained** in the refrigerated state...

Also add the following guideline to NCWM Publication 3:

Guideline: The Committee also discussed how an inspector could decide whether a product under refrigeration is required to be maintained under refrigeration. The following guidelines are provided:

1. The traditional food items that normally require refrigeration and are found in refrigerated cases will not ordinarily have any statement about requiring refrigeration. These items include milk, orange juice, and similar products. They may be tested at any temperature at, above, or below their reference temperature of 40 °F (4 °C) because such products are at their maximum density at their reference temperature, and the volume of such products will always increase at higher or lower temperatures. Thus any errors made by not measuring at the exact reference temperature will be in the favor of the packer.
2. Food items that normally require refrigeration, but which are processed so as not to require refrigeration prior to opening, will have "refrigerate after opening" or similar wording on the label. Such items as milk and orange juice can be found in this category as well as in the "refrigeration required" category. The two categories can be distinguished by the "refrigerate after opening" statement, which calls for testing at or above their reference temperature of 68 °F (20 °C).
3. Food items that are not expected to require refrigeration, but which may be refrigerated for the convenience of the consumer (such as carbonated beverages), are to be tested at temperatures of 68 °F (20 °C) or above even when found refrigerated for the convenience of the consumer.

231-10 VC 6.5.1. Symbols and Abbreviations; Add Abbreviations

(This item was adopted as part of the consent calendar.)

Background: At the 74th Annual Meeting, the NCWM adopted a change to the UPLR permitting random labels to be used for the packaging and labeling of fresh fruits and vegetables that are sold by count rather than weight. It is now necessary to add abbreviations for count that may appear on the label.

Committee Recommendation: Add the abbreviations "ea", "pc", and "ct" for "each," "piece," and "count" to Section 6.5.1.:

6.5.1. Symbols and Abbreviations. – Any of the following symbols and abbreviations, and none other, shall be employed in the quantity statement on a package of commodity:

avoirdupois	avdp	ounce	oz
cubic	cu	pint	pt
feet or foot	ft	pound	lb
fluid	fl	quart	qt
gallon	gal	square	sq
inch	in	weight	wt
liquid	liq	yard	yd
<u>each</u>	<u>ea</u>	<u>piece</u>	<u>pc</u>
<u>count</u>	<u>ct</u>		

231-11A I 6.11.3. Rounding; How to Round for the Net Weight Declaration

Background: Several weights and measures agencies and packagers have sought the assistance of the Office of Weights and Measures concerning how to declare the net weight on their packages. Section 6.11.3. covers rounding rules to convert from inch-pound to metric declarations, but does not discuss how to round in other situations.

In a related question concerning Section 6.11.3., a weights and measures jurisdiction inquired about the number of digits that should be used when declaring the net contents if both metric and inch-pound declarations are present. In particular, a U.S. baker had designed his label for use in both the U.S. and in Canada. The inch-pound declaration was 2 lb. The baker found that the particular product (cookies) was required to be sold in 100 gram multiples in Canada; therefore, instead of labeling his product 907 grams, the cookies were labeled 900 grams. In the Committee's Final Report, as it appeared in the 67th NCWM 1982, page 148, and in Section 2.2.4. of NCWM Publication 3, a discussion of this issue pointed out that the first sentence, stating that "...the number of significant digits retained should be such that accuracy is neither sacrificed nor exaggerated" should take precedence over the second: "As a general rule, converted values should be rounded down by dropping any digit beyond the first three." This is the reason for the phrase "as a general rule" and for the use of the word "should" rather than "shall." The packager must decide whether the accuracy of the net contents declaration is exaggerated by declaring three significant digits. In the case of the cookie packager, the number of digits in the inch-pound declaration (that is, 32 oz) is 2; thus, the equivalent (0.907 kg) or 907 grams, rounded down to two significant digits, is 900 grams (because 0.90 kg is not permitted.) ("9" and the first "0" are significant. The final "0" is not.)

The Committee has reviewed the requirements contained in the UPLR and recommends that Section 12.1.1. be used as the basis for further interpretations or requirements. Since Section 12.1.1. prohibits the average of the quantity in the packages from being below the declared net quantity, any calculated value to be declared on the label of a package must be rounded down (also known as truncating.)

Committee Recommendation: On the basis of its deliberations at the Interim Meeting, the Committee recommended clarifying Section 6.11.3. of the UPLR as follows:

6.11.3. Rounding. -- In all conversions for the purpose of showing an equivalent metric or inch-pound quantity to a rounded inch-pound or metric quantity, or in calculated values to be declared in the net quantity statement, the number of significant digits retained should be such that accuracy is neither sacrificed nor exaggerated. As a general rule, converted values should be rounded down by dropping any digit beyond the first three. (Example: 196.4 grams becomes 196 grams or 1.759 feet becomes 1.75 feet.)

It became apparent after the Interim Meeting that several problems with Section 6.11.3. still remain; therefore, the Committee will carry this item over. The last two sentences of Section 6.11.3. read "As a general rule, converted values should be rounded down by dropping any digit beyond the first three (Example: 196.4 grams becomes 196 grams or 1.759 feet becomes 1.75 feet)." The issues are:

1. This sentence must be read in context with the previous sentence in order to understand that the guideline refers to significant digits, not to the actual number of digits; therefore, 2000 lb is expressed as 4 digits, but there may be only 1 significant digit (the "2"), 2 significant digits ("20"), 3 significant digits ("200"), or 4 significant digits ("2000"). The regulatory official has no way of knowing how many of the digits are significant: this is for the packager to decide.
2. The Committee does not believe that a packager should be constrained to round down especially if he/she must label in round metric units for export to other countries; for example 7 oz might also be declared as 200 g (rather than 198 g) as long as the packager puts the larger amount (200 g) in the package.
3. Item 2 raises a question about uniformity of enforcement. Many weights and measures agencies only test the customary or inch-pound declaration; others test the larger of the declarations, whether metric or inch-pound; others test the "rational" declaration, for example, the 2-liter carbonated beverage or the 1-quart beverage, because they have both metric and inch-pound testing equipment.

The Committee intends to enlist the assistance of packagers, and in particular the Industry Committee on Packaging and Labeling for their assistance on this issue.

231-11B VC 2.13.4. Declaration of Weight/Polyethylene Sheeting and Film

(This item was adopted as part of the consent calendar.)

Background: Section 2.13.4. (polyethylene) requires that the labeled net weight for polyethylene sheeting and film

not be less than the weight calculated using a formula. It was asked if Section 6.11.3. that covers rounding rules should be used to guide the packager in how to declare the net weight on the label. Section 6.11.3. covers rounding "for the purpose of showing an equivalent metric or inch-pound quantity...", not for how to round the results of other net quantity declarations.

It was also asked how many digits should be declared on a label of polyethylene sheeting or film. The Committee believes that a uniform approach to the label declaration for polyethylene products is useful. Specific rounding rules are therefore recommended in Section 2.13.4.:

2.13.4. Declaration of Weight. -- The labeled statement of weight for polyethylene sheeting and film products under sections 2.13.1.1., and 2.13.3.2. shall be not less equal to or greater than the weight calculated by using the following formula below. The final value shall be calculated to four digits, and declared to three digits, dropping the final digit as calculated (for example, if the calculated value is 2.078 lb, then the declared net weight shall be 2.07 lb.)

$W = T \times A \times 0.03613 \times D$, where

W = net weight in pounds,

T = nominal thickness in inches,

A = nominal length in inches times nominal width¹ in inches,

D = density in grams per cubic centimeter as determined by ASTM Standard D1505-68 "Standard Method of Test for Density of Plastics by the Density Gradient Technique" (or latest issue); and 0.03613 is the factor for converting g/cm³ to lb/in³.

For the purpose of this regulation, the minimum density shall be 0.92 g/cm³.

231-12 I 10.5. Combination Packages and 10.6. Variety Packages

(This carry-over item was Item 231-5C in the Report of the 74th NCWM 1989.)

Last year, the Committee proposed that the requirements promulgated by the FTC concerning variety and combination packages be adopted because (1) they are more specific than existing requirements in the UPLR; and (2) the FTC requirements are essentially the same for combination and variety packages. Such a change would consequently eliminate the need to make judgments concerning packages composed of "dissimilar" (combination) or "similar" (variety) commodities. Unfortunately, the FDA has no definitions or requirements for combination or for variety packages. Thus, consumers see packages of "variety" meats or cereals labeled only with a total net weight; if State requirements tracked the FTC regulations for variety packages, the net weights of each style or type of product in a variety package would also have to be labeled. The Committee will write FDA for a formal interpretation as to whether State regulations patterned after FTC's requirements could be imposed on products under FDA jurisdiction. The final objective would be to reach an agreement among FDA, FTC, and the NCWM on the appropriate requirements for variety and combination packages.

231-13 I 10.X. Mechanical Pump Dispensers

Sealed mechanical pumps are a relatively new dispensing mechanism for toothpaste. They dispense dentifrice through a sealed mechanism that will always retain a minimum amount of product. Only on aerosol containers must the net contents declaration be the amount that is delivered to the purchaser (see Section 10.3 of the UPLR). The Western Weights and Measures Association recommended that a new section be added to the UPLR requiring these new types of packages to declare on their labels the total weight of product that will be delivered. The proposal was:

10.X. Mechanical Pump Dispensers. -- The declaration of quantity on packages that deliver product through a nonremovable mechanical pump shall disclose the net quantity of the commodity that will be expelled when the instructions for use, as shown on the container, are followed.

At the present time, two problems are associated with this type of container:

- (1) The dispensing head will always retain a certain amount of product in it, which cannot be obtained using normal dispensing methods. However, the package label declares the contained net weight, not the delivered net weight.
- (2) Compliance testing officials are not sure what method to use to determine the amount of product contained (as opposed to the amount delivered). Unlike aerosol packages, there are no warning statements on the package prohibiting the opening of the package. However, if emptied in the manner simulating use, the net weight will be less than the net weight determined by means which bypass the mechanical pump head.

The Cosmetics, Toiletries, and Fragrance Association (CTFA) met with the Committee and outlined how the mechanical pumps could be tested by regulatory officials to determine the amount of product contained. They also pointed out that studies showed mechanical pumps delivered comparable amounts of product as compared with tubes or other dispensing mechanisms, such as plastic squeeze bottles or hand pumps. (CTFA member firms found that other types of containers retain from 4.2 to 10.1% of labeled amounts without resorting to such extraordinary measures as cutting the containers apart, disassembling them, or waiting excessive periods of time for them to empty.) Another study showed that when consumers were asked to return tubes and mechanical pumps of toothpaste that they thought were "empty," pumps retained 4 to 5 percent of the labeled contents, while tubes retained 8 to 9 percent. Even though aggressive consumers can cut into a tube (but cannot do that to a pump), this study showed that they did not cut into the tube.

CTFA expressed concern that another declaration indicating the amount delivered in addition to the declaration presently on the packages (the amount contained) would be confusing. The Committee had not intended to require two declarations, but had interpreted the proposal as changing the net contents declaration, rather than adding one. Since such a requirement would be at variance with the traditional interpretation of the required net contents declaration (except for aerosols), the Committee is aware that the proposed section might be a solution that might require changes or additions to FDA regulations. However, it should be pointed out that certain segments of industry already provide a net contents statement that is the delivered amount; for example, many stick deodorant packages are labeled on the back declaring "(so many) ounces plus enough extra to secure the product to the base (of the dispenser)." The Committee will be carrying this item over for further study. See also Item 232-18 for further discussion.

Data collected in California indicated that mechanical pumps delivered from 89.5 to 100 percent of their declared net weights. The CTFA acknowledged that the various pumps now on the market have somewhat different dispensing characteristics. Mr. Ken Appell, Colgate-Palmolive Co., presented information concerning the possible causes of difference between California's and CTFA's data. They included the temperature at the time of measurement, the age of the product, the rate of use (fast, total dispensing vs. normal unit daily dosing), and container size (the size of the reservoir on the mechanical pump head compared with the size of the container, as well as the particular mechanical pump design). Other jurisdictions are urged to test both mechanical pumps and tubes and report their findings to the Committee. Data should include lot code information, temperature of test, and method of emptying the container, as well as container and package information, such as brand, product, and container net contents. It would be useful for the jurisdiction to test two samples of the same product, one to determine the delivered contents and one to determine the contained contents. Please contact the Office of Weights and Measures, Carroll Brickenkamp, 301-975-4005, for information on determining the contained net contents.

231-14 VC 11.23. Camera Film

(This item was adopted as part of the consent calendar.)

(This carry-over item was Item 231-6 in the Report of the 74th NCWM 1989.)

Background: The Western Weights and Measures Association had recommended that Section 11.23 of the Uniform Packaging and Labeling Regulation be broadened to provide for new products in the film industry beyond "camera film," "movie film," and "bulk still film." The recommendation was to add language to cover audio tapes, video film, and magnetic film. After consultation with members of the American National Standards Institute Image Board, the Committee published the following revision in its report to the 74th NCWM. Due to lack of time for the membership to study the extensive revisions and for the industry to comment, the Committee carried the item over. No comments were received.

Committee Recommendation: Revise Section 11.23. as follows:

11.23. Camera Film, Video Recording Tape, Audio Recording Tape and Other Image and Audio Recording Media Intended for Retail Sale and Consumer Use.

Image and audio media ~~Camera film~~ packaged and labeled for retail sale are exempt from the net quantity statement requirements of this regulation that specify how measurement of commodities should be expressed, provided that:

(a) Unexposed or Unrecorded Media. -- The net quantity of contents of unexposed or unrecorded image and audio media ~~on packages of movie film and bulk still film~~ is expressed in terms of

(1) for still film, tape, or other still image media, in terms of the usable or guaranteed number of available still image exposures. The length and width measurements of the individual exposures expressed in millimeters or inches, are authorized as an optional statement. (Example, "36 exposures, 36 millimeters x 24 millimeters" or "12 exposures, 2-1/4 inches x 2-1/4 inches.")

(2) for bulk or movie film, in terms of length (in meters or feet) of film available for exposure.

(3) for all other image and/or audio media, in terms of length of time of electronic media available for recording, together with recording and/or playing speed or other machine settings as necessary. Supplemental information concerning the length of the media may be provided.

Supplemental information may be provided on other than the principal display panel, number of linear meters or feet of usable film contained therein.

Note: Size, length of media, and format details to ensure interchangeability and other characteristics of audio and imaging media are available in the applicable American National Standards.

(b) Exposed, Recorded, or Processed Media. -- The net quantity of contents of exposed or processed film or prerecorded electronic media shall be on packages of movie film is expressed in terms of the length of running time that is of entertainment value, ~~of the exposed film for that portion of film that is of entertainment value.~~

"Entertainment value" is defined as that portion of a film, tape, or other media, that commences with the first frame of sound or picture, whichever comes first after the countdown sequence (if any), and ends with either: (a) the last frame of credits; or (b) the last frame of the phrase "The End," or (c) the end of sound, whichever is last.

~~(c) The net quantity of contents on packages of still film is expressed in terms of the number of exposures the contents will provide. The length and width measurements of the individual exposures, expressed in millimeters or inches, are authorized as an optional statement. (Example: "36 exposures, 36 millimeters x 24 millimeters" or "12 exposures, 2-1/4 inches x 2-1/4 inches")~~

The Federal Trade Commission permits film to be labeled in metric declarations only (for example, 35 mm film). Revise the footnote at the bottom of page IV-12 as follows:

Packages subject to the Federal Fair Packaging and Labeling Act (except for camera film) must be labeled in inch-pound units of measure. Metric units may also be declared on the principal display panel and may even appear first.

231-15 I 11.28. Commodities' Variable Weights and Sizes

(This carry-over item was Item 231-7 in the Report of the 74th NCWM 1989.)

Background: Under present U.S. Department of Agriculture (USDA) requirements, only poultry product shipping containers are required to be labeled with the tare weight of consumer packages inside them (if the poultry packages

do not already have net weights on them). Several weights and measures agencies have reported that the tare weights printed on the shipping containers are often incorrect. The Central Weights and Measures Association and Southern Weights and Measures Association contend that the tare weight marked on the shipping container may not be entirely accurate, but it can be used to screen the packages; if an error is found, an official test using Handbook 133 procedures can be performed. The retailer should be responsible for labeling an accurate net weight according to the associations, but should not be expected to open packages to determine an accurate tare and final net weight. The Committee members had mixed feelings about this proposal; one member reflected that the printed tare weights on shipping containers can no more be relied upon than the net weights. Another member said that the printed information on the shipping container is lost when the container is thrown away. Discussions with Mr. McCutcheon, USDA's representative to the NCWM, revealed that the Conference would have to petition USDA for such a change to existing regulations. The Committee does not want to hamper progress in this area, so it will assist the Liaison Committee in petitioning USDA to require that the tare weight be printed on shipping containers of meat products, similar to the information required for poultry products and, in addition, request that this information be checked for accuracy by USDA.

Committee Recommendation: Assist the Liaison Committee in petitioning the USDA to require the tare weight of consumer packages to be verified and printed on the shipping container.

231-16 VC 11.29. Packaged Commodities Sold by Count

(This item was adopted as part of the consent calendar.)

Background: The Office of Weights and Measures pointed out that Section 11.29, adopted in 1973 was at variance with FTC and FDA regulations, which do not exempt packages containing 6 or fewer items from including a statement of count when the individual items are fully visible. However, the Committee believes that there is merit in retaining the exemption given in Section 11.29, for adoption and use by State and local weights and measures agencies. Many produce items sold by count are fully visible to the consumer; requiring the packager to label the count appears to the Committee to be unnecessary.

Committee Recommendation: Make no change to this Section, but add a footnote as follows:

When the net contents declaration of a package that may enter interstate commerce includes count, Federal regulations under the Federal Fair Packaging and Labeling Act provide no exemption from declaring the count unless the count is one (1).

232 Uniform Regulation for the Method of Sale of Commodities

232-1 I 1.1. Berries and Small Fruits; Define "Small Fruits"

Background: One jurisdiction has classified grapes as small fruit even though they are sold attached to the stem in a "bunch." It has been assumed that all jurisdictions are aware that tomatoes are fruit, and that cherry tomatoes may be sold by measure. It has been asked whether very small plums are small fruit. These issues can be addressed depending upon whether the fruit to be sold in the small measure containers of 1/2 dry pint to 1 dry quart can fill the containers without a large amount of empty space left in the container (otherwise the method of sale is inappropriate). (Picture an apple in a pint container with a large amount of unfilled space in the corners.) The Central Weights and Measures Association had proposed that the diameter of the fruit might be used as a criterion for determining whether the fruit may be sold in measure containers of the sizes listed in Section 1.1. However, they were unable to recommend a suitable diameter or method of test. The Committee reviewed the existing NCWM recommendations for the method of sale of fresh fruits and vegetables (see Guideline 2.3.2. of NCWM Publication 3 "Policy, Interpretations, and Guidelines"). This section is reprinted in Appendix B. Only three commodities are recommended for sale by measure as defined in the Measure Container Code of Handbook 44: cherries, currants, and cherry tomatoes. The Committee therefore recommended in its Interim Report that these three become the definition of small fruit. It was thought that other items can be added as needed.

A member of the American Bunch Grape industry pointed out to the Committee that southern grapes, such as muscadines and nobles, are picked from the stem and sold by volume, but that they were not listed as "small fruit" in the Committee's Interim Report. Several comments were also received that if small fruits were defined, berries

should also be defined (for example, all fruit with the name "berry" as part of their names).

After further deliberations, some members of the Committee expressed the belief that, since the title of Section 1.1 is "Berries and Small Fruits," there are no required methods of sale for large fruit, such as grapes on the bunch, or apples, or plums.

Committee Recommendation: Because of these several unresolved issues, the Committee has elected to make this item informational and to devote time to their resolution next year. The Committee's Interim proposal was to add a definition for the term "small fruits" and make other editorial modifications as follows:

1.1. Berries and Small Fruits. --

1.1.1. Definition of "Small Fruit." -- For the purposes of this regulation, only cherries, currants, or cherry tomatoes are "small fruits."

1.1.2. Methods of Sale. -- Shall be offered and exposed for sale and sold by weight, or by volume if in measure containers that are either open or else covered by uncolored transparent lids or other wrappings that do not obscure the contents and have capacities per subsection 1.1.2(a) or subsection 1.1.2(b). When selling berries and small fruits by volume in measure containers, whether or not covered, the measure containers themselves shall not be packages for labeling purposes.

(a) Inch-Pound Capacities - 1/2 dry pint, 1 dry pint, or 1 dry quart.

(b) Metric Capacities - 250 milliliters, 500 milliliters, or 1 liter.

1.1.3. Marking Requirements for Shipping Containers. -- If two or more measure containers are placed in a shipping package, the crate or package shall show the number of measure containers and the quantity of contents of each.

232-2A I 1.5.1. In Combination with Other Foods

(This carry-over item was Item 232-3 in the Report of the 74th NCWM 1989.)

Background: Many food products are formulated and packaged by the retail store and labeled with names that may or may not have standards of identity or standards of composition in Federal regulation or policy (for example, "chicken cordon bleu"). Weights and measures officials need to know which names have standards of identity that must be followed in formulating the product and, therefore, in providing the ingredient statement.

Committee Recommendation: Reproduce the USDA Meat and Poultry Products Guide to Content and Labeling Requirements (Home and Garden Bulletin No. 236) in NCWM Publication 3 "Policy, Interpretations, and Guidelines" so that weights and measures officials will be better informed concerning packaged and unpackaged food identity statements. See Appendix C.

232-2B I 1.5.2.3. Fresh Oysters, Clams, Mussels, or Other Mollusks Removed from the Shell

The State of Maine alerted the Committee at the Interim Meeting that this subsection required fresh mollusks, including scallops, that are removed from the shell "and placed in a container [to] be sold by fluid volume." This subsection needs to be clarified: it was never the intent of the Committee to forbid direct sale from bulk of these items by drained weight. "Placed in a container" means prepackaged. Nevertheless, the Committee does not believe that the industry and weights and measures officials have been given enough time to respond to the Committee's position and to provide input for this item. The Committee intends to clarify this subsection next year. Weights and measures officials may want to survey the method of sale from bulk of fresh scallops, oysters, clams, and mussels removed from the shell and inform the Committee what legitimate practices are being followed. The following modification is being considered:

1.5.2.3. Fresh oysters, clams, mussels, or other mollusks removed from the shell and ~~placed in a container~~ sold prepackaged shall be sold by fluid volume. A maximum of 15 percent free liquid by weight is permitted. When sold from bulk, such items may be sold by drained weight.

232-3 I 1.5.X. Meat, Poultry, Fish, and Seafood -- Packaged with Other Packages of Food

(This carry-over item was Item 232-5 in the Report of the 74th NCWM 1989.)

Background: On behalf of the NCWM, the Liaison Committee petitioned USDA to require separate labeling of the net weight of meat and poultry products packaged with packages of other commodities. This petition was included by USDA along with other comments on its net weight regulations that are currently being revised. It was expected that USDA would issue its final rules before the Annual Meeting. If the USDA answered affirmatively, then the NCWM would immediately recommend modifications to State requirements for meat, poultry, fish, and seafood. If USDA declined the petition, the Conference voting membership could have been polled in order to determine what priority weights and measures officials put on this issue and could, if warranted, petition the USDA again with new information.

Committee Recommendation: Since USDA has not yet issued its final rule, the Committee is making this an information item. Its plan is to adopt the following new section only if USDA accepts the NCWM petition:

1.5.X. Packaged with Packages of Other Foods. -- When meat, poultry, fish, or seafood is packaged with other packages of food, (for example, pork with a separate packet of barbecue sauce, or turkey with a separate package of gravy), the net weight of the meat, poultry, fish, or seafood portion in the combination package must be declared separately. If the total selling price is computed from the net weight of the meat, poultry, fish, or seafood portion only, then only the net weight of meat, poultry, fish or seafood portion must be declared. In such instance, a separate declaration of the net contents of the other packages included with the meat, poultry, fish, or seafood is permitted, but not required.

232-4 V 1.7.1. Factory Packaged and Hand-Packed Ice Cream and Similar Frozen Products.

(This item was adopted.)

Background: The Central Weights and Measures Association asked the National Conference to alert jurisdictions to a practice of selling soft-serve frozen desserts by weight. The Association contended that many jurisdictions are not aware that Section 1.7.1. requires that such items as hand-packed ice cream or self-serve frozen yogurt be sold by volume.

Prior to the Interim Meeting, but after the deadline for submission of agenda items, the Committee received a proposal from industry that the following definition of the term "hand-packed" be adopted by the Conference:

"Hand-Packed," as used in this section, refers to the filling of a container for the consumer by a third party. It does not include the sale of self-serve frozen products when the amount to be purchased is determined by the consumer and dispensed by the consumer.

This proposal would permit self-serve frozen products to be sold by any method, that is, by weight, volume, or by "each."

The proposal was based on two arguments:

- (1) Consumers are best served if States permit self-serve frozen yogurt to be sold by weight because many consumers are unable to fill a volumetric measure container without air pockets. They may want peaks and swirls not measurable by means of a measure container, and they may want to buy random amounts, not necessarily the discrete sizes dictated by commonly available measure containers.

- (2) States do not uniformly require that self-serve frozen yogurt be sold by volume; therefore, the term "hand-packed" must be defined to exclude self-serve from sale by volume.

The Committee assumed that the Central Weights and Measures Association had asked that this item be placed on the agenda because it wanted more uniform enforcement of the existing regulation; the association had not asked that the subsection be revised. However, at the Interim Meeting, two of the four Central Association members present at the Committee meeting stated that they had not adopted Section 1.7.1.

For many years, many weights and measures officials have wanted to change the method of sale of ice cream and similar products to weight rather than volume. Arguments against this change have centered on a trade custom of selling by volume. The Conference has maintained the requirements in Section 1.7.1. so that consumers can make quantity comparisons. Arguments in favor of retaining this position are that consumers do not know how many servings of frozen yogurt there are in a pound, nor can they compare a self-served portion sold by weight with a package of frozen yogurt labeled by volume. Many retailers now sell some types of soft-frozen desserts by weight, negating the argument that the only trade custom is to sell by volume.

In further investigation of this issue, the Committee found that a State of Maryland law requires that self-serve frozen yogurt be sold only by weight. They also found that some jurisdictions, even though they had adopted the Uniform Regulation for the Method of Sale of Commodities, permitted methods of sale other than volume. Jurisdictions may, for example, interpret sales of this commodity as falling under Section 1.12. Ready-to-Eat Food. Subsection (a) permits "items sold for consumption on the premises" to be sold by weight, measure, or count. This paragraph permits retail operations furnishing spoons, napkins, etc., to sell by measure container, weight, or even by "small," "medium," or "large." This section does not, however, cover sales of large portions of commodity that are obviously not intended to be consumed on the premises. Thus, there is already a lack of uniformity in methods of sale of this commodity.

If it is true that consumers have difficulty delivering accurate volume, it is similarly true when retailers hand-pack frozen desserts and ice cream. Item 240-6 discusses testing procedures proposed by the International Association of Ice Cream Manufacturers due to the difficulty their members have in delivering full volume by hand packing.

Although the Conference has been unable to require a complete switch from volume to weight, the Committee believes that it is worth permitting the sale of all hand-packed, whether self-serve or not, ice cream and similar frozen desserts by either weight or volume. The Committee stresses that retailers of these products must use Class III scales if they choose to sell by weight. If there appears to be any consumer confusion or complaints because of the mixture of methods of sale, the Committee will investigate the need for a single method of sale; at the present time, several methods of sale are tolerated across the country.

In its Interim Report, the Committee had proposed permitting hand-packed ice cream to be sold by weight or volume:

1.7.1. ~~Factory Packaged and Hand-Packed~~ Ice Cream and Similar Frozen Products. --

(a) Factory packaged ice cream, ice milk, frozen yogurt, and similar products shall be kept, offered, or exposed for sale, or sold in terms of fluid volume.

(b) Hand-packed ice cream, ice milk, frozen yogurt, and similar products shall be sold by weight or by fluid volume. See also Section 1.12.(a) Ready-to-Eat Food for other provisions if the product is sold for consumption on the premises.

Based on correspondence since the Interim Meeting, it was determined that this proposal did not adequately deal with the long-standing practice of selling by the scoop or small/medium/large for ready-to-eat sales from bulk. Section 1.12. of the Uniform Method of Sale of Commodities Regulation permits ready-to-eat food to be sold by count (or by the number of scoops in this instance) only when sold for consumption on the premises.

The Committee was asked whether a grocer who packages frozen yogurt at the end of the day from his/her self-serve machines is packaging "factory packaged" frozen yogurt. "Factory packaged" ice cream does not mean grocery packed items, but refers to those standard-pack ice cream and similar commodities put up in measure container, usually in dairies. No consensus among the Committee members could be reached on the definition for "factory packed," but the term has been in the Uniform Regulation since the section was written and had not been questioned until the issue of self-serve and sale from bulk was raised. If the Regionals feel the need to propose a definition for "factory packaged," they are invited to submit their proposals as new work for the NCWM.

Committee Recommendation: The revision recommended below will have the effect of permitting all sales from bulk, whether or not self-serve, and all packaged products not "factory packaged" to be sold by weight, measure, or count (for example, by the scoop, small/medium/large, etc.):

1.7.1. Factory packaged and Hand-Packed Ice Cream and Similar Frozen Products.¹ -- Ice cream, ice milk, frozen yogurt, and similar products shall be kept, offered, or exposed for sale, or sold in terms of fluid volume.

232-5 I 1.9. Advertising and Price Computing of Bulk Food Commodities

(This item was Item 232-10 in the Report of the 74th NCWM 1989 and was withdrawn by the Committee as a voting item last year.)

Background: Subsection 1.9.2. Price Advertising now requires that the price of bulk food commodities be advertised or displayed in terms of whole units of pounds or kilograms. The subsection has been interpreted as applying only if prices are advertised, not requiring the display of price at the point of sale. In addition, the subsection does not address display of identity when the product and the price display are not close together. Utah weights and measures officials pointed out that many stores post no prices at all for bulk food commodities, or post the prices in such a way that they are unreadable (too small print, too far from the consumer, or hidden by equipment). There is often no clear information about which product is being offered at what price. Since these stores are not self-serve, the customer must ask for the product and can ask the price. The problem is that the customer has no idea about the price per pound of many items sold from bulk, for example, in a candy store or a boutique cookie store. It is argued that the absence of posted pricing is in itself deceptive; for example, purchasers may select one or two cookies costing \$1.00 without realizing that they are priced at \$6.95 per pound. Purchases are often on impulse; the consumer cannot make a value comparison without knowing the price per pound. When many customers are in line, a person may wait a long time before being able to ask the price of a product and to decide whether to make the purchase. Customers may be embarrassed to refuse the product when it costs more than expected. If the price is clearly posted, they can readily decide whether or not to buy. Utah weights and measures recommended requiring that the unit price be posted. The wording recommended last year (see Item 232-10) was considered a problem because it also required that the identity of the commodity be displayed; however, the extent of identification was not clearly defined. It was also determined that a price should be posted even if the commodity is sold by a method other than weight. The recommendation below was believed to take care of all these concerns:

1.9.1. Price Posting. -- The price of bulk food commodities or food commodities not in package form, whether sold by weight, measure, or count, shall be prominently displayed. When the price is not displayed adjacent to or on each commodity or each tray or bin of such commodity, a fully descriptive identity must also be provided along with the price.

Several issues were raised as a result of the Committee's Interim Report on this item. Some weights and measures jurisdictions were of the opinion that Section 1.9. already requires unit price posting. Other jurisdictions believed that the recommendation would go too far in that certain types of businesses selling from bulk, such as pubs selling draft beer, would be required under the proposed revision to post their prices for beer (selling by "each" or by count). California officials contend that the proposed revision would still not take care of the problems confronting consumers if cookies, for example, were sold by weight and a unit price per pound were posted. The consumer would still be unable to determine the price of a cookie without asking to have a cookie weighed. Some officials expressed the opinion that it is not necessary to post the unit price for food commodities sold by count.

Committee Recommendation: The Committee recommends carrying this item over.

232-6 W 1.12. Ready-to-Eat Food

(This carry-over item was Item 232-11 in the Report of the 74th NCWM 1989.)

No input was provided by any regional association or other party; the Committee is therefore withdrawing this item. It is recommended that any regional weights and measures association wishing to pursue this item develop a specific

proposal for the Committee's consideration.

232-7 I 1.X. Method of Sale for Fresh Fruits and Vegetables

Background: As part of the Laws and Regulations 1989 Committee Report (Item 231-3), the Conference adopted a change to the Uniform Packaging and Labeling Regulation that permits random labels to be used for fresh fruits or vegetables labeled by count. It was noted in the report that the Conference adopted guidelines for appropriate methods of sale for fresh fruits and vegetables in 1979. (See NCWM Publication 3, "Policy, Interpretations, and Guidelines" 2.3.2. Fresh Fruits and Vegetables and Appendix B.)

The Office of Weights and Measures recommended that this guideline be added to the UMSCR as a new section. The Committee did not believe that this guideline should be proposed as a regulation this year because several "quantities" in the list need to be defined, including "head" and "bunch;" some dry measure quantities should be reviewed; and many common items are not in the list. However, the Committee agrees that this guideline should be more widely distributed and used. See Appendix B for a first draft of an update to this guideline.

Committee Recommendation: Reprint the recommended guidelines on the method of sale for fresh fruits and vegetables with some additions and modifications as proposed by the Committee and ask for recommendations for additions or changes to this list for further updating. No recommendation for change this year.

232-8 W 1.X. Method of Sale for Salads

The Central Weights and Measures Association informed the NCWM that salad items are offered for sale by weight and by volume. They contend that there should be a uniform method of sale for these types of items, enforced not only at the grocery store, but also at the fast food restaurant. Items to be considered include: potato salad, cucumber salad, lettuce salad, and macaroni salad. No specific recommendation was made, nor were any supporting data submitted. The Committee is therefore withdrawing this item from its report and returning it to the Regional Associations for further development and specific recommendations.

232-9 W 1.X. Method of Sale for Bakery Items

The Central and Northeastern Weights and Measures Associations alerted the Committee to a long-standing trade practice of selling unpackaged bakery items by count. Supermarkets often incorporate an in-store bakery that may sell unpackaged bakery items, most often by count. Such supermarket items compete directly with packaged products that must be labeled and sold by weight. The purchaser cannot make a price and quantity comparison between similar products. The Regional Associations note that the trade practice of selling bakery goods by count should either be acknowledged or eliminated in the UMSCR. Since no specific proposal was provided, nor were there specific recommendations as to which type of bakery products should be sold by what method, the Committee is withdrawing this item from its report and sending the item back to the Regional Associations for further development. It should be noted by the Regionals that FDA specifically permits hot dog rolls and buns made with unenriched flour to be sold by count; however, that agency already recommends that donuts and rolls and buns made with enriched flour be sold by weight. In addition, the Regionals should study how any recommendation will impact Section 1.2. BREAD of the UMSCR.

232-10 I Method of Sale Requirements in the U.S. and in Canada

At the Interim Meeting, the Committee explored the differences between Canadian and U.S. method of sale requirements in anticipation of future efforts to make requirements for both nations more compatible. In the interests of free trade, the Committee will study ways that the U.S. and Canada can ease the burden for packagers to comply with each nation's requirements. A bilateral group, called the Free Trade Committee for Food, has representatives from both countries; FDA is represented on that group. No comments were received from industry prior to or at the Interim Meeting on specific problems that have resulted from conflicting U.S. and Canadian requirements.

Mr. Gilles Vinet, Canadian Weights and Measures, provided insight into several aspects of labeling for both countries. One problem that many U.S. packagers must avoid is declaring gallons without also declaring that they are U.S.

gallons; an Imperial gallon is larger and will be assumed in Canada unless the declaration is clearly "U.S. gallons." Consumer packaged products are required to be labeled in metric units in Canada. Other packages are required to be labeled in metric or Canadian units of measurement. It is illegal to sell product on the basis of U.S. units only. Mr. Vinet provided a table (see below) showing examples of dual U.S. and metric quantity declaration that are not exact equivalents.

Examples of Declarations (U.S. - Metric)		
In general, these dual declarations are accepted in Canada as long as both quantity declarations are met. Specific products may also have size restrictions, for example, skin lotion cannot be packaged in a 125 ml size.		
Example 1: Cookies		
Fact	Label	% Overpack
2 lb = 907.2 g	2 lb 900 g	-0.79%
1 lb = 453.6 g	1 lb 450 g	-0.79%
8 oz = 226.8 g	8 oz 225 g	-0.79%
Other Examples		
5 U.S. fl oz = 147.86 ml	5 U.S. fl oz 125 ml	-15.46%
	or 5 U.S. fl oz 150 ml	+ 1.45%
4 U.S. fl oz = 118.29 ml	4 U.S. fl oz 100 ml	-15.46%
	or 4 U.S. fl oz 125 ml	+ 5.67%
3 U.S. fl oz = 88.72 ml	3 U.S. fl oz 75 ml	-15.46%
	or 3 U.S. fl oz 100 ml	+ 11.28%
8 U.S. fl oz = 236.58 ml	8 U.S. fl oz 200 ml	-15.46%
	or 8 U.S. fl oz 225 ml	-4.89%
	or 8 U.S. fl oz 250 ml	+ 5.67%
<u>% Overpack:</u>		
(-) if U.S. quantity is exact, metric declaration is less than real content by listed %.		
(+) in regard to U.S. quantity declaration, packages must be overpacked by listed % to equal metric declaration.		

Examples of differing methods of sale are (1) powdered laundry detergents that are permitted only in certain weights and box sizes (volumes) in Canada; (2) toothpaste that must be labeled by volume in Canada, but by weight in the U.S.

One problem that arose this past year concerned the sale of cookies. A U.S. manufacturer who wanted to market cookies in both the United States and Canada labeled his cookies with a net weight declaration of 2 lb (900 g). This declaration was acceptable in Canada, which requires metric declarations in the range of 600 to 1000 grams to be rounded to the nearest 100 g; however, a U.S. weights and measures jurisdiction objected to the metric declaration because it believed the 900 g was not a close enough equivalent to 2 lb (using the conversion factor given in Handbook 44, the gram equivalent of 2 lb given to one decimal place is 907.2 grams.)

232-11 I Vacuum-Packed Cans of Coffee

There have been many consumer complaints to the Federal Trade Commission, FDA, and State Weights and Measures officials concerning the lack of fixed or required sizes for vacuum-packed coffee. No recommendation has been made by consumers or regulatory officials that coffee be standardized in one-pound increments, nor does the Committee believe that a method of sale is needed for vacuum-packed coffee.

The National Coffee Association has offered the following explanation concerning net weight declarations on vacuum-packed coffee containers. The Association states that a new "fast roast" process at higher speeds and temperatures is much more effective than the traditional roasting process. The increase in roasting speed and higher temperatures result in a larger bean size with a more expanded intracellular structure. When the customary 401 x 508 can size is filled with this coffee, the resulting net weight is 13 oz rather than 16 oz, the net weight of coffee roasted in the traditional manner. According to industry representatives, 13 ounces of fast-roast product, when measured out by volume (for example, using a scoop), yields the same quantity and quality of brewed coffee as does 16 ounces of the traditional roast. The same size can, labeled by net weight, is used for both 13-oz and 16-oz quantities due to the existing packing equipment. However, a new 11-oz size with a smaller diameter has now been introduced.

One of the consumer letters forwarded to the Committee complained about the supplemental statement appearing on certain cans that claims that the product "made the same amount of coffee as the old 1-pound size." The consumer apparently misunderstood this statement because she went on to say: "When I went to school, it took 16 oz, not 13 oz, to make a pound." Enforcement officials should note problems with supplemental statements on these packages and direct their and consumer complaints to the Food and Drug Administration (Division of Regulatory Compliance, HFF 310, FDA, 200 C St SW, Washington DC 20035).

232-12 VC 2.10.3.(a) and (b) Quantity (of Softwood Lumber)

(This item was adopted as part of the consent calendar.)

Background: Section 2.10.3. now requires that all receipts or invoices for sales of softwood lumber by nominal dimensions be accompanied by declaration of the actual dimensions. The Committee believes that this information is no longer necessary with all invoices and other sales documents because it is fairly well known that nominal 2x4 lumber is not 2 inches by 4 inches. It also appears that this requirement is not being enforced. The Committee recommends that the invoicing requirement be replaced with a posting requirement: that the minimum actual dimensions be posted so that purchasers can determine what the nominal dimensions mean depending upon purchase of seasoned or unseasoned lumber.

In addition, the Committee would like to alert weights and measures enforcement officials that the minimum dressed dimensions given in Table 1 of the Uniform Regulation for the Method of Sale of Commodities may not actually be offered for sale: many officials have found lumber of smaller dimensions than the minimums. Enforcement action should be taken in these instances.

Committee Recommendation: (1) Delete the requirement that any sales receipt or invoice stating nominal dimensions must also have printed on it the actual sizes (as delineated in parts (a) and (b)), and (2) make it mandatory to post Table 1. Softwood Lumber Sizes. The revision is as follows:

2.10.3. Quantity -- representations shall be in terms of

- ~~(a) the number of pieces, the minimum dressed width and thickness;~~
- ~~(b) the length of individual pieces, or the lineal footage, except that:~~
- ~~(c) the minimum dressed width and thickness, except that~~
- ~~(a)~~

the use of nominal dimensions shall be allowed when used in conjunction with the required minimum dressed sizes and actual length, as long as a table of minimum dressed sizes is displayed prominently and the term "nominal" or "nom" is also used in conjunction with any representation of dimensions.

~~(b) with respect to all invoices, a table of minimum dressed sizes may appear on the reverse side of the invoice, so long as appropriate reference to the table is prominently and conspicuously shown on the face of the invoice.~~

232-13 VC 2.14. Insulation

(This item was adopted as part of the consent calendar.)

Background: This section should be amended to track the most recent version of Federal requirements for insulation: FTC regulations in 16 CFR Part 460 "Labeling and Advertising of Home Insulation." The Committee also recommends that references to the minimum net weight that were in Section 2.14. and that are also part of the Federal requirements be deleted. The Committee believes that this requirement is confusing to the weights and measures inspector and that the average requirement should be retained as the standard for all packaged goods.

Committee Recommendation: Revise this section as follows:

2.14.1. Packaged Loose-Fill Insulation Except Cellulose. -- ~~The label shall declare: (1) Packaged loose-fill insulation, except cellulose, shall declare the type of insulation and the net weight with no qualifying statement; each package must contain at least the stated weight. In addition, the following information shall be supplied on the package: and (2) the~~ minimum thickness, maximum net coverage area, ~~number of bags per 1000 square feet,~~ and minimum weight per square foot at R-values of 11, 19, and 22. This information shall also be supplied for any additional R-values listed.

2.14.2. Packaged Loose-Fill Cellulose Insulation. -- ~~The label shall declare: (1) The principal display panel of packaged loose-fill cellulose insulation shall declare the type of insulation and the net weight with no qualifying statement; each package must contain at least the stated weight. In addition, the following information shall be supplied on the package: and (2) the~~ minimum thickness, maximum net coverage area, number of bags per ~~100~~ 1000 square feet, and minimum weight per square foot at R-values of 13, 19, 24, 32, and 40. This information shall also be supplied for any additional R-values listed.

232-14 VC 2.16. Liquefied Petroleum Gas Cylinder Tare Weights; Compressed or Liquefied Gases in Cylinders

(This item was adopted as part of the consent calendar.)

(This carry-over item was Item 232-12A in the Report of the 74th NCWM 1989.)

Background: See the Report of the 72nd NCWM 1987 (page 134), Report of the 73rd NCWM 1988 (page 160), and Report of the 74th NCWM 1989 (page 107). The Committee developed substantial revisions to Section 2.16 in 1987. The Committee delayed recommending changes until a complete test procedure was available for incorporation into Handbook 133 to permit safe testing of cylinders. A test procedure was developed by the Committee in 1988 (see the 73rd NCWM Report) and reviewed by the Compressed Gas Association (CGA), which proposed additional precautions and procedures to protect the less experienced testing official. The committee wishes to thank CGA for its help in this important matter. This is an area in which many weights and measures officials are not well informed and it appears to be poorly monitored. The Committee urges weights and measures officials to visit cylinder refilling operations in their jurisdictions during the coming year to become familiar with the practices for the measurement and sale of these commodities. Officials should note the amounts charged for these important and widely used systems.

The proposed requirement permits the use of either the stamped or stenciled tare weight or the actual tare weight in net contents determinations. The proposed text clarifies the two permitted methods of fill: (a) to use the stamped tare weight (at which time tighter tolerances than those recommended for safety purposes would have to be maintained), or (b) to determine the actual tare weight whenever a cylinder is filled (additional markings on the cylinder or attached to the cylinder are then required). Stamped tare weights are required for safety purposes under U.S. Department of Transportation regulations. These Federal regulations permit a 1 percent tolerance between the actual tare weight and the stamped tare weight. This tolerance, although acceptable for safety purposes (for example,

to avoid overfilling a cylinder and for determining if the cylinder is empty prior to refilling), is not precise enough for use in determining the net contents to arrive at a final charge for the cylinder of compressed gas. For example, a 200-pound tare weight cylinder of acetylene contains about 20 lb of acetylene and costs about \$75-100. If the stamped tare were permitted to be used and if it were permitted to differ from the actual tare by 1 percent (2 lb on the 200 lb cylinder), this would amount to a potential error of 2 lb in 20 lb, (i.e., 10 percent of acetylene product) or \$7.50 to \$10.00 in product cost. The potential error in smaller cylinders is even more significant. California Weights and Measures recommended reducing the current allowable difference (1 percent) between the actual tare weight and the stamped tare weight of cylinders (Section 2.16.) to 1/4 percent and to apply this to all cylinders of compressed gases. The Committee broadened the California recommendation of 1/4 percent for this proposal to 1/2 percent for small tanks of under 20 lb tare weight.

Committee Recommendation: Replace Section 2.16. with the text below and incorporate Appendix D into NIST Handbook 133:

2.16. Compressed or Liquefied Gases in Refillable Cylinders

2.16.1. Application. -- This Section does not apply to disposable cylinders of compressed or liquefied gases.

2.16.2. Net Contents. -- The net contents shall be expressed in terms of cubic feet or cubic meters; pounds and ounces; or kilograms. See Section 2.21. for permitted net contents for liquefied petroleum gas. A standard cubic foot of gas is defined as a cubic foot at a temperature of 70 °F and a pressure of 14.696 psia (or metric equivalent) except for liquefied petroleum gas as stated in Section 2.21.

2.16.3. Cylinder Labeling. - Whenever cylinders are used for the sale of compressed or liquefied gases by weight, or are filled by weight and converted to volume, the following shall apply:

2.16.3.1. Tare Weights. --

(a) **Stamped or Stenciled Tare Weight.** -- For safety purposes, the tare weight shall be legibly and permanently stamped or stenciled on the cylinder. All tare weight values shall be preceded by the letters "TW" or the words "tare weight." The tare weight shall include the weight of the cylinder (including paint), valve, and other permanent attachments. The weight of a protective cap shall not be included in tare or gross weights. The Code of Federal Regulations Title 49, Section 178.50-22 requires the maker of cylinders to retain test reports verifying the cylinder tare weight accuracy to a tolerance of 1 percent.

(b) **Tare Weight for Purposes of Determining the Net Contents.** -- The tare weight used in the determination of the final net contents may be either:

- (1) the stamped or stenciled tare weight or
- (2) the actual tare determined at the time of filling the cylinder. If the actual tare is determined at the time of filling the cylinder, it must be legibly marked on the cylinder or on a tag attached to the cylinder at the time of filling.

(c) **Allowable Difference.** -- If the stamped or stenciled tare is used to determine the net contents of the cylinder, the allowable difference between the actual tare weight and the stamped (or stenciled) tare weight, or the tare weight on a tag attached to the cylinder, for a new or used cylinder shall be:

- (1) 1/2 percent for tare weights of 20 lb or less or
- (2) 1/4 percent for tare weights of more than 20 lb.

(c) **Average Requirement.** -- When used to determine the net contents of cylinders, the stamped or stenciled tare weights of cylinders at a single place of business found to be in error predominantly in a direction favorable to the seller and near the allowable difference limit shall be considered to be not in conformance with these requirements.

2.16.3.2. Acetylene Gas Cylinder Tare Weights. -- Acetone in the cylinder shall be included as part of the tare weight.

2.16.3.3. Acetylene Gas Cylinder Volumes. - The volumes of acetylene shall be determined from the product weight using approved tables such as those published in NIST Handbook 133 or those developed using 70 °F and 14.7 cu ft per pound at one atmosphere as conversion factors.

2.16.3.4. Compressed Gases such as Oxygen, Argon, Nitrogen, Helium, and Hydrogen. -- The volumes of compressed gases such as oxygen, argon, nitrogen, helium, or hydrogen shall be determined using the

tables and procedures given in NIST Technical Note 1079, Tables of Industrial Gas Container Contents and Density for Oxygen, Argon, Nitrogen, Helium, and Hydrogen and supplemented by additional procedures and tables in NIST Handbook 133.

232-15 I 2.16. Liquefied Petroleum Gas Cylinder Tare Weights; Acetylene

(This carry-over item was Item 232-12C in the Report of the 74th NCWM 1989.)

The Committee received no input on this item from regional weights and measures associations. Kansas City, Kansas, Weights and Measures and Maryland Weights and Measures responded to the questions asked in the Committee's report to the 74th NCWM. A survey will be conducted to get answers to the questions posed in the Committee's final report before any recommendations are made.

232-16 I 2.20. Gasoline-Alcohol Blends; Add Labeling of All Oxygenates

Background: Eighteen spokespersons provided testimony on a proposal to broaden the labeling requirement for gasoline-alcohol blends to all gasoline containing any oxygenate above 1 percent by volume. An "oxygenate" is any oxygen-containing chemical compound, including alcohols (such as ethanol or methanol) and ethers (such as methyl-t-butyl ether (MTBE), another common additive to gasoline). The proposal was as follows:

2.20.1. Method of Retail Sale. -- All motor fuel kept, offered, or exposed for sale, or sold, at retail containing at least 1 percent by volume of oxygenates ethanol, methanol, or a combination shall be labeled by the maximum percentage of the oxygenate, by common name of the oxygenate (ethanol, methanol, MTBE, etc), and shall be identified as "with" or "containing" (or similar wording) "ethanol," "methanol," or "ethanol/methanol" on the upper 50 percent of the dispenser front panel in a position clear and conspicuous to the driver from the driver's position, in a type at least 1/2 inch in height, 1/16 inch stroke (width of type).

2.20.2. Documentation for Dispenser Labeling Purposes. -- The retailer must be provided, at the time of delivery of the fuel, on an invoice, bill of lading, shipping paper, or other documentation, the presence and maximum amount of any oxygenate ethanol, methanol, or any combination of oxygenate of ethanol/methanol (in terms of percent by volume) contained in the fuel. This documentation is only for dispenser labeling purposes; it is the responsibility of any potential blender to determine the total oxygen content of the motor fuel before blending.

The reasons for this proposal provided by the Central Weights & Measures Association and the National Association of State Directors of Agriculture were:

1. Greater use of ethanol fuel has major national benefits for the environment, U.S. agriculture, and national security.
 - a. The President has announced a comprehensive program supporting the use of ethanol and other oxygenated fuels to help meet air quality standards.
 - b. To facilitate attainment of these standards, current retail motor-fuel dispenser labeling requirements for ethanol need to be reviewed.
2. Requiring only ethanol/methanol blended fuels, instead of all oxygenated fuels, to be labeled is discriminatory.
 - a. Because alcohol is the only ingredient other than lead required to be labeled on retail motor-fuel dispensers, such labeling is viewed by many consumers as a warning statement against the use of ethanol-blended fuels.
 - b. With the increasing use of oxygenated fuels, some automobile manufacturers in their owner's manuals specifically limit the maximum amount of such other oxygenates as MTBE.
3. As long as there is a need for alcohol labeling, the requirements for alcohol labeling should be expanded to include other oxygenated fuel components.

The American Petroleum Institute and some of its members were opposed to the proposal. Their arguments included:

1. MTBE has been added in small amounts at the refineries for many years to boost the octane without raising the concern of automobile manufacturers. These amounts often range from 2 to 7 percent by volume.
2. Oil companies do not know whether the gasoline that they receive through common-carrier pipelines has MTBE in it, nor how much. The MTBE has traditionally been added to gasoline to meet minimum specifications in octane; MTBE is expensive so that only the minimum amounts to raise the base gasoline to the prescribed octane are added.
3. If small volume amounts of MTBE in gasoline must be labeled, all gasoline suppliers will have to begin extensive testing.

The issue arises now because:

1. large amounts of an oxygenate (either ethanol or MTBE) must be added to gasoline in some Southwestern U.S. localities in the winter months in order to reduce pollution from emissions of carbon monoxide; and
2. gasoline refiners are producing gasoline blends with very high MTBE concentrations (e.g., 15 percent blends).

Automobile manufacturers recommend that owners purchase gas with no more than 10 percent ethanol ("gasohol") and to watch for drivability problems when using any gasoline-alcohol mixture. Older cars may not operate properly with gasoline-alcohol blends. (Due to tax incentives, mixtures of 10 percent are the universal norm for gasoline-ethanol). Some boat, airplane, and small engine manufacturers warn against the use of any gasoline-alcohol blend. Automobile owners manuals now recommend limits concerning high concentrations of MTBE (11 or 15 percent), but do not caution about gasoline-MTBE blends of lower levels.

The Motor Vehicle Manufacturers Association and the Automobile Importers of America recommend labeling of the presence of oxygenates when the gasoline contains more than 5 1/2 percent by volume of ethanol or more than 11 percent by volume of MTBE. (These amounts are equivalent in terms of the amount by weight of oxygen in the blends.) The Committee does not know if manufacturers of small engines or airplane engines are also concerned about high levels of MTBE in gasoline to be used in their engines.

Some agricultural interests expressed a desire that no labeling of gasohol be required. There was also some interest in broadening the labeling requirements, but retaining the requirement that labeling appear on the dispenser front panel. Finally, there were alternative proposals that (1) labeling be required if alcohol content is greater than 1 percent by volume or if oxygenate content is 2 percent by weight or greater of oxygen (equivalent to 11 percent MTBE); or (2) labeling be required if alcohol content is greater than 1 percent by volume or if oxygenate content is above 2.7 percent by weight (equivalent to 15 percent MTBE).

Part of the proposal was to allow the alcohol label to be placed on the side of the dispenser. Several persons at the Interim Meeting commented that the label should remain on the front of the dispenser; one person suggested that the label be required where it can best be seen, on the front or on the side, depending upon the location of the dispenser nozzle.

Additional complications are:

1. MTBE in any concentration cannot be detected with a field screening test method as ethanol or methanol can be.
2. In 1988, 19 percent of all gasoline contained concentrations of MTBE at or above 1 percent. Ninety-five percent of MTBE blended gasoline contains less than 11 percent MTBE by volume.
3. The U.S. Congress is expected to revise the Clean Air Act, which may affect the use of oxygenated fuels in unforeseen ways. Bills in both the Senate and House of Representatives contain proposals to require certain types of motor fuel for environmental purposes that would affect the usefulness of any labeling proposal before the National Conference.

Committee Recommendation: No action at this time. The item will be open for discussion at the Annual Meeting. Comments are welcome.

232-17 I 2.22. Liquid Oxygen Used for Respiration

Background: At the 74th Annual Meeting a new section was adopted concerning the sale of liquid oxygen for respiration. It currently requires in part:

- (a) If sold by weight, liquid oxygen must be weighed on an appropriate, sealed commercial scale. A pressure or other type of gauge may not be used to determine weight.

There is no similar requirement for metering liquid oxygen. Since liquid oxygen must be weighed on an appropriate, sealed commercial scale, it was proposed that appropriate measuring methods be required when selling by other measure. The Committee did not have time to address this proposal in any depth. It is possible that the new Health Care Finance Administration (HCFA) rules for reimbursement of medical oxygen providers have nearly eliminated the sale of respiration oxygen by weight or by volume. The HCFA rules provide for reimbursement based on a flow rate schedule, rather than on a final quantitative amount. In addition, one medical oxygen provider said that hospitals and other large customers of liquid oxygen will not accept a metered value from the oxygen supplier as a basis for payment. Because a large volume of oxygen evaporates after the product has been metered during the filling of the tank, many oxygen customers require in their contracts that the volume be determined by means of a gauge rod in the holding tank.

Committee Recommendation: No action at this time. These practices will have to be investigated before the Committee can make final recommendations as was proposed in the agenda: to revise subsection (4b) to permit only sealed meters for use in dispensing liquid oxygen by measure and to prohibit use of gauge rods or similar methods.

232-18 I 2.X. Products Dispensed from Mechanical Devices

Background: It was proposed to add a new section for solid or liquid products dispensed from mechanical devices to require that the "delivered" weight or volume be the net contents declaration, rather than the "contained" weight or volume. Reason: the consumer does not usually receive all of the net contents of containers (e.g., toothpaste, deodorant sticks, or hair spray pumps). The container label should declare the net contents that will actually be delivered when the device is operated as indicated on the label. See the discussion under Item 231-13.

Committee Recommendation: The Committee will not make a recommendation concerning this issue this year, but it generally endorses the concept of labeling commodities on a "to deliver" basis. As several consumers at the meeting pointed out, there is some precedent in declaring a delivered weight in the stick deodorant industry: on stick deodorant packages, the label states that there are so many ounces of product "plus enough extra to secure the product to the base [of the dispenser]."

232-19 VC 2.X. Animal Bedding

(This item was adopted as part of the consent calendar.)

Background: Animal bedding is sold by weight or by volume, the latter by dry measure or cubic measure. Some packages are labeled by compressed volume, while others are labeled by the "loose" or "usable" quantity. Value comparison is difficult.

Committee Recommendation: Add the guideline adopted by the Conference at the 73rd NCWM as a new section in the UMSCR:

Section 2.X. Animal Bedding. -- Packaged animal bedding of all kinds, except for baled straw, shall be sold by volume, that is, by the cubic yard, cubic foot, cubic inch, or cubic meter. If the commodity is packaged in a compressed state, the quantity declaration shall include both the quantity in the compressed state and the usable quantity that can be recovered. Example: "500 cu in. Expands to 1000 cu in."

The recommended test method is Section 4.11. Peat Moss from Handbook 133. The test official may need to "fluff up" the product prior to testing by pulling the particles apart by hand or by sieving the product (selecting the sieve

size according to the size of the individual particles) so that the material may be reconstituted from a compressed state or to compensate for compacting that may occur under ordinary packaging and distribution processes. The recommended test method will be noted in NCWM Publication 3 and added to the index of the next edition of NIST Handbook 133.

240 Handbook 133: Package Testing

240-1 I Proposed Sampling Plans and Smaller MAV's

(This carry-over item was Item 240-1A in the Report of the 74th NCWM 1989.)

Background: At the January 1989 Interim Meetings, the Committee did not think that enough information had been submitted with the New York proposal for changes to Handbook 133 to make a decision or recommendation, nor was there enough time between the 1989 Interim Meetings and the 74th Annual Meeting for weights and measures officials or industry representatives to determine the effects of the proposal on their operations. It was subsequently found that the New York proposal needed modification to permit concurrent jurisdiction with USDA on meat and poultry products. No further data or information on this proposal has been submitted by New York or other parties since that time.

At the 74th Annual Meeting, the Western Weights and Measures Association Meeting, and the Southern Weights and Measures Association Meeting, requests were made from the floor to withhold action on this item because weights and measures and industry representatives needed time to assimilate and work with Handbook 133 in its present form before they could decide whether changes should be made. The Committee therefore announced in its agenda for the 1990 Interim Meetings plans to table the item. However, at the Interim Meeting, the Industry Committee on Packaging and Labeling (ICPL) raised the issue of their planning to propose other modifications to Handbook 133, specifically to add a sampling allowance to Category B sampling plans similar to the sampling factor that must be computed when using a Category A sampling plan. They requested time at the Annual Meeting to make a presentation from the floor concerning this issue. The Committee would like to stress that ICPL made it clear they had no quarrel with Handbook 133 as written, but they felt that regulatory agencies have taken liberties with the procedures and, consequently, a new approach may be needed. In addition, New York discussed its plans to submit further data concerning the proposal to change both the sampling plans and MAV's.

Committee Recommendation: No action at this time. The Committee is aware that the New York proposal has been modeled in some part after the European Community sampling plans. In the interests of international uniformity, the Committee believes that it may be beneficial to compare these procedures with Handbook 133 prior to making any further modifications to the basic sampling plans. (One of the authors of Handbook 133 advised the Committee that the EC plans had been considered for weights and measures field use in the early 70's, but were not acceptable to field inspectors at that time.)

240-2 VC 3.11.4. Exhausting the Aerosol Container; Clarify Instructions

(This item was adopted as part of the consent calendar.)

Background: This section instructs testing officials to follow emptying instructions provided on the container label. When testing aerosol cans of whipped cream that had no instructions printed on the cans, weights and measures officials shook the test containers for 1 minute. This turned the whipped cream into butter inside the can and it could not then be dispensed. The packager of the whipped cream will print shaking and emptying instructions on his containers. He has also requested that further instructions be included in the section on emptying aerosol containers to warn the testing official that shaking and emptying instructions may differ greatly from a 1-minute shake. Also, when the test stand is not available to the testing official, an exhausting time less rigorous than 30 minutes should be permitted.

Committee Recommendation: Revise subsection (a) as follows:

- a. **Foam Products:** Shake container according to directions on the can. Placing selected container in the position specified in the instructions on the package, exhaust it by holding the valve wide open until visible

spray is interrupted. Continue exhausting container for 30 seconds. If using portable test stand (see Figures 3-11 and 3-12), exhaust container following the above procedures. However, hold valve wide open for 30 minutes.

240-3 I Moisture Loss for Ice-Packed Poultry and Other Meat and Poultry Items

(This carry-over item was Item 240-5A in the Report of the 74th NCWM 1989.)

Further Information: The Task Force on Commodity Requirements completed its work at the 73rd Annual Meeting. Ongoing efforts to refine test methods and define specific approaches for different commodities subject to moisture loss were left to the Laws and Regulations Committee and the Liaison Committee. The Task Force recommended that the Committee take up the issue of moisture-loss for ice-packed poultry shipped in bulk for repackaging by retail stores. Weights and measures agencies have repeatedly found large shortages in bulk shipments of ice-packed poultry and have been frustrated in their efforts to decrease the occurrences of shortages. The Task Force was unable within the time allotted to it to design a data collection study that would shed light on the shortages caused by the loss of moisture during shipping. The U.S. Department of Agriculture (USDA), Food Safety and Inspection Service (FSIS), volunteered its help in collecting the necessary data.

USDA proposed five product categories in addition to ice-packed poultry for which to determine gray areas: (1) cured pork products (hams, shoulders, loins, and picnics); (2) cured beef products (corned beef, corned beef brisket, and tongues); (3) raw meat products (chopped beef, ground beef, hamburger, and beef patties); (4) ham patties, chopped ham, pressed ham, spiced ham, and similar products; and (5) meat and poultry products that are cooked in vacuum packaging. USDA has again volunteered to obtain data for moisture loss by tracking products from selected Federal establishments. This recommendation and offer of assistance from USDA are evidence of the USDA's strong commitment to improve net weight compliance procedures and achieve uniformity in net weight compliance test results.

The Committee met with Mr. John McCutcheon, FSIS, USDA, and Mr. George Wilson, representing the American Meat Institute (AMI) during the Interim Meetings. AMI is conducting its own tests to determine the amount of moisture loss in corned beef and will transmit their data to the NCWM.

Concerning ice-packed poultry, FSIS and the NIST Office of Weights and Measures designed a test protocol for weighing cases of poultry on the packing line, in the plant, at the point of shipping, and as received by the purchaser. A pilot study was planned for the spring of 1990 in order to finalize the test method prior to asking other States and manufacturing plants to participate. The study sought to determine the amount of moisture lost at each point in the manufacturing and distribution system for a wide variety of products, distribution distances, and times.

A pilot study on ice-packed bulk poultry was conducted by the States of Maryland, Delaware, and Connecticut. The Committee expresses its appreciation to these jurisdictions for their fine work. Moisture loss on whole chicken was as high as 9% in a little over 24 hours. The Committee must decide whether moisture loss of this magnitude can in any way lend itself to the gray area approach. Perhaps a more viable solution would be to help retailers with their contracts with their suppliers, who may not be the poultry packagers themselves, but could be middlemen.

The American Meat Institute is not only conducting studies on cured pork products and cured beef products, but assessing certain unanticipated problems with the types of products used as models to determine the size of the gray areas for bacon and for luncheon meats. They will provide the Conference their results and recommendations when completed.

240-4 I Moisture Loss for Pet Foods

(This carry-over item was Item 240-5B in the Report of the 74th NCWM 1989.)

Further Information: Members of the Pet Food Institute are collaborating with selected weights and measures jurisdictions in the conduct of a study of moisture loss for dry pet foods. Their objective is to provide moisture loss data that can be used to determine the amount of weight loss that may be experienced from the time of packaging.

All regions of the country, as well as all representative types and sizes of dry pet foods and packaging materials, are represented in the study. Weights and Measures officials have been asked to visit the packaging plants and warehouses where the weight loss studies are being conducted, test the scales used to determine the amount of weight loss, and become acquainted with the net weight and other quality control aspects of the packager. The study began in January 1990 and is expected to end in June 1990; a second study to determine the effects of different seasonal variations will begin in May and end in November 1990.

Four companies are in the midst of collecting data on moisture loss for dry pet food: Alpo, Nabisco, Quaker, and Ralston Purina. The first 6-month collection period will end about August, 1990. The second phase will begin in July, 1990 and continue until January or February of 1991. Heinz Pet Products will participate with the other 4 companies in the second phase. The preliminary results of their work will be reviewed at the Interim Meeting in January 1991.

240-5 I Moisture Loss for Pasta

(This carry-over item was Item 240-5C in the Report of the 74th NCWM 1989.)

Further Information: The National Pasta Association would like to use the gray area approach adopted by the NCWM for flour as a model for moisture loss in pasta. They have provided the NCWM with a list of all U.S. packagers to act as contacts with the packaging plant. A round robin will have to be conducted to make sure that all laboratories obtain the same moisture content on the pasta. The association has agreed to sponsor the round robin; weights and measures officials will be kept informed and asked to participate in a pilot study when a final details have been worked out.

240-6 I Section 4.X. Hand-Packed Ice Cream

Background: Companies that deliver hand-packed ice cream by volume report that it is impossible to deliver the volume using brim-full measure containers and the current test methods for ice cream as specified in Handbook 133. Section 4.13. of Handbook 133 tests the volume of ice cream by measuring the displacement of ice water. The industry contends that this test method is satisfactory for testing factory-filled ice cream packages, but that the displacement test method applied to hand-packed ice cream does not adequately recognize the nature of the product. Hand-packing does not always eliminate air pockets, no matter how skilled or trained the store clerk is, resulting in failure to comply when the current test method is used. The presence of air pockets in hand-packed containers of ice cream sold by volume has led to complaints by some consumers, who argue that they receive less than the quantity of product indicated by the container size. The International Ice Cream Association therefore proposed adding the following new test method:

4.X. Hand-Packed Ice Cream

The following test method is for hand-packed ice cream only. Prepacked/factory packaged ice cream and related products should be tested according to Section 4.14.

4.X.1. Equipment

Scales and weights recommended in Section 3.1.

4.X.2. Procedure

1. Determine inspection lot, fill out the standard pack report form heading, and select the random sample and tare sample. Place the sample in the freezer or ice chest until ready to test. Remove packages from the freezer one at a time.
2. Remove the first package from the freezer and gross weigh it. Record the weight.
3. Note the appearance of the container and record - does it appear visibly full?
4. Clean and air-dry the tare materials (container, lid, etc.). Weigh and record the weight of these materials for the first package.

5. Subtract the tare weight from the gross weight and record.
6. Repeat steps 2-5 for the rest of the sample.
7. Weight of every package in the sample set must equal or exceed 4.5 pounds/gallon or appropriate subdivisions thereof.

4.X.3. Action

If the criterion in either step 3 or step 7 is not met, the lot fails to comply with the requirements; if both criteria are met, the lot conforms with the requirements.

Committee Position: The Committee believes that the proposed procedure can be only a screening procedure, not an enforcement test method. If the method of sale is by volume (as recommended by the Conference), then the enforcement test procedure must determine volume. The actual weight of ice cream ranges from 4.5 to 6 pounds per gallon. Thus a measure container with ice cream weighing 6 pounds per gallon that "looks full" will have 25 percent of air space in the container (that is, 1.5 pounds of missing product divided by 6 pounds per gallon), yet will be found "full measure" by means of the test procedure above. Weights and measures officials at the Interim Meeting asked whether the typical brim-full measure containers were suitable devices for the delivery of hand-packed ice cream; they suggested that larger containers than the measure containers intended for use in factory-filled operations be obtained by hand-packaging operators in order to accommodate the air space that they know packers will introduce. This situation is similar to that discovered in the sale of oysters by the gallon. One-gallon ice cream measure containers were used by oyster packers. The containers would contain 1 gallon only when filled to the brim; their design did not allow for the head space needed when filling the container with a watery fluid. The measuring devices were therefore inappropriate for the product being measured. Retailers who sell ice cream and similar frozen products by volume must deliver the stated volume; they should determine the size of container needed to deliver this volume. Brim-full measure containers are not required and may not even be appropriate for hand-packing operations.

The Committee is recommending a change to Section 1.7.1. of the Uniform Regulation for the Method of Sale of Commodities that will permit the sale of hand-packed ice cream and similar frozen desserts by weight or by volume. The industry must be warned, however, that if Item 232-4 is adopted, and if a retailer wishes to sell by weight, Class III scales must be used for such sales.

240-7 I Polyethylene/Test Methods for Bags

This carry-over item was Item 240-4C in the Report of the 73rd NCWM, 1988.

Background: The recommended test procedure needs further modification. The State of California is investigating alternatives to using vermiculite that (1) would not require that the inspector wear a dust mask when using it (recommended in the test procedure) and (2) would not break up during use and would reliably retain its volume. The use of styrofoam balls is being investigated. In addition, the method must be supplemented; the present recommendation only tests for tie-off volume; it does not test the capacity of bags labeled "fits x-gallon can."

Committee Recommendation: No action at this time.

S. Colbrook, Illinois, Chairman

B. Bloch, California
F. Clem, Columbus, Ohio
A. Nelson, Connecticut
L. Straub, Maryland

C. Brickenkamp, Technical Advisor

Committee on Laws and Regulations

Appendix A

Uniform Weighmaster Law

Section 1. Purpose

The purpose of this Act is to ensure accurate measurements by public weighmasters.

Section 2. Scope

This Act:

- (a) establishes a registration, licensing, and enforcement program;
- (b) provides authority for license fee collection;
- (c) empowers the state to promulgate regulations as needed to carry out the provisions of the Act;
- (d) provides for optional or voluntary licensing when the employing organization or other organizations require it as part of the condition for employment;
- (e) provides for civil and criminal penalties.

Section 3. Definitions

As used in this Act:

- 3.1. **Public Weighing** means the weighing, measuring, or counting, upon request, of vehicles, property, produce, commodities, or articles other than those that the weigher or his/her employer, if any, is either buying or selling.
- 3.2. **Public Weighmaster** means any person who performs public weighing as defined in 3.1.
- 3.3. **Vehicle** means any device (except railroad freight cars) in, upon, or by which any property, produce, commodity, or article is or may be transported or drawn.
- 3.4. **Director** means the _____ of the Department of _____.

Section 4. Enforcing Officer: Rules and Regulations

The Director is authorized to:

- (a) enforce the provisions of this Act;

- (b) issue reasonable regulations for the enforcement of this Act that shall have the force and effect of law; and
- (c) adopt rules that include, but are not limited to, determining:
 - (1) the qualifications of the applicant for a license as a public weighmaster;
 - (2) renewal or refusal of a license;
 - (3) the period of license validity;
 - (4) measurement practices that must be followed, including the measurement or recording of tare;
 - (5) the required information to be submitted with or as part of a certificate;
 - (6) the period of recordkeeping.

Section 5. Qualifications for Weighmaster

To receive authorization to act as a public weighmaster, a person must receive a license from the Director. In order to qualify for a license, a person must:

- (a) be able to weigh or measure accurately;
- (b) be able to make correct certificates; and
- (c) possess other qualifications required by regulations promulgated under the Act.

Section 6. License Application

Using a form provided by the Director, the applicant for a license as a public weighmaster shall furnish evidence that he/she has the qualifications required by Section 5 of this Act and regulations promulgated under the Act.

Section 7. Evaluation of Qualifications of Applicants

The Director will determine the qualifications of the applicant based on:

- (a) the information provided on the application; and
- (b) supplementary information as determined by the Director.

The Director may also determine the qualifications of the applicant based on the results of an examination of the applicant's knowledge.

Section 8. Issuance and Records of Licenses

The Director will:

- (a) grant licenses as public weighmasters to qualified applicants;
- (b) keep a record of all applications submitted and of all licenses issued.

- (c) establish the period of validity of licenses issued.

Section 9. License Fees

The Director shall have the authority to set fees for the administration and effective enforcement of the provisions of this Act. Before the issuance of a new license or renewal of a license as a public weighmaster, the applicant must pay a fee of \$_____ to the Director.

Section 10. Certificate: Required Entries

- (a) The certificate, when properly filled out and signed shall be prima facie evidence of the accuracy of the measurements shown.
- (b) The design of and the information to be furnished on a weight certificate shall be prescribed by the Director and will include, but not be limited to, the following.
- (1) The name and license number of the public weighmaster.
 - (2) The kind of commodity weighed, measured, or counted.
 - (3) The name of the owner, agent, or consignee of the commodity.
 - (4) The name of the recipient of the commodity, if applicable.
 - (5) The date the certificate is issued.
 - (6) The consecutive number of the certificate.
 - (7) The identification, including the identification number, if any, of the carrier transporting the commodity, and the identification number or license number of the vehicle.
 - (8) Other information needed to distinguish or identify the commodity from a like kind.
 - (9) The number of units of the commodity, if applicable.
 - (10) The measure of the commodity, if applicable.
 - (11) The weight of the commodity and the vehicle or container (if applicable) broken down as follows:
 - (i) the gross weight of the commodity and the associated vehicle or container;
 - (ii) the tare weight of the unladen vehicle or container; or
 - (iii) both the gross and tare weight and the resultant net weight of the commodity.
 - (12) Signature of the public weighmaster who determined the weight, measure, or count.

Section 11. Certificate: Execution, Requirements

- (a) When filling out a certificate, a public weighmaster shall:
 - (1) enter the measurement values to clearly show that the measurements were actually determined;
 - (2) enter only the measurement values personally determined;
 - (3) not enter measurement values determined by other persons.
- (b) If the certificate provides for entries of gross, tare, or net, the public weighmaster shall:
 - (1) strike out or otherwise cancel the printed entries for the values not determined; or
 - (2) enter the scale and date on which the values were determined on the certificate if the values were not determined on the same scale or on the same date shown on the certificate.

Section 12. Measurement Practices & Equipment Used

A public weighmaster shall use measurement practices and equipment:

- (a) in accordance with the requirements of the latest edition of NIST Handbook 44, "Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices;"
- (b) examined, tested, and approved for use by a weights and measures officer of this State.

Section 13. Scale Used: Capacity, Platform Size, One-Draft Weighing

- (a) A public weighmaster shall not weigh a vehicle, or combination of vehicles, when part of the vehicle or connected combination, is not resting fully, completely, and as one entire unit on the scale.
- (b) When weighing a combination of vehicles that will not rest fully, completely, and as one complete unit on the scale platform,
 - (1) the combination shall be disconnected and weighed in single drafts; and
 - (2) the weights of the single drafts may be combined in order to issue a single certificate for the combination, provided that the certificate indicates that the total represents a combination of single draft weighings.

Section 14. Copies of Certificates

A public weighmaster shall keep and preserve for the period specified in the regulations a legible copy of each certificate issued by him or her. The certificates shall be available for inspection by any weights and measures officer of this State during normal office hours.

Section 15. Reciprocal Acceptance of Certificates

The Director is authorized to recognize and accept certificates issued by licensed public weighmasters of other States that recognize and accept certificates issued by licensed weighmasters of this State.

Section 16. Optional Licensing

The following persons shall be authorized, but are not required, to obtain licenses as public weighmasters:

- (a) a law enforcement or weights and measures officer, or other qualified employee of a State, city, or county agency or institution when acting within the scope of his/her official duties;
- (b) a person weighing property, produce, commodities, or articles:
 - (1) that he or his employer is either buying or selling; or
 - (2) in conformity with the requirements of Federal statutes or the statutes of this State relative to warehousemen or processors.

Section 17. Prohibited Acts

It is a prohibited act for any person

- (a) without a valid license to:
 - (1) assume the title of public weighmaster, or any title of similar import;
 - (2) perform the duties or acts to be performed by a public weighmaster;
 - (3) hold himself or herself out as a public weighmaster;
 - (4) issue any certificate, ticket, memorandum, or statement for which a fee is charged;
 - (5) engage in full-time or part-time business of measuring for hire.
- (b) to use or operate any device for certification purposes that does not meet, nor in a manner not in accordance with, the requirements of the latest edition of NIST Handbook 44, "Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices;"
- (c) to falsify a certificate or to falsely certify any gross, tare, or net weight or measure required by the Act to be on the certificate;
- (d) to refuse without cause to weigh or measure any article or thing which it is his/her duty to weigh or measure, or refuse to state in any certificate anything required to be therein;
- (e) to hinder or obstruct in any way the Director or his/her authorized agent in the performance of the Director's official duties under this Act;
- (f) to violate any provision of this Act or any regulation promulgated under this Act;
- (g) to delegate his/her authority to any person not licensed as a public weighmaster;
- (h) to request a false certificate or to request a public weighmaster to weigh, measure, or count any vehicle, property, produce, commodity, or article falsely or incorrectly;
- (i) to issue a certificate simulating the certificate in the Act;
- (j) to use or have in his/her possession a device which has been altered to facilitate fraud.

Section 18. Suspension and Revocation of License

The Director is authorized to suspend or revoke the license of any public weighmaster:

- (a) when, after a hearing held following 10 days notice to the licensee, he/she is satisfied that the licensee has violated any provision of this Act or of any regulation under this Act;
- (b) when the licensee has been convicted in any court of competent jurisdiction of violating any provision of this Act or of any regulation under this Act; or
- (c) when the licensee is convicted of any felony.

Section 19. Civil Penalties

Any person who by him/herself, by his/her servant or agent, or as the servant or agent of another person commits any of the acts enumerated in Section 17 may be subject to a civil penalty.

19.1. Civil Action. A civil action may be brought by the Director in any court of competent jurisdiction to recover a civil penalty of:

- (a) not less than \$___ nor more than \$___ for a first violation,
- (b) not less than \$___ nor more than \$___ for a second violation within 2 years from the date of the first violation, and
- (c) not less than \$___ nor more than \$___ for a third violation within 2 years from the date of the first violation.

19.2. Administrative Hearing. Upon a finding of a violation of any provision of this Act, the Director or his/her designee shall be authorized to conduct an administrative hearing and, upon notice and an opportunity to be heard, may assess a civil penalty of

- (a) not less than \$___ nor more than \$___ for a first violation,
- (b) not less than \$___ nor more than \$___ for a second violation within 2 years from the date of the first violation, and
- (c) not less than \$___ nor more than \$___ for a third violation within 2 years from the date of the first violation.

19.3. Judicial Review. The final decision of the Director shall be subject to appropriate judicial review.

19.4. Transmittal of Monies. Any civil penalty collected under this Act shall be transmitted to the state treasurer, who shall credit the same to the ___ fund.

Section 20. Criminal Penalties

20.1. Misdemeanor. Any person who, by him/herself by his/her servant or agent, or as the servant or agent of another person commits any of the acts enumerated in Section 17 or violates any other provision of this Act shall be guilty of a Class___ misdemeanor and upon conviction shall be punished by a fine not less than \$___ nor more than \$___, or by imprisonment for not less than ___ nor more than ___, or both fine and imprisonment.

20.2. Felony. Any person who by him/herself by his/her servant or agent, or as the servant or agent of another person intentionally commits any of the acts enumerated in Section 17 or repeatedly violates any other provision of this Act shall be guilty of a Class___ felony and upon conviction shall be punished by a fine not less than \$___ and/or by imprisonment for not less than ___ nor more than ___ or more than ___.

Section 21. Restraining Order and Injunction

The Director is authorized to apply to any court of competent jurisdiction for a restraining order, or a temporary or permanent injunction, restraining any person from violating any provision of this Act.

Section 22. Validity of Prosecutions

Prosecutions for violation of any provision of this Act are declared to be valid and proper notwithstanding the existence of any other valid general or specific Act of this State dealing with matters that may be the same as or similar to those covered by this Act.

Section 23. Separability Provision

If any provision of this Act is declared unconstitutional, or the applicability thereof to any person or circumstance is held invalid, the constitutionality of the remainder of the Act and the applicability thereof to other persons and circumstances shall not be affected.

Section 24. Repeal of Conflicting Laws

All laws and parts of laws contrary to or inconsistent with the provisions of this Act, and specifically _____, are repealed insofar as they might operate in the future; but as to offenses committed, liabilities incurred, and claims now existing thereunder, the existing law shall remain in full force and effect.

Section 25. Citation

This Act may be cited as the "Public Weighmaster Act of _____."

Section 26. Effective Date

This Act shall become effective on _____.



Appendix B National Conference on Weights and Measures

POLICY, INTERPRETATIONS, AND GUIDELINES

SECTION 2 - Laws, Regulations and Commodity Control

SUBSECTION 3 - Method of Sale

2.3.2. Fresh Fruits and Vegetables

(L&R, 1979, p. 176; 1980; 1982, p. 152)

Guideline

Recognizing the difficulty faced by consumers when more than one method of sale is employed in the same outlet for the same product, noncomparable methods of sale (e.g., weight and measure) for the same produce item in the same outlet should be minimized.

The methods of retail sale for fresh fruits and vegetables should be:

Commodity	Method of Sale
Apples	Weight or count, or by dry measure in units not less than $\pm \frac{1}{2}$ peck
Apricots	Weight
Artichokes	Weight or count
Asparagus	Weight or bunch
Avocados	Count
Bananas	Weight
Beans	Weight or dry measure, in units not less than $\pm \frac{1}{2}$ peck
Beets	Weight or bunch
Berries (all) ¹	Weight or measure
Broccoli	Weight or bunch
Brussels sprouts	Weight
Cabbage	Weight
Cantaloupes	Weight or count
Carrots	Weight or bunch
Cauliflower	Weight or bunch
Celery	Weight or count
Cherries ¹	Weight or measure
Coconuts	Weight or count
Corn on cob	Count
Cranberries ¹	Weight or measure

¹ Commodities sold by measure must be sold in containers standardized by the Berry Basket and Box Code in Handbook 44.

2.3.2. Fresh Fruits and Vegetables

Commodity	Method of Sale
Cucumbers	Weight or count
Currants ¹	Weight or measure
Dates	Weight
Eggplant	Weight or count
<u>Endive</u>	<u>Weight or bunch</u>
Escarole	Weight or bunch
Figs	Weight
Garlic	Weight or count
<u>Ginger root</u>	<u>Weight or count</u>
Grapefruits	Weight or count
Grapes	Weight
Greens (all)	Weight
<u>Horseradish root</u>	<u>Weight or bunch</u>
Kale	Weight
Kohlrabi	Weight
<u>Kiwi fruit</u>	<u>Weight or count</u>
<u>Kumquats</u>	<u>Weight or count</u>
Leeks	Weight
Lemons	Weight or count
Lettuce	Weight or count
Limes	Weight or count
Mangoes	Weight or count
Melons (whole)	Weight or count
Melons (cut or pieces)	Weight
Mushrooms	Weight or measure
Nectarines	Weight or count
<u>Nuts</u>	<u>Weight</u>
Okra	Weight
Onions (spring or green)	Weight or bunch
Onions (dry)	Weight
Oranges	Weight or count
Papaya	Weight or count
Parsley	Weight or bunch
Parsnips	Weight
Peaches	Weight or count, or by dry measure in units not less than $\pm \frac{1}{2}$ peck
Pears	Weight or count, or by dry measure in units not less than $\pm \frac{1}{2}$ peck
Peas	Weight
Peppers	Weight or count
Persimmons	Weight or count
Plums	Weight or dry measure, in units not less than $\pm \frac{1}{2}$ peck
Pineapples	Weight or count

¹ Commodities sold by measure must be sold in containers standardized by the Berry Basket and Box Code in Handbook 44.

2.3.2. Fresh Fruits and Vegetables

Commodity	Method of Sale
Pomegranates	Weight or count
Potatoes (Irish or sweet)	Weight
Prunes	Weight
Pumpkins	Weight or count
<u>Quinces</u>	<u>Weight or count</u>
Radishes	Weight
Rhubarb	Weight
Rutabagas	Weight
Spinach	Weight or bunch
<u>Sprouts</u>	<u>Weight</u>
<u>Squash</u>	<u>Weight</u>
<u>Tangelos</u>	<u>Weight or count</u>
Tangerines	Weight or count
Tomatoes	Weight or dry measure, in units not less than $\pm \frac{1}{2}$ peck
Tomatoes (cherry) ¹	Weight or measure
Turnips	Weight or bunch

¹ Commodities sold by measure must be sold in containers standardized by the Berry Basket and Box Code in Handbook 44.

Appendix C

Meat and Poultry Products A Consumer Guide to Content and Labeling Requirements¹

Food Standards

The U.S. Department of Agriculture's Food Safety and Inspection Service (FSIS) and the U.S. Department of Health and Human Services' Food and Drug Administration (FDA) share the responsibility of assuring truthful and accurate information on product labels. FSIS has authority over all products containing more than 3 percent fresh meat or at least 2 percent cooked poultry meat. FDA oversees the labeling of most other food products.

Both agencies use a system of "food standards." These standards set requirements on the kinds and amounts of ingredients used in the manufacture of processed foods. Basically, these standards assure consumers that, if a product goes by a particular name, it will have certain characteristics.

USDA Standards of Identity and Composition

Almost all standards enforced by FSIS are called "standards of composition." These standards identify the minimum amount of meat or poultry required in a product's recipe. For example, the standard of composition for "chicken a la king" states that, if a product carries this name on its label, at least 20 percent cooked poultry meat must be used in the recipe.

But standards of composition don't prevent a manufacturer from increasing the meat or poultry content or adding other ingredients, to increase a product's appeal. For instance, a processor has the option of using more than the required amount of chicken in chicken a la king and adding other ingredients to make the product unique.

"Standards of identity," on the other hand, set specific requirements for a food's makeup: the kind and minimum amount of meat or poultry; maximum amount of fat or moisture; and any other ingredients allowed. Corned beef hash and chopped ham are two FSIS-regulated products that have standards of identity.

Label Approval

Before a product may be marketed, its label must be examined and approved by FSIS staff specialists. Food manufacturers submit over 100,000 labels a year for agency review. Label approval applications must include the product name, formula, method of preparation, type of container, and how the label is to be used.

A number of labeling regulations apply across-the-board to all meat and poultry products. These include: appropriate product name; ingredients, listed from most to least, by weight in the product recipe; net quantity of the package contents; name and address of the manufacturer, packer, or distributor; the USDA mark of inspection; and any special care or handling instructions, such as "keep refrigerated." In addition, label photographs or artwork depicting a product must not be misleading.

To assure consumers that the names of meat and poultry products accurately reflect the contents of these products, label reviewers evaluate product formulas and methods of preparation by comparing them with official standards in the meat and poultry inspection regulations. Because unpublished standards are used to evaluate some products, FSIS labeling policies also provide guidance.

Sometimes, no standard exists for a certain product. In these cases, a manufacturer can either give the product a "descriptive" name, such as "Chopped and Formed Cured Pork Product," or use a "fanciful" name accompanied by a descriptive name—"Breakfast Strips: Chopped and Formed Cured Pork Product." A manufacturer may also submit a proposal to FSIS, requesting a standard for the product.

Why You Should Know About Content and Labeling Requirements

¹Home and Garden Bulletin No. 236

Although Federal labeling laws and regulations are established to protect the public, consumers are sometimes unaware of how to use the information on product labels. FSIS content and labeling requirements provide a simple means by which consumers can learn what to expect from a product if it is labeled with a particular name.

If you know that product names are required to truthfully reflect product content, much can be learned just by noting the order in which major ingredients appear. For example, the name "Beef with Gravy" tells you that there is more beef in that product than in one called "Gravy with Beef."

This guide includes listings for over 250 popular meat and poultry products—from baby food to won ton soup.

For your convenience, the list of meat and poultry product content and labeling requirements is divided into two sections—"Meat Products" and "Poultry Products." Some product definitions include terms that are further defined elsewhere in the guide. For example, the "meatballs" in "spaghetti and meatballs" (page 124) is defined on page 123. The term byproducts is explained on pages 126, in the DEFINITIONS section.

Meat Products

All percentages of meat are on the basis of fresh uncooked weight unless otherwise indicated. Keep in mind the meat may shrink in weight after cooking because fat and water cook away.

Baby Food

High Meat Dinner—At least 26% meat.

Meat and Broth—At least 61% meat.

Vegetable with Meat—At least 8% meat.

Bacon (Cooked)—Weight of cooked bacon is 40% of uncooked, cured, smoked bacon.

Bacon and Tomato Spread—At least 20% cooked bacon.

Bacon Dressing—At least 8% cured, smoked bacon.

Barbecue Sauce with Meat—At least 35% meat (cooked basis).

Barbecued Meat—Weight of meat when barbecued can't exceed 70% of the fresh uncooked meat. Must have barbecued (crusted) appearance and be prepared over burning or smoldering hardwood or its sawdust. If cooked by other drying means, product name must mention the method of cooking.

Beans with Bacon or Ham in Sauce—At least 12% bacon or ham (cooked basis).

Beans with Frankfurters in Sauce—At least 20% franks.

Beans with Meat in Sauce—At least 12% meat.

Beans with Meatballs in Sauce—At least 20% meatballs.

Beef a la King—At least 20% beef (cooked basis).

Beef a la Mode—At least 50% beef.

Beef Almandine with Vegetables—At least 18% beef (cooked basis). Product must contain almonds.

Beef and Dumplings with Gravy or Beef and Gravy with Dumplings—At least 25% beef.

Beef Burgundy—At least 50% beef; enough wine to characterize the sauce.

Beef Carbonade—At least 50% beef.

Beef Roulade—At least 50% beef (cooked basis).

Beef Sausage (raw)—No more than 30% fat. No byproducts, no extenders and no more than 3% water.

Beef Stroganoff—At least 45% fresh, uncooked beef or 30% cooked beef and one of the following: at least 10% sour cream; or a combination of at least 7 1/2% sour cream and 5% wine; or 9 1/2% whole milk, 2% sour cream, and 2 1/2% wine.

Beef with Barbecue Sauce—At least 50% beef (cooked basis).

Beef with Gravy—At least 50% beef (cooked basis).

Breaded Steaks, Chops, etc.—Breading can't exceed 30% of finished product weight.

Breakfast (frozen product containing meat)—At least 15% cooked meat based on total net weight of breakfast.

Breakfast Sausage—No more than 50% fat. May contain 3 1/2% binders and extenders, and 3% water.

Brown and Serve Sausage—No more than 35% fat and no more than 10% added water.

Brunswick Stew—At least 25% meat, made up of at least two kinds of meat, including poultry meat. Must contain corn as one of the vegetables.

Burgundy Sauce with Beef and Noodles—At least 25% beef (cooked basis) and up to 20% noodles; enough wine to characterize the sauce.

Burrito-At least 15% meat.

Cabbage Rolls with Meat in Sauce-At least 12% meat.

Cannelloni with Meat and Sauce-At least 10% meat.

Cappelletti with Meat in Sauce-At least 12% meat.

Cheesefurter-Shall contain sufficient cheese to characterize the product.

Chili con Carne-At least 40% meat.

Chili con Carne with Beans-At least 25% meat.

Chili Hot Dog with Meat-At least 40%

Chili Mac-At least 16% meat. Must be qualified with true product name: "Beans, Macaroni, and Beef in Sauce."

Chili Sauce with Meat-At least 6% meat.

Chop Suey (American Style) with Macaroni and Meat-At least 25% meat.

Chop Suey Vegetables with Meat-At least 12% meat.

Chopped Ham-Must be prepared from fresh, cured, or smoked ham, plus certain kinds of curing agents and seasonings. May contain dehydrated onions, dehydrated garlic, corn syrup, and not more than 3% water to dissolve the curing agents.

Chow Mein Vegetables with Meat-At least 12% meat.

Chow Mein Vegetables with Meat and Noodles-At least 8% meat and the noodles must equal no more than 1/3 of the product.

Corn Dog-Must be accompanied by true product name, "Batter Wrapped Franks on a Stick." Limited to 65% batter and a minimum of 35% frankfurter.

Corned Beef and Cabbage-At least 25% corned beef (cooked basis).

Corned Beef Hash-At least 35% beef (cooked basis). Must contain potatoes, curing agents, and seasonings. May contain onions, garlic, beef broth, beef fat, or others. No more than 15% fat; no more than 72% moisture.

Country Ham-A dry-cured product frequently coated with spices. Minimum 4% salt content.

Creamed Meat Products or Creamed Sauce with Meat Products (Chipped Beef, Cooked Beef, Cured Beef, Ham, Franks, Meatballs, etc.)-At least 18% meat product (cooked basis).

Crepe with Meat-Based on total net weight of product; at least 20% meat (cooked basis) if filling has no other major characterizing ingredient, or 10% meat (cooked basis) if one other major characterizing ingredient ("Crepe with Meat and Cheese," for example).

Croquettes-At least 35% meat (cooked basis); 50% fresh basis.

Curried Sauce with Meat and Rice (casserole)-At least 35% meat (cooked basis) in the sauce and meat part. No more than 50% cooked rice.

Deviled Ham-No more than 35% fat; no added moisture; no cereal.

Dinner (frozen product containing meat)-At least 25% meat or meat food product (cooked basis) figured on total meal minus appetizer, bread, and dessert. Consumer package must weigh at least 10 ounces (284 grams).

Dumplings with Meat in Sauce-At least 18% meat.

Egg Foo Yong with Meat-At least 12% meat.

Egg Roll with Meat-At least 10% meat.

Egg Roll with Meat and Seafood-At least 5% meat.

Eggs Benedict-At least 18% cured smoked ham.

Enchilada with Meat-At least 15% meat.

Entree: Meat or Meat Food Product and One Vegetable-At least 50% meat or meat food product (cooked basis).

Frankfurter, Bologna, and Similar Cooked Sausage-May contain only skeletal Meat. No more than 30% fat, 10% added water, and 2% corn syrup. No more than 15% poultry meat (exclusive of water in formula).

Frankfurter, Bologna, and Similar Cooked Sausage with Byproducts or Variety Meats-Same limitations as above on fat, added water, and corn syrup. Must contain at least 15% skeletal meat. These products must be specifically labeled, such as "Frankfurters with Byproducts," and each byproduct or variety meat must be specifically named in the list of ingredients. These include heart, tongue, spleen, tripe, and stomach.

Frankfurter, Bologna, and Similar Cooked Sausage with Byproducts or Variety Meats and which also Contain Nonmeat Binders-Product made with the above formulas and also containing up to 3 1/2% nonmeat binders (or 2% isolated soy protein). These products must be distinctively labeled, such as, "Frankfurters with Byproducts, Nonfat Dry Milk Added." The binders may be named in their proper order in the list of ingredients.

Laws and Regulations Committee

Fried Rice with Meat-At least 10% meat.

Fritter-At least 35% meat; no more than 65% breading.

German Style Potato Salad with Bacon-At least 14% bacon (cooked basis).

Goulash-At least 25% meat.

Gravy-At least 25% meat stock or broth, or at least 6% meat.

Gravy and Sauerbraten-35% meat (cooked basis).

Gravy and Swiss Steak-At least 35% meat (cooked basis).

Gravy and Yankee Pot Roast-At least 35% meat (cooked basis).

Gravy with Beef-At least 35% beef (cooked basis).

Ham (canned)-Limited to 8% total weight gain after processing.

Ham, Cooked or Cooked and Smoked (not canned)-Must not weigh more after processing than the fresh ham weights before curing and smoking; if contains up to 10% added weight, must be labeled, "Ham, Water Added."

Ham a la King-At least 20% ham (cooked basis).

Ham and Cheese Spread-At least 25% ham (cooked basis).

Ham Chowder

Ready-to-Eat-At least 5% ham (cooked basis)

Condensed-At least 10% ham (cooked basis).

Ham Salad-At least 35% ham (cooked basis).

Ham Spread-At least 50% ham.

Hamburger, Hamburg, Burger, Ground Beef, or Chopped Beef-No more than 30% fat; no extenders.

Hash-At least 35% meat (cooked basis).

Hors d'oeuvre-At least 15% meat (cooked basis) or 10% bacon (cooked basis).

Jambalaya with Meat-At least 25% meat cooked basis).

Knish-At least 15% meat (cooked basis).

Kreplach-At least 20% meat.

Lasagna with Meat and Sauce, or Cheese Lasagna with Meat-At least 12% meat.

Lasagna with Meat Sauce-At least 6% meat.

Lasagna with Sauce, Cheese, and Dry Sausage-At least 8% dry sausage.

Lima Beans with Ham or Bacon in Sauce-At least 12% ham or bacon (cooked basis).

Liver Products, such as Liver Loaf, Liver Paste, Liver Pate, Liver Cheese, Liver Spread, Liverwurst, Braunschweiger, and liver Sausage-At least 30% liver.

Macaroni and Beef in Sauce-At least 12% beef.

Macaroni and Cheese with Ham-At least 12 ham (cooked basis).

Macaroni and Meat-At least 25% meat.

Macaroni Salad with Ham or Beef-At least 12% meat (cooked basis).

Manicotti with Meat in Sauce (contains a meat filling)-At least 10% meat.

Margarine or Oleomargarine-If product is entirely of animal fat or contains some animal fat, it is processed under Federal inspection. Must contain-individually or in combination-pasteurized cream, cow's milk, skim milk, combination of nonfat dry milk and water or finely ground soybeans and water. May contain butter, salt, artificial colorings, vitamins A and D, and permitted functional substances. Finished product must contain at least 80% fat from animal or vegetable sources. Label must clearly state which types of fat are used.

Meat and Dumplings in Sauce-At least 25% meat.

Meat and Vegetables-At least 50% meat.

Meat Casserole-At least 25% fresh, uncooked meat or 18% cooked meat.

Meat Curry-At least 50% meat.

Meat Loaf (baked or oven-ready)-At least 65% meat and no more than 12% cereal products.

Meat Pasty-At least 25% meat.

Meat Pie or Vegetable Meat Pie-At least 25% meat.

Meat Ravioli-At least 10% meat in ravioli.

Meat Ravioli in Sauce-At least 10% meat in ravioli; at least 50% ravioli in total product.

Meat Salad-At least 35% meat (cooked basis).

Meat Sauce-At least 6% meat.

Meat Soup

Ready-to-Eat-At least 5% meat.

Condensed-At least 10% meat.

Meat Spread-At least 50% meat.

Meat Stew-At least 25% meat.

Meat Taco-At least 15% meat.

Meat Taco Filling-At least 40% meat.

Meat Turnover-At least 25% meat.

Meat Wellington-At least 50% cooked tenderloin spread with liver pate or similar coating and covered with not more than 30% pastry.

Meatballs-No more than 12% extenders, including textured vegetable protein. At least 65% meat.

Meatballs in Sauce-At least 50% meatballs (cooked basis).

Meatball Stroganoff-At least 45% meatballs (cooked basis).

Mince Meat-At least 12% meat.

Mousaka-At least 25% meat. Must be qualified on label as "Eggplant and Meat Casserole."

New England Boiled Dinner-At least 25% cooked corned beef.

Omelet with Bacon-At least 9% bacon (cooked basis).

Omelet with Dry Sausage-At least 12% dry sausage.

Omelet with Ham-At least 18% ham (cooked basis).

Omelet with Meat Food Product, such as Creamed Chipped Beef or Corned Beef Hash-At least 25% meat food product.

Omelet, Western-At least 18% cooked ham. Contains onions and green and/or red bell peppers.

Pate de Foie-At least 30% liver.

Pepper Steak (Chinese)-At least 30% thin, braised strips of beef (cooked basis).

Peppers and Italian Sausage in Sauce-At least 20% sausage (cooked basis).

Pizza with Meat-At least 15% meat.

Pizza with Sausage-At least 12% sausage (cooked basis) or 10% dry sausage, such as pepperoni.

Pork Sausage-Nor more than 50% fat or 3% water; may contain no byproducts or extenders.

Pork with Barbecue Sauce-At least 50% port (cooked basis).

Pork with Dressing-At least 50% pork (cooked basis).

Pork with Dressing and Gravy-At least 30% pork (cooked basis).

Proscuitto-A flat, dry-cured ham coated with spices.

Quiche Lorraine-At least 8% bacon or ham (cooked basis) and 10% swiss or gruyere cheese.

Rice with Meat-At least 12% meat.

Salisbury Steak-At least 65% meat and no more than 12% extenders, including textured vegetable protein.

Sandwich Meat-At least 35% meat in total sandwich; bread component may not exceed 50% of the sandwich.

Sauerbraten-At least 50% beef (cooked basis).

Sauerkraut Balls with Meat-At least 30% meat.

Sauerkraut with Wieners and Juice-At least 20% wieners.

Sausage with Sauerkraut in Sauce-At least 40% sausage (cooked basis).

Scalloped Potatoes and Ham or Sausage-At least 20% ham or sausage (cooked basis).

Scallopini ("Veal Scallopini," for example)-At least 35% meat (cooked basis).

Scrambled Eggs with Ham in a Pancake-At least 9% ham (cooked basis).

Scrapple-At least 40% meat and/or meat byproducts.

Shepherd's Pie-At least 25% meat; no more than 50% mashed potatoes.

Sloppy Joe-At least 35% meat (cooked basis). Must be qualified with true product name, "Barbecue Sauce with Beef."

Snack-At least 15% meat (cooked basis) or 10% bacon (cooked basis).

Spaghetti Sauce with Meat-At least 6% meat.

Spaghetti with Meat or Meatballs in Sauce-At least 12% meat.

Spanish Rice with Meat-At least 20% meat (cooked basis).

Stuffed Cabbage with Meat in Sauce-At least 12% meat.

Stuffed Pepper with Meat in Sauce-At least 12% meat.

Sukiyaki-At least 30% meat.

Sweet and Sour Meat-At least 25% meat and at least 16% fruit.

Laws and Regulations Committee

Swiss Steak with Gravy-At least 50% meat (cooked basis).

Tamale-At least 25% meat.

Tamale with Sauce or Gravy-At least 20% meat.

Tamale Pie-At least 20% meat; filling must be at least 40% of total product.

Taquito-At least 15% meat.

Tongue Spread-At least 50% tongue.

Tortellini with Meat-At least 10% meat.

Tortellini with Meat in Sauce-At least 50% cooked meat tortellini.

Veal and Peppers in Sauce-At least 30% meat (cooked basis).

Veal Bird-At least 60% meat and no more than 40% stuffing.

Veal Cordon Bleu-At least 60% veal, 5% ham, and containing swiss, gruyere, mozzarella, or pasteurized process swiss cheese.

Veal Fricassee-At least 40% meat.

Veal Parmigiana-At least 40% breaded veal in sauce.

Veal Scallopini-At least 35% veal (cooked Basis).

Veal Steak-Chopped, shaped, cubed, frozen. Beef can be added up to 20% with product name shown as, "Veal Steaks, Beef Added, Chopped, Shaped, and Cubed." If more than 20% beef, must be labeled, "Veal and Beef Steak, Chopped, Shaped, and Cubed." No more than 30% fat in total product.

Vegetable and Meat Casserole-At least 25% meat.

Vegetable and Meat Pie-At least 25% meat.

Won Ton Soup-At least 5% meat.

Poultry Products

All percentages of poultry are on cooked, deboned basis unless otherwise indicated. When standard indicates poultry meat, skin, and fat, the skin and fat are in proportions normal to poultry.

Baby Food

High Poultry Dinner-At least 18 3/4% poultry meat, skin, fat, and giblets.

Poultry with Broth-At least 43% poultry meat, skin, fat, and giblets.

Beans and Rice with Poultry-At least 6% poultry meat.

Breaded Poultry-No more than 30% breading.

Canned Boned Poultry

Boned (kind) Solid Pack-At least 95% poultry meat, skin, and fat.

Boned (kind)-At least 90% poultry meat, skin, and fat. **Boned (kind), with Broth**-At least 80% poultry meat, skin, and fat.

Boned (kind), with Specified Percentage of Broth-At least 50% poultry meat, skin, and fat.

Cannelloni-At least 7% poultry meat.

Chicken Cordon Bleu-At least 60% boneless chicken breast (raw basis), 5% ham, and either swiss, gruyere, or mozzarella cheese. (If breaded, no more than 30% breading).

Creamed Poultry-At least 20% poultry meat. Product must contain some cream.

Egg Roll with Poultry-At least 2% poultry meat.

Eggplant Parmigiana with Poultry-At least 8% poultry meat.

Entree: Poultry or Poultry Food Products and One Vegetable-At least 37 1/2% poultry meat or poultry food product.

Gravy with Poultry-At least 15% poultry meat.

Noodles or Dumplings with Poultry-At least 6% poultry meat.

Poultry a la Kiev-Must be breast meat (may have attached skin) stuffed with butter and chives.

Poultry a la King-At least 20% poultry meat.

Poultry Almandine-At least 50% poultry meat. Product must contain almonds.

Poultry Brunswick Stew-At least 12% poultry meat. Must contain corn.

Poultry Burgers-100% poultry, with skin and fat not in excess of natural proportions.

Poultry Burgundy-At least 50% poultry meat; enough wine to characterize the product.

Poultry Burrito-At least 10% poultry meat.

Poultry Cacciatore-At least 20% poultry meat, or 40% with bone.

Poultry Casserole-At least 18% poultry meat.

Poultry Chili-At least 28% poultry meat.

Poultry Chili with Beans-At least 17% poultry meat

Poultry Chop Suey-At least 4% poultry meat.

Poultry Chow Mein (without noodles)-At least 4% poultry meat.

Poultry Creole with Rice-At least 35% cooked meat in poultry and sauce portion. Not more than 50% rice in total product.

Poultry Croquette-At least 25% poultry meat.

Poultry Croquette with Macaroni and Cheese-At least 29% croquettes.

Poultry Dinner (a frozen product)-At least 18% poultry meat, figured on total meal menu minus appetizer, bread, and dessert.

Poultry Empanadillo (a poultry turnover)-At least 25% poultry meat.

Poultry Fricassee-At least 20% poultry meat.

Poultry Fricassee of Wings-At least 40% poultry wings (cooked basis, with bone).

Poultry Hash-At least 30% poultry meat.

Poultry Lasagna-At least 8% poultry meat (raw basis).

Poultry Livers with Rice and Gravy-At least 30% livers in poultry and gravy portion, or 17½% in total product.

Poultry Meat Loaf-A minimum of 65% raw poultry or 50% poultry meat, and a maximum of 12% extenders.

Poultry Paella-At least 35% poultry meat or 35% poultry meat and other meat (cooked basis); no more than 35% cooked rice. Must contain seafood.

Poultry Parmigiana-At least 40% breaded poultry.

Poultry Pie-At least 14% poultry meat.

Poultry Ravioli-At least 2% poultry meat.

Poultry Roll-No more than 3% binding agents, such as gelatin, in the cooked product; no more than 2% natural cooked-out juices.

Poultry Roll with Broth-Contains more than 2% poultry broth in addition to natural cooked-out juices.

Poultry Roll with Gelatin-Gelatin exceeds 3% of cooked product.

Poultry Roll with Natural Juices-Contains more than 2% natural cooked-out juices.

Poultry Salad-At least 25% poultry meat (with normal amounts of skin and fat).

Poultry Scallopini-At least 35% poultry meat.

Poultry Soup

Ready-to-Eat-At least 2% poultry meat.

Condensed-At least 4% poultry meat.

Poultry Stew-At least 12% poultry meat.

Poultry Stroganoff-At least 30% poultry meat and at least 10% sour cream or a "gourmet" combination of at least 7 ½% sour cream and 5% wine.

Poultry Tamale-At least 6% poultry meat.

Poultry Tetrazzini-At least 15% poultry meat.

Poultry Turnover-At least 14% poultry meat.

Poultry Wellington-At least 50% boneless poultry breast spread with a liver or similar pate coating and covered in not more than 30% pastry.

Poultry with Gravy-At least 35% poultry meat.

Poultry with Gravy and Dressing-At least 25% poultry meat.

Poultry with Noodles au Gratin-At least 18% poultry meat.

Poultry with Noodles or Dumplings-At least 15% poultry meat, or 30% with bone.

Poultry with Rice-At least 15% poultry meat.

Poultry with Vegetables-At least 15% poultry meat.

Sauce with Poultry or Poultry Sauce-At least 6% poultry meat.

Stuffed Cabbage with Poultry-At least 8% poultry meat.

Stuffed Peppers with Poultry-At least 8% poultry meat.

Turkey Ham-A product made with cured turkey thigh meat only.

Definitions

Some terms used throughout this document are defined below:

Binders, Extenders-Binders and extenders help to hold a meat or poultry product together, and also aid in retaining product moisture. Sometimes, these ingredients are used to supplement the required minimum amount of meat or poultry present in a product.

Cure-Curing ingredients are used to preserve such products as ham, frankfurters, and bacon. They also give these products their characteristic taste and color. Today, almost all curing of meats is done by adding limited amounts of nitrite in combination with salt during processing. If nitrite-cured products are stored at the proper temperature, the presence of nitrite prevents the growth of organisms that cause botulism in humans.

Meat-Meat comes from the muscles of cattle, sheep, swine, and goats. "Skeletal" meat refers to the muscular cuts which were attached to the animal's bone structure. Muscle found in the tongue and heart is also defined as "meat," but is permitted only in some meat products. Regulations require that all meats be identified by species (type) of animal, and, if meat from the tongue or heart is used, it must be named in the list of ingredients.

Meat Byproducts (sometimes known as "variety meats")-These terms refer to the edible and wholesome parts of cattle, sheep, swine, and goats, other than skeletal meat. Whenever byproducts are added to meat products, each specific byproduct must be named in the list of ingredients.

Meat Food Product (also known as "meat product")-Any food suitable for human consumption made from cattle, sheep, swine, or goats, containing more than 3 percent meat.

Poultry-All domesticated birds (chickens, turkeys, ducks, geese, guineas).

Poultry Byproducts-All edible parts of poultry other than sex glands and "poultry meat."

Poultry Food Product (also known as "poultry product")-Any food suitable for human consumption made from any domesticated bird, containing more than 2 percent poultry meat.

Poultry Meat-This term refers to the white and dark meat portions of deboned poultry, excluding fat, skin, and other edible poultry parts.

Vegetable (Plant) Protein-Vegetable protein products derived from soybeans may be used as binders or extenders in such meat and poultry products as sausages, luncheon meats, soups, sauces, and gravies. Sometimes, they are the main ingredients in meat and poultry product substitutes. Soybeans are processed into three basic soy protein products: soy flour, soy protein concentrate, and isolated soy vegetable protein. Whenever soy protein is added to a meat or poultry product, its presence is noted in the ingredient statement on the label. In some instances, it is also included in the product name, e.g., "Beef and Textured Vegetable Protein Burritos."

Appendix D

Test Method for Compressed Gases

for inclusion into Handbook 133

4.6.4. Method D: Determining the Net Contents of Compressed Gas in Cylinders. These procedures are for industrial compressed gas.

Compressed gas may be labeled by weight (for example, LP gas or carbon dioxide) or by volume. Acetylene, liquid oxygen, nitrogen, nitrous oxide, and argon are filled by weight, but sold by cubic feet (acetylene) or by liters (for the other products listed). Helium, gaseous oxygen, nitrogen, air, and argon are filled following pressure and temperature tables. Checking the net contents of compressed gas cylinders depends on the method of fill; those filled by weight may be checked by weight. It is unnecessary to connect the cylinder to anything, but it may be necessary to move the cylinder to weigh it. In addition, it may be necessary to schedule testing over a 2-day period if acetylene is one of the products to be checked; it takes from 10 to 12 hours to fill acetylene cylinders. Once the tare weight has been determined, it will require another day to test filled cylinders for which the tare weight is known.

Those cylinders filled by using pressure and temperature charts must be tested by connecting a pressure gauge to the cylinder and determining the pressure and temperature.

Safety is a primary concern with all testing procedures.

A. Safety

Anyone handling a compressed gas cylinder must be made aware of the hazards of high pressures found with any compressed gas. Untrained or partially trained individuals should not be allowed to handle compressed gas.

It is essential that anyone handling a cylinder of gas or cryogenic liquid be certain of the contents before the cylinder is connected to anything. Discharging a gas or cryogenic liquid through a system for which the material is not intended could result in damage due to the incompatibility of the system and the product. A fire and/or explosion could be the result of such a mistake.

Before connecting a cylinder to anything, be certain of the following:

1. The cylinder is clearly marked or labeled with the name of the contents and that there are no conflicting marks or labels. Do not rely on the color of the cylinder to identify the contents of a cylinder.
2. The marked or labeled contents are all correct.
3. The cylinder is provided with the correct Compressed Gas Association (CGA) connection(s) for the product.
4. The connection(s) on the cylinder properly fits the system. A proper connection will go together smoothly. Do not use excessive force. Do not use an adaptor to connect oxygen to non-oxygen cleaned equipment.
5. Personnel moving or using cylinders are trained and knowledgeable regarding the product, cylinder, fittings, and proper procedures. See CGA pamphlet P-1 "Safe Handling of Compressed Gases in Containers," for additional information.

Warning! Failure to observe the precautions above is reported to have caused fatalities.

B. Additional Safety Warnings

1. The inspector must have a thorough knowledge of the procedure, with emphasis on safety precautions, before attempting any tests. Charts referred to in the procedure should not be furnished to inspectors until the necessary training has been completed.
2. The inspector must be extremely careful with all gases since some react violently when mixed or when coming in contact with other substances. For example, oxygen reacts violently when it comes in contact with hydrocarbons.
3. Always wear safety glasses when testing cylinders by the temperature-pressure method.
4. When moving a cylinder, always place the protective cap on the cylinder. Do not leave spaces between cylinders when moving them. This can lead to a "domino" effect if one cylinder is pushed over.
5. When a cylinder valve is opened to measure the internal pressure, position your body away from the pressure gauge blowout plug or in front of the gauge if the gauge has a solid cast front case. If the bourdon tube should rupture, you do not want to be in a position to receive serious injuries from gas pressure or fragments of metal.
6. Open all valves slowly. A failure of the gauge or other ancillary equipment can result in injuries to nearby persons. Remember: high gas pressure can propel objects with great force. Gas ejected under pressure can also cause serious bodily injuries if someone is too close during release of pressure.
7. One of the gauges shall be reserved for testing oxygen only and shall be prominently labeled "For Oxygen Use Only." See 4.6.4. (A) 2. This gauge must be cleaned for oxygen service and maintained in that "clean" condition.
8. The other gauge(s) may be used for testing a variety of gases if they are compatible with one another.
9. Special precautions must be observed with flammable gas in cylinders, in addition to the several precautions necessary for the safe handling of any compressed gas in cylinders.

Contrary to general practice with other gas cylinders, do not "crack" cylinder valves of flammable gas before connecting them to a regulator or test gauge. This is extremely important for hydrogen or acetylene.

10. Additional precautions necessary for personal safety are described in the Handbook of Compressed Gases. All personnel testing compressed gases should have this manual for reference and be familiar with its contents.

C. Equipment

1. Scale, calibrated weights, and ramp.
2. Two (2) calibrated precision bourdon tube gauges or any other approved laboratory-type pressure-measuring device that can be accurately read within plus or minus 5 psi. A gauge having scale increments of 25 psi or smaller shall be considered as satisfactory for reading within plus or minus 5 psi. The range of both gauges shall be a minimum of 0 to 5000 pounds per square inch when testing cylinders with standard industrial cylinder valve connections. Standard industrial cylinder connections are those connections listed in CGA Standard V-1, Standard for Compressed Gas Cylinder Valve Outlet and Inlet Connections,¹ for use with gas pressures up to 3000 psig (20 680 k Pa). For testing cylinders with cylinder valve connections rated for over 3000 psig, the test gauge and its inlet connection must be rated at 2000 psig over the maximum pressure that the connection is rated for in CGA V-1. (Note that there are standard high pressure industrial connections on the market that are being used up to their maximum pressure of 7500 psig.)

Any gauge or connectors used with oxygen cylinders must be cleaned for oxygen service, transported in a manner which will keep them clean and never used for any other gas including air or oxygen mixtures. Oxygen will react with hydrocarbons and many foreign materials and can result in fire or explosion.

3. An approved and calibrated electronic temperature measuring device or three calibrated mercury-in-glass thermometers having either a digital readout or scale division of no more than 1 degree. The electronic device equipped with a surface temperature sensor is preferred over a mercury-in-glass thermometer because of its shorter response time.

4. Safety glasses.

5. Two wrenches. Box wrenches of 1 1/8 inch for oxygen, nitrogen, carbon dioxide, argon, helium, and hydrogen and 7/8 inch for some sizes of propane. All industrial CGA connections are limited to these two hex sizes. Use of an adjustable wrench should be avoided because of the tendency to round the edges of the fittings which can lead to connections not being tightened properly.
6. It is best to use a separate gauge and fitting for each gas to be tested. If adaptors must be used, be sure that they are never used on oxygen systems.

D.Procedure

Containers must be labeled in compliance with NIST Handbook 130 requirements. Containers which do not bear a labeled statement of net quantity will be marked "off sale" until the containers are brought into compliance.

1. Testing by Weight

- (a) The cylinder is stamped or stenciled with a tare weight. This is a safety feature that assists the filling plant in many of its filling operations. It may or may not be the weight used by the filling plant when determining the net weight of those cylinders sold or filled by weight. If there is a tare weight marked on the net contents tag or directly on the cylinder, then an actual tare weight was determined at the time of fill. If there is no tare weight marked on a tag or on the cylinder, then the stamped or stenciled tare weight was used to determine the net contents. When the stamped or stenciled tare weight is used in net contents determinations, the inspector should check the accuracy of the stamped tare weights. The actual tare weight must be within
 - (1) 1/2 percent of the stamped tare weight for 20 lb tare weights or less, or
 - (2) 1/4 percent of the stamped tare weight for greater than 20 lb tare weights.
- (b) Place cylinder on scale.
- (c) Remove protective cap. The cap is not included in the tare weight. The tare does include acetone when acetylene cylinders are tested.
- (d) Weigh the cylinder and determine net weight. Compare actual net weight with labeled net weight or use the actual net weight to look up the correct volume declaration and compare that with the labeled volume.
- (e) The acetone in acetylene cylinders is included in the tare weight of the cylinder. Therefore, as acetylene is withdrawn from the cylinder, some acetone will also be withdrawn, changing the tare weight. Most producers will replace acetone in the cylinder before the cylinder is refilled, filling the cylinder with acetone to the stamped tare weight. Other producers, although not following recommended procedures, do not replace the acetone until it drops to a specified weight. In the latter situation, the refilling plant must note the actual tare weight of the cylinder and show it on the tag containing the net content statement or on the cylinder itself.
- (f) Refer to tables for acetylene gas if necessary (that is, if the acetylene is billed by the cubic foot). See (d) above.

2. Volumetric Testing

- (a) Thermometers or temperature sensors used for measuring temperatures during testing of cylinder gases shall be in contact with the outside surface of the cylinder approximately at the midpoint of the longitudinal axis.
- (b) The cylinders to be tested for quantity shall be taken from a lot that has had time to stabilize at the ambient temperature. Normally, the outside row of cylinders should not be selected for testing since they may be of a different temperature. The temperature used shall be an average taken from three cylinders selected at random. Cylinders that are exposed to heat or sunlight shall not be chosen for test unless an electronic heat sensor is used to measure the temperature of each cylinder. This is the preferred method of measuring the cylinder temperature because there can be differences in temperature from cylinder to cylinder, and the electronic sensors will stabilize within a few seconds. It is not practical to measure the temperature of each cylinder with a mercury-in-glass thermometer due to the time required for the thermometer to stabilize.

Laws and Regulations Committee

- (c) Measure the pressure of each cylinder in the sample selected.
- (d) Determine the temperature of the cylinders in the sample selected.
- (e) Determine the cylinder nominal capacity from cylinder data table.
- (f) Refer to NIST Tech Note 1079 and compute the actual net content.²

1. "Standard For Compressed Gas Cylinder Valve Outlet and Inlet Connections," Compressed Gas Association, 1235 Jefferson Davis Highway, Arlington, VA 22202.

2. "NBS Technical Note 1079," U.S. Department of Commerce, National Institute of Standards and Technology, Gaithersburg, MD 20899.

Report of the Specifications and Tolerances Committee

David Watson, Chairman
Consumer Products Supervisor
City of Fort Worth, Texas

300 Introduction

This is the Final Report of the Committee on Specifications and Tolerances for the 75th Annual Meeting of the National Conference on Weights and Measures. This report is based on the Interim Report offered in the Conference "Program and Committee Reports" (NCWM Publication 16), the Addendum Sheets issued at the Annual Meeting, and actions taken by the membership at the Voting Session of the Annual Meeting.

Table A identifies the items in the Report by Reference Key Number, Item Title, and Page Number. Table B reports the voting results. Voting items are indicated with a "V" after the item number. At the Annual Meeting, the committee grouped the less controversial voting items into a consent calendar. These are marked with "VC." Items marked with an "I" after the reference key number are information items. The items marked with a "W" were withdrawn by the Committee.

The attached Report contains many revisions and amendments to the National Institute of Standards and Technology (NIST) Handbook 44, 1991 Edition, "Specifications, Tolerances, and other Technical Requirements for Weighing and Measuring Devices." Revisions to the handbook are shown in **bold face print** by ~~crossing out~~ what is to be deleted, and underlining what is to be added. Requirements that are proposed to be nonretroactive are printed in *italics*. Entirely new paragraphs or sections proposed for addition to the handbook are designated as such and shown in **bold face print**.

Table A
Index to Reference Key Items

Reference Key No.		Title of Item	Page
General Code			
310-1	I	G-S.1. Identification; NTEP Certificate of Conformance	134
310-2	W	G-S.1. Identification; Year of Manufacture	136
310-3	W	G-S.8. Provision for Sealing Electronic Adjustable Components; Terminology	136
310-4	I	G-S.8. Provision for Sealing Electronic Adjustable Components; Scope	136
310-5	W	G-T.1. Acceptance Tolerances	137
310-6	I	G-UR.4.1. Maintenance of Equipment	137
310-7	VC	Review of Nonretroactive Requirements	138

Table A (Continued)

Reference Key No.	Title of Item	Page
Scales Code		
320-1	VC S.1.7. Capacity Indication, Weight Ranges, and Unit Weights; Initial Zero-Setting Mechanism	138
320-2	W S.2.3.2. Identification of Type of Tare	139
320-3	VC S.6. Marking Requirements; Table Format	139
320-4	VC S.6.11. Marking Requirements; Load Cells	145
320-5	VC N.3.1. Minimum Test-Weight Load for Railway Track Scales	145
320-6	V Proposed Test Procedures and Tolerances for Coupled-In-Motion Railway Track Scales	146
320-7	I Weighing Individual Railroad Cars for Custody Transfer; Liquids in Tank Cars	151
320-8	I Weighing Individual Railroad Cars for Custody Transfer; Mixed Manifest Trains	152
320-9	V T.1. Tolerances for Unmarked Scales; Reorganization	153
320-10	V T.1. Tolerances for Unmarked Scales; Revision	156
320-11	V T.N.1. Principles; Multiple-Weighing Devices Interfaced with a Single Indicator	157
320-12	V T.N.8.1.3. Temperature Effect on Zero-Load Balance	159
320-13	I UR.1.1. Selection Requirements; Suitability of Equipment	160
320-14	I UR.1.1. Selection Requirements; On-Board Weighing Systems	161
320-15	VC UR.3.1. Recommended Minimum Load; Weight Classifiers	162
320-16	I UR.3.1.1. Minimum Load, Grain Dockage Determination; Value of the Scale Division	162
320-17	I T.1. Tolerance Values; In-Motion Weighing, Monorail Scales	163
Belt-Conveyor Scale Systems		
321-1	VC N.3.3. Simulated Load Tests	163
Liquid-Measuring Devices		
330-1	I S.3. Discharge Lines and Valves	164
330-2	VC S.3.9. Antidrain Means	164
330-3	W UR.2.5. Product Storage Information	165
330-4	V UR.3. Use of Device; UR.3.3. (b) Computing Device	165
330-5	I Definitions of Retail and Wholesale	166
Liquefied Petroleum Gas and Anhydrous Ammonia Liquid-Measuring Devices		
332-1	VC S.1.4.2. Return to Zero	168
Hydrocarbon Gas Vapor-Measuring Devices		
333-1	VC N.4.2.2. Low-Flame Test	168
333-2	VC LPG Vapor Meters Installed Adjacent to Heaters Vaporizing LP Gas	169
Water Meters		
336-1	VC N.4.1. Normal Tests	169

Table A (Continued)

Reference Key No.	Title of Item	Page
Odometers Code		
353-1	VC S.1.6. Digital Indications and Representation	170
Taximeters		
354-1	VC S.1.3.2. Lighting of Indications	170
354-2	VC S.6. Short-Term Power Interruption, Electronic Taximeters	171
354-3	I T.1.2.2. On Average Time Interval Computed After Excluding the Initial Interval	172
354-4	VC S.2.1. Initial Time and Distance Interval; UR.3. Statement of Rate	173
Other Items		
360-1	I Draft Code for Mass Flow Meters	173
360-2	I Lubricating Oil Meters	174
360-3	I Draft Carbon Dioxide Liquid-Measuring Devices Code	174
360-4	I OIML Report	174

Order of Presentation

The Report was presented to the membership for voting as follows:

1. A single vote was taken on the consent calendar.
2. A separate vote was taken on each of the separate voting items listed in Table C.
3. A vote was taken on the entire Report with editorial privileges accorded to the Executive Secretary.

Table C
Voting Results

Reference Key No. or Subject	House of State Representatives		House of Delegates		Results
	Yes	No	Yes	No	
Consent Calendar	44	0	77	0	Passed
320-6	34	8	63	2	Passed
320-9	42	3	68	3	Passed
320-10	44	0	69	1	Passed
320-11	40	2	66	1	Passed
320-12	44	0	68	0	Passed
330-4 (Item 1)	17	27	42	34	Failed
330-4 (Item 2)	42	2	54	16	Passed
Entire Report	44	0	34	0	Passed

Details of All Items

310

General Code

310-1 I G-S.1. Identification; NTEP Certificate of Conformance

Discussion: A significant number of States require a device to have an NTEP Certificate of Conformance before it may be used in commercial applications, and generally want the certificate number indicated on the device to aid the enforcement official in determining whether or not a device has received a Certificate of Conformance. In earlier Conferences, weights and measures officials had proposed that noncommercial devices be marked "Not Legal For Trade" so that devices not designed to meet Handbook 44 requirements would not be used in commercial applications. These proposals had been opposed by industry and some weights and measures officials because the statement "Not Legal For Trade" has a negative connotation. Some officials questioned whether they had jurisdiction over noncommercial devices to require this marking. The Committee believes that marking the NTEP Certificate of Conformance number will serve as a positive indication that a device meets Handbook 44 requirements.

The Committee originally recommended that a mark of "NTEP Pending" be used on a device for which a type evaluation has been requested but not yet completed. This recommendation appeared to create more problems than it solved, so the proposed marking of "NTEP Pending" is withdrawn. Therefore, only the marking of the NTEP Certificate of Conformance number is recommended.

The proposal to include the marking of the Certificate number as part of the General Code paragraph G-S.1. was opposed by many Conference members as being too broad. Generally, it appears that weights and measures officials want the Certificate number marked on scales and liquid measuring devices, which represent the largest number of

devices falling under routine weights and measures enforcement. The Certificate of Conformance number is not believed to be necessary on equipment such as linear measures, berry baskets, and other categories of devices that have not posed significant enforcement problems. Consequently, the Committee recommends that the requirement to mark the Certificate of Conformance number be placed directly into the Scales Code and the Liquid-Measuring Devices Code (Handbook 44 Sections 2.20 and 3.30, respectively). These are the main areas in which there is a problem of determining whether or not a device has a Certificate of Conformance. The marking of other types of devices will be considered on a case by case (code by code) basis.

It is emphasized that the proposed requirement would not permit the installation of a device in those States that require an NTEP Certificate of Conformance until after the NTEP Certificate of Conformance number has been issued. Weights and measures officials are advised that NTEP does not perform type evaluations on all types of weighing or measuring equipment; consequently, not all devices will have Certificate of Conformance numbers. Manufacturers are encouraged to use one of the prefixes NTEP, NTEP No., or NTEP # to identify the NTEP Certificate of Conformance number if the requirement is adopted by the Conference.

In general, the industry is opposed to this marking requirement, stating that:

1. it will create an administrative problem for the industry in the production process;
2. the marking will have limited benefit;
3. the Certificate of Conformance marking by itself does not assure that a device meets all the requirements of Handbook 44 or that it is suitable for the application for which it has been installed; and
4. the delays in obtaining a type evaluation can interfere with the marketing of a device.

The marking of the NTEP certificate number will not eliminate the need for the inspector to determine that the device is the correct model listed on the Certificate of Conformance and that the HP LaserJet Series II (feed) HPLASEII.PR.Svalue, accuracy, and other characteristics are suitable for the application. Even if a device has a Certificate of Conformance, new production devices must comply with any new or amended requirements of Handbook 44 when the date of manufacture is after the effective date of the new requirement.

Although this proposal will place an additional marking requirement on the manufacturers of devices, the Committee believes that the marking of the NTEP Certificate of Conformance number will result in substantial benefits to device users and enforcement officials. The selling and placing into commercial service of devices that have not been designed to meet Handbook 44 requirements has been a long-standing and continuing problem. Marking with the NTEP number should aid potential purchasers to obtain devices that are suitable for commercial use.

The Committee has concluded that many aspects of this issue must be studied further before the NTEP Certificate of Conformance number can be required to be marked on devices. Issues that must be addressed include which devices, main elements, and components of both scales and liquid-measuring devices must be marked, what markings are required when the same hardware (computer model) is used in different applications with different software, the process of incorporating updated Certificate numbers into production, and if office computers used as part of loading rack meter systems must be marked with Certificate numbers. Consequently, the S&T Committee has changed this item from a voting item in 1990 to an information item with the intent to present the item for a vote in 1991. The Committee appreciates the strong support and desire among weights and measures officials for this marking requirement.

Committee Recommendation: To aid in further study and development of this issue, the Committee is making the following changes to this item.

The Committee recommends additions to the Scales Code and the Liquid-Measuring Devices Code to require that the NTEP (National Type Evaluation Program) Certificate of Conformance number be marked on devices and associated equipment after the number has been issued. The marking requirement also applies to all equipment, that is, to each part of a device that receives a separate Certificate of Conformance. Examples of equipment that, if evaluated separately, will be required to be marked with the NTEP Certificate number include scales, indicating elements, scales without indicating elements, load cells, retail motor fuel dispensers, loading rack meters, measuring elements evaluated separately, service station consoles, and any other device or equipment that is evaluated separately and falls under the requirements of these two Codes. A point-of-sale systems is not required to have the Certificate of Conformance number unless it serves as the primary indicating element for a scale or measuring device.

The Committee recommends that a marking requirement S.6.12. be added to the Scales Code to read:

*S.6.12. NTEP Certificate of Conformance Number. - The NTEP Certificate of Conformance number shall be marked on load cells with an NTEP Certificate of Conformance, scales in a single enclosure, separate indicating elements, and scales without indicating elements.
[Nonretroactive as of January 1, 199x]*

If this recommendation and the table format for marking requirements (Item 320-3) are adopted, this marking requirement will be included as part of the table of marking requirements.

The Committee recommends the addition of a similar requirement to the Liquid-Measuring Devices Code as paragraph S.4.5. to read:

*S.4.5. NTEP Certificate of Conformance Number. - The NTEP Certificate of Conformance number shall be marked on retail motor fuel dispensers, loading rack meters, measuring elements evaluated separately, and service station consoles.
[Nonretroactive as of January 1, 199x]*

310-2 W G-S.1. Identification; Year of Manufacture

(This item was withdrawn.)

Discussion: This item proposed marking the year of manufacture on devices to assist the weights and measures official in the proper application of nonretroactive requirements. It is often very difficult for the enforcement official to determine if a nonretroactive requirement applies to a specific device. The proposal also suggested establishing a task force to explore the possibility of encoding the year of manufacture and other required marking information to reduce the cost of marking this information on the device.

The Committee received comments in strong opposition to this proposal. Many manufacturers believe that the benefits of this marking requirement are minimal and do not justify the cost of complying with the requirement. Additionally, manufacturers anticipate marketing difficulties because customers may object to the installation of new equipment marked with a prior year of manufacture even if the product is of the latest design. The Committee also recognizes that the year of manufacture is only one of the criteria to determine if a nonretroactive requirement applies to the device. Consequently, the Committee has withdrawn this item.

Committee Recommendation: Withdrawn.

310-3 W G-S.8. Provision for Sealing Electronic Adjustable Components; Terminology

(This item was withdrawn.)

Discussion: The proposal suggested changing the term "metrological integrity" to "metrological characteristics" in an effort to state more clearly the scope of the sealing requirement. However, there was a lack of support for the proposal. Additionally, industry comments supported the understanding that metrological integrity includes more than just performance requirements, but does not extend to every programmable or selectable characteristic in a device. See Item 310-4 for further information on this subject.

Committee Recommendation: Withdrawn.

310-4 I G-S.8. Provision for Sealing Electronic Adjustable Components; Scope

Discussion: There is no uniform understanding and acceptance of the types of features and adjustments to be sealed as a result of the change to G-S.8. The Committee intended the scope of the provision for sealing to include more than just performance criteria. (When the 1989 changes to G-S.8. were adopted, the features listed as examples in the 1988 and 1989 Reports of the S&T Committee were to have provision for sealing.) There are still significant

differences among industry representatives, weights and measures officials, and the S&T Committee regarding the specific features that are required to have provision for sealing based upon the changes adopted in 1989. The S&T Committee requests the assistance of the three Sectors of the NTEP Technical Committee to establish guidelines for judging what must be sealed and to define the features and characteristics that shall have provision for sealing.

The device adjustment mechanisms, features, and characteristics under review can be divided into at least the following categories:

1. Provision for sealing required. Access to electronic adjustment mechanisms that affect the performance characteristics of a device has been required since G-S.8. was adopted in 1985.
2. Provision for sealing not required. Access to operator files, such as shift totals, unit prices, and price-look-up files is generally accepted as not requiring provision for sealing.
3. Provision for sealing not expected. The setting of device configuration parameters, such as programming the number of hoses on a retail motor fuel dispenser, the types of product dispensed, whether or not a card reader is provided, and whether or not the dispenser is programmed for multi-tier pricing is generally not expected to have provisions for sealing.

The main areas of disagreements on which features and characteristics should have provision for sealing are:

1. the selection of operating parameters that can affect device compliance with Handbook 44; and
2. the selection of device features that are operational during commercial use and which can affect the suitability of a device for use in a commercial application.

It is unrealistic to require every minor characteristic of a device to be sealed. Judgments will be required as to what must be sealed, based on the difficulty of changing a setting and the potential for fraudulent use of a selectable feature. Discussions should address whether or not provision for sealing should be required on the access to settings for which, once an operating parameter or feature is selected at the time of installation, there is no reason for that feature or parameter to change during the normal use of the device in that installation. Comments from weights and measures officials are encouraged regarding their understanding of the intent of the 1989 change and the features and device characteristics that should have provision for sealing.

Committee Recommendation: The Committee emphasizes that interpretation of Handbook 44 is the purview of the S&T Committee. The NTEP Technical Committee Sectors are requested to develop guidelines and lists of characteristics to be sealed and to submit their recommendations to the S&T Committee by November 1, 1990. The S&T Committee will review the recommendations and, if they agree with the interpretations, modify them as deemed necessary and present the results to the Conference for a vote. The industry is reminded that, when new features or device characteristics are incorporated in new devices, the NTEP laboratories will make the type evaluation decisions on an "ad hoc" basis to determine whether or not these new features must be sealed.

310-5 W G-T.1. Acceptance Tolerances

(This item was withdrawn.)

Discussion: This item proposed applying acceptance tolerances to a device whenever the security seal is broken. The Committee concluded that the broad coverage of the proposed change would create unreasonable accuracy requirements when a seal is broken due to service or maintenance for operations unrelated to performance (accuracy), e.g., ticket jammed in the printer of a meter. The proposal would require acceptance tolerances to apply whenever the security seal has been changed. The application of this requirement to a device utilizing an audit trail, as compared to a physical security seal being broken, would have to be studied. The possible ramifications of this proposal have not been sufficiently developed to evaluate the proposal.

Committee Recommendation: Withdrawn.

310-6 I G-UR.4.1. Maintenance of Equipment

Discussion: This item is based on a request to develop guidelines to assist in the uniform application of G-UR.4.1. and is not a proposal to change the language of Handbook 44. The Committee supports the concept of developing

guidelines for the enforcement of this requirement; however, this would take considerable time and study. Because of the great variety of situations that arise in the enforcement process and conditions influencing the decision in a specific instance, it may not be possible to develop universally applicable guidelines. Judgment on the part of the enforcement official will still be necessary.

Committee Recommendation: Continue to study this proposal.

310-7 VC Review of Nonretroactive Requirements

(This item was adopted as part of the consent calendar.)

Discussion: It is the Conference policy to review nonretroactive requirements periodically to determine if they should be made retroactive. Based upon the comments received, it appears that virtually all devices currently in commercial use comply with G-S.5.3.1. and G-S.5.6. Making these requirements retroactive should have very little impact on existing devices. The Committee reviewed the General Code paragraphs G-S.1. and G-S.6, and the Scales Code paragraphs S.2.1.3., S.2.3., and T.5., but decided to retain them as nonretroactive requirements. The comments on these latter paragraphs indicated that a considerable number of older devices are still in the field. If these paragraphs were made retroactive, extensive modification would often be required to bring the devices into compliance.

Committee Recommendation: The Committee recommends making the General Code paragraphs G-S.5.3.1. and G-S.5.6. retroactive.

320 Scales Code

320-1 VC S.1.7. Capacity Indication, Weight Ranges, and Unit Weights; Initial Zero-Setting Mechanism

(This item was adopted as part of the consent calendar.)

Discussion: An initial zero-setting mechanism allows a manufacturer to electronically and automatically compensate for the variation in the dead load of scale platforms instead of manually adjusting the weight of platforms or adjusting the electronics to satisfy S.1.7. These changes would be consistent with the OIML (International Organization of Legal Metrology) draft International Recommendation for Non-Automatic Weighing Instruments.

Permitting the use of an initial zero-setting mechanism will allow scales to zero up to 20 percent of the scale capacity when the unit is first connected to its power supply without the need for any additional testing during type evaluation. The scale would still be required to indicate up to 100 percent of its capacity and be accurate. No special testing would be required during type evaluation if the maximum amount of weight that can be zeroed when power is supplied does not exceed 20 percent.

A scale will be permitted to zero more than 20 percent when power is first supplied; however, additional testing must be performed during type evaluation to verify that the scale can satisfy the influence factors requirements when the maximum range of the initial zero-setting mechanism is utilized. If a scale is able to zero more than 20 percent of capacity, then the maximum amount of weight that can be zeroed must be zeroed during the type evaluation process and the complete set of type evaluation tests must be run to verify that the performance requirements are still satisfied.

The Committee believes this feature is appropriate on class I, II, and III scales. However, it does not seem appropriate or necessary to allow this feature on vehicle scales or other class III L scales.

Committee Recommendation: The Committee recommends permitting an initial zero-setting mechanism on class I, II, and III scales to automatically zero any dead load up to 20 percent of the scale capacity at the time the scale is switched on. A larger range is permitted if the scale is tested and found to be accurate. Any device that has an initial zero-setting mechanism must be accurate after it is placed into commercial service. The recommended changes to the Scales Code are listed below.

Add a definition to read:

initial zero-setting device. Automatic means provided to set the indication to zero at the time the instrument is switched on and before it is ready for use.

Amend S.1.7. to read:

S.1.7. Capacity Indication, Weight Ranges, and Unit Weights. - An indicating or recording element shall not display nor record any values when the gross platform load (not counting initial dead load that has been cancelled by an initial zero-setting device) is in excess of 105 percent of the capacity of the system. The total value of weight ranges and of unit weights in effect or in place at any time shall automatically be accounted for on the reading face and on any recorded representation.

This requirement does not apply to: (1) single-revolution dial scales, (2) multi-revolution dial scales not equipped with unit weights, (3) scales equipped with two or more weighbeams, and (4) devices that indicate mathematically-derived totaled values.

Add a new paragraph S.2.1.5. to read:

S.2.1.5. Initial Zero-Setting Mechanism. -

- (a) Scales of accuracy classes I, II, and III may be equipped with an initial zero-setting device.
- (b) An initial zero-setting mechanism shall not zero a load in excess of 20 percent of the maximum capacity of the scale unless tests show that the scale meets all applicable tolerances for any amount of initial load compensated by this device within the specified range.

320-2 W S.2.3.2. Identification of Type of Tare

(This item was withdrawn.)

Discussion: This item proposed establishing a nonretroactive requirement to identify the type of tare (e.g., keyboard, push-button, or programmed tare) to be identified on the display of a scale, and with the printed tare value when more than one type of tare capability exists in a system. Although this additional definition of values is considered beneficial to tracing the actions of a transaction and may aid in determining if the appropriate type of tare has been taken, it does not guarantee the accuracy of the tare that was taken. Moreover, the abbreviations for the type of tare entry probably would not be meaningful to consumers. Consequently, this item is withdrawn.

Committee Recommendation: Withdrawn.

320-3 VC S.6. Marking Requirements; Table Format

(This item was adopted as part of the consent calendar.)

Discussion: At least 14 paragraphs in the General and Scales Codes require the manufacturer to mark specific information on a scale, a main element, or a component of a scale or weighing system. Both the manufacturer and enforcement official have difficulty in identifying the required markings applicable to a specific device or a specific part of a weighing system. The Scale Manufacturers Association (SMA) evaluated the many marking requirements and suggested that a table format, supplemented by additional notes as necessary to specify the applicability of specific requirements, would be a better reference source for the marking requirements. The Committee agrees with the SMA suggestion. The proposed table consolidates all of the marking requirements of the General Code and the Scales Code. The text of the General Code marking requirements would still be retained since they continue to apply to all of the other codes in Handbook 44. The marking requirements from the General Code must be satisfied as they are written there. The proposed summary information in the tables is simply an aid to locating the applicable requirements.

Some changes were made when consolidating the text into abbreviated statements; however, they are considered minor and should not present problems in either device design or weights and measures enforcement. These are listed below to alert all interested parties to the effect of these changes.

1. The marking of the "scale without indicating element" with the serial number along with an identifying symbol is new. A serial number is not currently required on weighing elements because S.6.8. supersedes G-S.1. and does not specifically require a serial number. However, it is believed that most, if not all, weighing elements not permanently attached to indicating elements are already given a serial number. Moreover, the addition of this requirement has been supported by the Scale Manufacturers Association.
2. A scale normally consists of a digital indicating element, a weighing element, and a load-receiving element. The term "scale without indicating element" refers to the weighing element with the load-receiving element. The "scale without indicating element" is the portion of the scale that is "not permanently attached to an indicating element" as referenced in S.6.8.
3. The marking of the nominal capacity is summarized as applying to any device where the capacity is not immediately apparent. This one statement is to apply to those devices specifically identified in S.6.2.1.
4. A weight classifier has been added as an example for special marking restricting its application in order to draw attention to its special design. The special design of weight classifiers makes them inappropriate for many applications where scales are required to round to the nearest scale division. See note 13 in Tables 4a and 4b.
5. The interpretation of G-S.1. as it has been applied in the National Type Evaluation Program has been incorporated into notes 10 and 16 in Table 4b.
6. The marking requirements for load cells as proposed for amendment in Item 320-4 are included in the table and note 11. If Item 320-4 is not adopted, note 11 will be changed accordingly.

In an effort to standardize the symbols used in marking devices, main elements, and components for the maximum number of scale divisions and the minimum verification value, the use of the following symbols is recommended (but is not required, except where already specified in Handbook 44):

- n represents the number of scale divisions in a weighing system or in a weighing range for a multi-ranging scale (variable division-value scale).
- n_{\max} represents the maximum number of scale divisions for which a main element or load cell complies with the applicable requirements of Handbook 44. Scales and other weighing systems may be installed to have fewer scale divisions (n) than n_{\max} . The maximum number of scale divisions permitted for an installation is limited to the lowest n_{\max} marked on the scale, indicating element, weighing element, or load cell.
- e declares the verification scale division on a scale when e is different from the displayed scale division, d .
- e_{\min} states the smallest scale division for which a weighing element complies with the influence factors requirements of Handbook 44 (S.6.8.(f)).
- v_{\min} marks the verification interval on load cells.

To assist in the review of the consolidation of the marking requirements into Table 4a and to aid in tracing the history of the marking requirements, a table titled "Code References for Proposed Table 4a" is included in this discussion to show the Handbook 44 references.

Table 4a
S.6. Marking Requirements

To Be Marked With	Weighing Equipment	Scale Single Enclosure	Scale Without Indicating Element	Indicating Element Separate	Load Receiving Element (9)	Other Equipment or Device (10)	Load Cell W/COC (11)
Manufacturer's ID	(1)	G-S.1.	G-S.1.	G-S.1.	x	G-S.1.	x
Model Designation	(1)	G-S.1.	x	G-S.1.	x	G-S.1.	x
Serial Number and Prefix	(2)	G-S.1.	x	G-S.1.	x	G-S.1. (16)	x
Accuracy Class		x	x	x (8)	x		x
Nominal Capacity	(3)	x	x	x	x		
Value of Scale Division	(3)	x		x			
Value of "e"	(4)	x		x			
Temperature Limits	(5)	x	x	x			x
Concentrated Load Capacity	(12)			x	x		
Special Application	(13)	x	x	x			
Maximum Number of Scale Divisions	(6)		x	x			x
Minimum Verification Scale Division			x		x		
"S" or "M"	(7)						x
Direction of Loading	(15)						x
Minimum Dead Load							x
Maximum Capacity							x
Safe Load Limit							x
Load Cell Verification Interval (v_{min})							x
Section Capacity	(14)			x	x		

For applicable notes, see Table 4b.

Committee Recommendation: The Committee recommends that the following paragraphs be deleted: S.6.1., S.6.2.1., S.6.3., S.6.4., S.6.5., S.6.6., S.6.7., S.6.7.1., S.6.7.2., S.6.8., S.6.10., and S.6.11.

The Committee recommends that paragraphs S.6.2.2. and S.6.9. be renumbered as S.6.1. and S.6.2., respectively, and that the marking requirements of the deleted paragraphs be consolidated into a table, supplemented by notes, providing the specific information needed to apply the marking requirements to scales. The General Code paragraph references and the "x" markings in the table indicate which requirements are applicable to the various weighing equipment; the subsequent tables in the Scales Code will be renumbered.

The Committee recommends that the S.6. section of Handbook 44 be amended to read:

S.6. Marking Requirements [See also G-S.1., G-S.4., G-S.6., G-S.7., G-UR2.1.1., and UR3.4.1.]

~~S.6.2.2.~~ **S.6.1. Nominal Capacity; Vehicle, Axle-Load, and Livestock Scales. -**

For all vehicle, axle-load, and livestock scales, the marked nominal capacity shall not exceed the concentrated load capacity times the quantity of the number of sections in the scale minus 0.5. As a formula, this is stated as

$$\text{nominal capacity} \leq \text{concentrated load capacity} \times (N - 0.5)$$

where N = the number of sections in the scale.

(See N.1.3.4., T.1.3., and T.N.3.1.)

[Nonretroactive as of January 1, 1989.]

(Added 1988)

S.6.9: S.6.2. Location Of Marking Information. - Scales that are not permanently attached to an indicating element and for which the load-receiving element is the only part of the weighing/load-receiving element visible after installation, may have the marking information required in G-S.1. of the General Code and S.6. of the Scales Code located in an area that is accessible only through the use of a tool, provided that the information is easily accessible (e.g., the information may appear on the junction box under an access plate). The identification information for these scales shall be located on the weighbridge (load-receiving element) near the point where the signal leaves the weighing element or beneath the nearest access cover.

(Added 1989)

S.6.3. Scales, Main Elements, and Components of Scales or Weighing Systems - Scales, main elements of scales when not contained in a single enclosure for the entire scale, load cells for which Certificates of Conformance (COC) have been issued under the National Type Evaluation Program, and other equipment necessary to a weighing system, but having no metrological effect on the weighing system, shall be marked as specified in Table 4a and explained in the accompanying notes (Table 4b).

Code References For Proposed Table 4a

Marking Requirements

To Be Marked With \ Weighing Equipment	Scale Single Enclosure	Scale Without Indicating Element	Indicating Element Separate	Load Receiving Element (9)	Other Equipment or Device (10)	Load Cell W/COC (11)
Manufacturer's ID (1)	G-S.1.	G-S.1.	G-S.1.	S.6.9.	G-S.1.	S.6.11.
Model Designation (1)	G-S.1.	S.6.8.	G-S.1.	S.6.9.	G-S.1.	S.6.11.
Serial Number and Prefix (2)	G-S.1.	new	G-S.1.	S.6.9.	G-S.1 NTEP	S.6.11.
Accuracy Class	S.6.1.	S.6.8.	S.6.10	S.6.9.		S.6.11.
Nominal Capacity (3)	S.6.2.1.	S.6.8.	S.6.2.1.	S.6.9. S.6.2.1.		
Value of Scale Division (3)	S.6.3.		S.6.3.			
Value of "e" (4)	S.6.4.		S.6.4.			
Temperature Limits (5)	S.6.5.	S.6.5.	S.6.5.			S.6.11.
Concentrated Load Capacity (12)			S.6.7.2.	S.6.7.2.		
Special Application (13)	S.6.6.	S.6.6.	S.6.6.			
Maximum Number of Scale Divisions (6)		S.6.8.	S.6.10.			S.6.11.
Minimum Verification Scale Division		S.6.8.		S.6.8. S.6.9.		
"S" or "M" (7)						S.6.11.
Direction of Loading (15)						S.6.11.
Minimum Dead Load						S.6.11.
Maximum Capacity						S.6.11.
Safe Load Limit						S.6.11.
Load Cell Verification Interval (v_{min})						S.6.11.
Section Capacity (14)			S.6.7.1. S.6.7.2.	S.6.7.1. S.6.7.2.		

Table 4b

Notes For Table 4a

1. Manufacturer's identification and model designation (See G-S.1.)
2. *Serial number [Nonretroactive as of January 1, 1968] and prefix [Nonretroactive as of January 1, 1986]. (See G-S.1.)*
3. *The nominal capacity and value of the scale division shall be shown together (e.g., 100,000 x 10 lb or 30 x 0.01 lb) adjacent to the weight display when the nominal capacity and value of the scale division are not immediately apparent. Each scale division value or weight unit shall be marked on variable-division value or division-unit scales. [Nonretroactive as of January 1, 1983]*
4. *Required only if different from "d." [Nonretroactive as of January 1, 1986]*
5. *Required only on class III, III L, and IIII scales if other than 14 °F to 104 °F. [Nonretroactive as of January 1, 1986]*
6. *This value may be stated on load cells in units of 1,000; e.g., n: 10 is 10,000 divisions. [Nonretroactive as of January 1, 1988]*
7. *Denotes compliance for single or multiple load cell applications. [Nonretroactive as of January 1, 1988]*
8. *Can have dual compliance and marking; i.e., III/III L mark with the maximum number of scale divisions for each class. [Nonretroactive as of January 1, 1988]*
9. *For vehicle, axle load, and livestock scales only. Markings must be added to any scale not previously marked, at the time of modification. [Nonretroactive as of January 1, 1989]*
10. *Necessary to the weighing system but having no metrological effect, e.g., auxiliary remote display, keyboard, etc.*
11. *The markings may be either on the load cell or in an accompanying document; except that, if an accompanying document is provided, the serial number shall appear both on the load cell and in the document. [Nonretroactive as of January 1, 1988] The manufacturer's name or trademark, the model designation, and identifying symbol for the serial number shall also be marked both on the load cell and in any accompanying document. [Nonretroactive as of January 1, 1991]*
12. *Required on the indicating element and the load-receiving element of vehicle, axle load, and livestock scales; may be abbreviated CLC. [Nonretroactive as of January 1, 1989]*
13. *A scale designed for a special application rather than general use shall be conspicuously marked with suitable words visible to the operator and customer restricting its use to that application, e.g., postal scale, prepack scale, weight classifier, etc. [Nonretroactive as of January 1, 1986]*
14. *Required on the indicating element of railway track scales only. When marked on vehicle, axle load, and livestock scales manufactured before January 1, 1989, it may be used as the CLC.*
15. *Required if the direction of loading the load cell is not obvious. [Nonretroactive as of January 1, 1988]*
16. *Serial number [Nonretroactive as of January 1, 1968] and prefix [Nonretroactive as of January 1, 1986]. (See G-S.1.) Modules without "intelligence" on a modular system (e.g., printer, keyboard module, cash drawer, and secondary display in a point-of-sale system) are not required to have serial numbers.*

320-4 VC S.6.11. Marking Requirements; Load Cells

(This item was adopted as part of the consent calendar.)

Discussion: S.6.11. could be interpreted to mean that the information specified therein need only be provided in an accompanying document, and that the load cell need not be marked with a serial number or any other required information. The Committee believes that the manufacturer's name or trademark, model designation, and serial number are the minimum information that must be marked on a load cell that has received an NTEP Certificate of Conformance. The document accompanying the load cell is often misplaced and not available at the time of inspection to weights and measures officials or to a service technician. This information must be available to both parties to permit verification that the load cells are appropriate for the application and to trace the load cell back to the manufacturer. The service technician also needs the information if repairs require replacing the load cell with a metrologically equivalent or better load cell.

This marking requirement applies only to load cells for which Certificates of Conformance have been issued. If Items 320-3 and 320-4 are adopted, the text proposed in this recommendation will not appear in the Scales Code; instead, the marking requirements will be incorporated into Table 4a and the notes of Table 4b.

Committee Recommendation: The Committee recommends that load cells be physically marked with the manufacturer's name or trademark, the model designation, and the serial number prefaced by an appropriate abbreviation or symbol. The following changes are recommended.

Amend S.6.11.(f) and the last paragraph to read:

- (f) the name and address of the manufacturer or the manufacturer's trademark, model designation, *serial number*, minimum dead load, maximum capacity, safe load limit, and load cell verification interval (v_{min}).

Amend and editorially revise the last paragraph of S.6.11. to read:

The required information may be given on a data plate attached to the load cell or, alternatively, in an accompanying document. If the document is the source of the information, the serial number of the load cell shall be marked on the load cell and also given in the document.

The name of the manufacturer or the manufacturer's trademark, the model designation, and a nonrepetitive serial number of the load cell shall be marked on the load cell and given in an accompanying document, if the latter is provided.* The serial number shall be prefaced by words, an abbreviation, or a symbol that clearly identifies the number as the required serial number. The other required information may be marked on the load cell or be included in an accompanying document containing all of the required information.
[Nonretroactive as of January 1, 1988]

*[The markings required on load cells are nonretroactive as of January 1, 1991, except that the serial number marking is nonretroactive as of January 1, 1988.]

320-5 VC N.3.1. Minimum Test-Weight Load for Railway Track Scales

(This item was adopted as part of the consent calendar.)

Discussion: Due to the large capacity of railway track scales and the potential for errors, and to promote an adequate test of railway track scales, a larger known test load is required whenever a railway track scale is to be certified. Current testing practices are often inadequate to ensure accuracy of coupled-in-motion (CIM) weighing over extended periods of time. The Association of American Railroads Scale Handbook requires a minimum test-weight load of 80,000 lb. The Committee agrees that a known test-weight load larger than the 30,000 lb currently specified in N.3.1. is needed to perform an adequate test on a railway track scale. The availability of a minimum known test-weight load of 80,000 lb could be a problem for a weights and measures jurisdiction to conduct enforcement tests on railway track

scales and for service companies to place a scale back into service after emergency repairs. Consequently, provision is made to test these scales using less than 80,000 lb of known test load if the scale is found to be inaccurate or if the scale is returned to service on an interim basis until a more thorough test can be performed.

A special meeting of the S&T Committee was held October 12, 1989, to discuss the railroad issues on the agenda. Based on the comments made at the October 12 meeting and letters received, the current S&T Committee position is summarized below:

1. The initial test of a railway track scale shall be conducted with a minimum test load of 80,000 lb. A strain-load test to the used capacity of the scale is recommended. These criteria apply to tests used to certify a railway track scale.
2. A minimum test load of 30,000 lb may be used to return a scale into service on an interim basis. A strain-load test to 25% of the scale capacity is mandatory (whenever the scale design permits a strain-load test to be performed) if the test load is less than 80,000 lb. The strain-load test to the used capacity of the scale is recommended if the known test load is at least 80,000 lb.
3. The length of time that a scale may be used based on the interim test is left to the discretion of the official with statutory authority.
4. A scale may be tested using a minimum test load of 30,000 lb and rejected if found to be out of tolerance.

Committee Recommendation: The Committee recommends that N.3.1. be amended to (1) require that a minimum known test load of 80,000 lb be used to approve a railway track scale; (2) require conduct of a strain-load test to the used capacity of the railway track scale under specified conditions; (3) recognize the use of a lower known test load in combination with a strain-load test to the used capacity of the scale to perform a weights and measures enforcement test or to return a scale to service on an interim basis after a repair; and (4) state that a minimum test load of 30,000 lb is required to take enforcement action on a scale that is found to be inaccurate.

The Committee recommends that N.3.1. be replaced with:

N.3.1. Minimum Test-Weight Load and Recommended Strain-Load Test for Railway Track Scales.

N.3.1.1. Approval. - The test-weight load shall be not less than 80,000 lb. A strain-load test conducted up to the used capacity of the weighing system is recommended.

N.3.1.2. Interim Approval. - A test-weight load of not less than 30,000 lb and a strain-load test up to at least 25 percent of scale capacity may be used to return a scale into service following repairs.

Note: The length of time the scale may be used following an interim test is at the discretion of the official with statutory authority.

N.3.1.3. Enforcement Action for Inaccuracy. - To take enforcement action on a scale that is found to be inaccurate, a minimum test load of 30,000 lb must be used.

**320-6 V Proposed Test Procedures and Tolerances for Coupled-In-Motion
Railway Track Scales**

(This item was adopted.)

Discussion: The discussion and recommendation contained in this item do not address, nor do they finalize, the required test procedure for CIM scales used to weigh individual tank cars containing liquids or mixed merchandise trains (referred to in previous years as mixed manifest trains) when the individual weights are used for custody transfer of the individual cars. These issues of CIM weighing of liquids in tank cars and mixed merchandise trains are addressed in Items 320-7 and 320-8. The current position of the S&T Committee is reported for further consideration in the first point "C" that follows, as well as in Items 320-7 and 320-8. This item (320-6) proposes the minimum test procedure that may be used on CIM scales and describes the "as used" test procedures for CIM scales.

The S&T Committee has addressed the procedures for testing coupled-in-motion railway track scales over the last several years. The Committee believes that the 10-car minimum test specified in NIST Handbook 44 has resulted in installations where the scales do not generate accurate weights in normal use. The Committee believes that the most accurate method of testing coupled-in-motion scales are to test them "as used" with train lengths reflecting those normally weighed. However, the Committee realizes that the cost of testing CIM scales "as used" is usually much higher than the minimum 10-car test. The Committee has also received many letters and comments from owners and users of CIM scales stating that they have not had any problems with the accuracy of weights obtained from scales that have been tested using the 10-car train.

The proposed changes specify a minimum 10-car/5-times test but provides the option, at the discretion of the official with statutory authority, to test a scale with "as used" procedures if there is reason to believe that it is necessary to determine the accuracy of the weighing system under "as used" conditions. These procedures will apply to both the existing CIM scales and to new installations. The "as used" test procedures, if adopted, will be described in the Note section of the Scales Code. The proposed changes do not "grandfather" existing scales that have been tested up until the time of this proposal using the 10-car test. The decision of whether a scale must be tested using the minimum test or the "as used" test procedures is left to the discretion of the official with statutory authority. New N.4.2. language will allow the official with statutory authority to test existing scales as used; however, it will also open the door to testing new scales using shorter trains. The Committee believes that it is important to indicate in Handbook 44 the test the Committee believes will provide the best determination of the accuracy of the scale, that is, the "as used" test procedures, while considering the costs of the tests.

The following explanation is provided in an effort to state clearly how these changes apply to CIM scales used to weigh unit trains as defined in Handbook 44.

- A. Where CIM scales are used for the assessment of freight charges only, the 10 car/5 times minimum test applies; however, the "as used" test procedures may be required at the discretion of the official with statutory authority.
- B. Where CIM scales are used for the custody transfer of unit trains only, the 10 car/5 times minimum test applies; however, the "as used" test procedure may be required at the discretion of the official with statutory authority.
- C. It is the position of the S&T Committee that the "as used" test procedures shall be followed where CIM scales are used to determine individual car weights for custody transfer of liquids and mixed merchandise trains. Note that shorter trains may be used if test results are shown to agree with the results for longer trains.

The tolerance paragraphs for CIM weighing are revised slightly in an effort to clarify the application of the tolerances. Additional explanations to clarify the application of the tolerances to scales used to weigh trains used for different purposes are given below.

- A. T.N.3.6.3. requires that the sum of the weights for a unit train (a group of contiguous cars carrying a single commodity from one consignor to one consignee, with the same commodity on the same type of car) must be within the sum of the maintenance static tolerances applicable to the weights in the group. The individual car tolerance distribution does not apply when only unit train weights are used for custody transfer. A train may consist of more than one unit train.
- B. Both T.N.3.6.1. and T.N.3.6.2. apply to unit trains consisting of the same commodity on the same type of car when the individual car weights are to be used for the assessment of freight charges and for custody transfer. The S&T Committee has not finalized its position regarding the appropriateness of CIM weighing of mixed merchandise (mixed manifest) trains or the tolerances to be applied to them. The CIM weighing of mixed merchandise trains and liquids in tank cars for the custody transfer of individual cars will be addressed again in 1991.
- C. T.N.3.6.1. also requires that the sum of car weights for each run of a test train be within the sum of the maintenance static tolerances applicable to the weights in the group.

The Committee is still considering the extent of agreement required between test results from a long train test and a shorter train test for "as used" test procedures: 0.15 percent may be too large a deviation (see proposed N.4.2.1.1.). If the test results of a long and a short train have shown reasonable agreement and a shorter train is used to test a CIM scale, should the results for the short train be adjusted in subsequent tests to have an offset from zero error so that the errors presumed to exist for the long train will be zero? Comments are requested on this particular point.

Specifications and Tolerances Committee

The Committee is also considering proposing a requirement that the weights from CIM scales used for the custody transfer of individual cars shall identify that the car(s) were weighed on a CIM scale. A requirement for identifying the specific scale is also being considered. Comments are requested on this point, but a recommendation for this requirement is not planned for the 1990 National Conference.

The changes recommended in this item are intended to remove some of the uncertainty surrounding the use of CIM scales, but are not intended to end the discussion of these issues. The issues will continue to be studied and, if warranted, further action may be proposed.

The S&T Committee has requested and continues to request that the industry notify the Committee when tests to collect data on this issue for S&T consideration are scheduled for CIM scales. So far the Committee has been notified only twice, limiting the opportunity to work with the industry. Whenever possible, the Committee members would like to observe the test process when collecting data to be submitted to the Committee in order to gain a better understanding of the many considerations and difficulties involved. The Committee encourages weights and measures officials to work with the industry whenever a CIM scale is tested in their jurisdiction to better understand CIM weighing and the testing of CIM scales.

Committee Recommendation: In an effort to reach a consensus on the issue, but still address the comments and concerns that have been raised, the Committee recommends that the following changes be made to the Scales Code. The crossing out and underlining of text is not included in this item because of the extensive changes. The proposals should be studied in their entirety. Paragraph T.N.3.7. is included for reference although the content is not changed from the current language in Handbook 44.

It is the perception of many in the railway industry that a separate paragraph addressing scales installed prior to January 1, 1991, improves the negotiating position of the railroads to interact with weights and measures officials who want to test existing scales with the "as used" test procedures. They believe the revised language places a responsibility on the weights and measures official to provide justification in the form of possible problems concerning installation or operating conditions, or complaints concerning the accuracy of weights in order to change the test procedure for existing scales from the 10-car/5-times test that the S&T Committee is proposing as the minimum test that is acceptable. The S&T Committee requests the assistance of the railroad industry, owners of coupled-in-motion scales, scale manufacturers, shippers, utilities, and industry associations to develop guidelines to aid weights and measures officials in determining when the as used test procedures should be used.

It is emphasized that the test procedure specified in the proposed N.4.2. is the minimum test procedure and minimum length of test train allowed to be used to test scales installed before January 1, 1991; N.4.2. should not be construed as being sufficient to conduct an adequate test for all installations. The minimum test does not only address the number of times a test train is passed over a scale or the minimum number of cars used to test a scale, it also addresses the minimum length of train that may be used to test the scale.

**PROPOSED TEST PROCEDURES & TOLERANCES
FOR COUPLED-IN-MOTION RAILWAY TRACK SCALES**

Add the following definitions:

Test car. A railroad car weighed on a reference scale for use in a test train.[Added editorially.]

Test train. A train consisting of cars weighed on a reference scale and used to test coupled-in-motion railway track scales. The test cars may be placed consecutively or distributed in different places within a train.

Consecutive-car test train. A train consisting of cars weighed on a reference scale, then coupled consecutively and run over the coupled-in-motion railway track scale under test.

Distributed-car test train. A train consisting of cars weighed first on a reference scale, cars coupled consecutively in groups at different locations within the train, then run over the coupled-in-motion railway track scale under test. The groups are typically placed at the front, middle, and rear of the train.

Delete the existing N.3.1.1. and renumber the existing N.4. as N.5.

Add the following paragraphs:

N.4. COUPLED-IN-MOTION RAILWAY TRACK SCALES

N.4.1. SCALES USED TO WEIGH TRAINS OF LESS THAN 10 CARS.- These scales shall be tested using a consecutive-car test train consisting of the number of cars weighed in the normal operation run over the scale a minimum of five times in each mode of operation following the final calibration.

N.4.2. Scales Placed In Service Prior To January 1, 1991, And Used To Weigh Trains of 10 Or More Cars.- The minimum test train shall be a consecutive-car test train of no less than 10 cars run over the scale a minimum of five times in each mode of operation following final calibration.

N.4.3. Scales Placed In Service On Or After January 1, 1991, And Used To Weigh Trains of 10 Or More Cars.-

- (a) These scales shall be tested using a consecutive-car test train of no less than 10 cars run over the scale a minimum of five times in each mode of operation following final calibration; or
- (b) if the official with statutory authority determines it necessary, the AS USED TEST PROCEDURES outlined in N.4.3.1. shall be used.

N.4.3.1. AS USED TEST PROCEDURES - A scale shall be tested in a manner that represents the normal method of operation and length(s) of trains normally weighed. The scales may be tested using either:

- (1) a consecutive-car test train of a length typical of train(s) normally weighed;
or
- (2) a distributed-car test train of a length typical of train(s) normally weighed.

However, a consecutive-car test train of a shorter length may be used provided that initial verification test results for the shorter consecutive-car test train agree with the test results for the distributed-car or full-length consecutive-car test train as specified in N.4.3.1.1.

The official with statutory authority shall be responsible for determining the minimum test train length to be used on subsequent tests.

N.4.3.1.1. INITIAL VERIFICATION.- Initial verification tests should be performed on any new scale and whenever either the track structure or the operating procedure changes. If a consecutive-car test train of length shorter than trains normally weighed is to be used for subsequent verification, the shorter consecutive-car test train results shall be compared to either a distributed-car or consecutive-car test train of length(s) typical of train(s) normally weighed.

The difference between the total train weight of the train(s) representing the normal method of operation and the shorter consecutive-car test train shall not exceed 0.15 percent. If the difference in test results exceeds 0.15 percent, the length of the shorter consecutive-car test train shall be increased until agreement within 0.15 percent is achieved.

N.4.3.1.2. SUBSEQUENT VERIFICATION.- The test train may consist of either a consecutive-car test train with a length not less than that used in initial verification, or a distributed-car test train representing the number of cars used in the normal operation.

N.4.3.1.3. DISTRIBUTED CAR TEST TRAINS.-

- (a) The length of the train shall be typical of trains that are normally weighed.
- (b) The test cars shall be split into three groups, each group consisting of 10 cars or 10 percent of the train length, whichever is less.
- (c) The test groups shall be placed near the front, around the middle, and near the end of the train.
- (d) Following the final adjustment, the distributed-car test train shall be run over the scale at least three times or shall produce 50 weight values, whichever is greater.
- (e) The scale shall be tested in each mode of operation.

N.4.3.1.4. CONSECUTIVE-CAR TEST TRAINS.-

- (a) A consecutive-car test train shall consist of at least 10 cars.
- (b) If the consecutive-car test train consists of between 10 and 20 cars, inclusive, it shall be run over the scale a minimum of five times in each mode of operation following the final calibration.
- (c) If the consecutive-car test train consists of more than 20 cars, it shall be run over the scale a minimum of three times in each mode of operation.

The proposed section T.N.3.6. is revised to provide the tolerances for coupled-in-motion weighing as stated below. T.N.3.6.4. is not changed from its current language, but is renumbered as T.N.3.7. so that it does not fall under the T.N.3.6. heading for coupled-in-motion weighing. The current T.N.3.7. and T.N.3.8. would be renumbered as T.N.3.8. and T.N.3.9., respectively.

T.N.3.6. COUPLED-IN-MOTION WEIGHING, RAILWAY TRACK SCALES. - Tolerances for the group of weight values appropriate to the application must satisfy the following conditions:

T.N.3.6.1. - For any group of weight values, the difference in the sum of the individual in-motion car weights of the group as compared to the sum of the individual static weights shall not exceed two tenths of one percent (0.2%).

T.N.3.6.2. - If a scale is used to weigh trains of five or more cars, and if the individual car weights are used, any single weight value within the group must meet the following criteria:

- (a) no single error may exceed three times the static maintenance tolerance;
- (b) not more than 5 percent of the errors may exceed two times the static maintenance tolerance; and
- (c) not more than 35 percent of the errors may exceed the static maintenance tolerance.

T.N.3.6.3. - For any group of weight values wherein the sole purpose is to determine the sum of the group, T.N.3.6.1. alone applies.

T.N.3.6.4. - For a scale used to weigh trains of less than five cars, no single car weight within the group may exceed the static maintenance tolerance.

T.N.3.7. UNCOUPLED-IN-MOTION WEIGHING, RAILWAY TRACK SCALES. - For any single weighment within a group of non-interactive (i.e., uncoupled) loads, the weighment error shall not exceed the static maintenance tolerance.

A new User Requirement UR.5. will be added to impress upon the scale owner/user that a scale is to be tested in the manner in which it is normally used and that the proper test procedures must be followed for coupled-in-motion scales.

UR.5. RAILWAY TRACK SCALES WEIGHING COUPLED-IN-MOTION.- A coupled-in-motion scale placed in service on or after January 1, 1991, should be tested in the manner in which it is operated, with the locomotive either pushing or pulling the cars at the designed speed and in the proper direction. The cars used in the test train should represent the range of gross weights that will be used during the normal operation of the scale. Except as provided in N.4.2. and N.4.3.(a), normal operating procedures should be simulated as nearly as practical. Approach conditions for a train length in each direction of the scale site are more critical for a scale used for individual car weights than for a unit-train-weights-only facility, and should be considered prior to the installation of the coupled-in-motion weighing system.

320-7 I Weighing Individual Railroad Cars for Custody Transfer; Liquids in Tank Cars

Discussion: The CIM weighing of liquids in tank cars introduces another set of variables into the process of weighing the cars. The liquid may be moving inside the tank; some tank cars may have internal baffles to reduce the effect of moving liquid; the cars may not be completely filled; the liquids in different cars may be of significantly different densities; and the car couplers are often safety couplers to reduce danger in the event of a railroad accident.

The Committee has received data from a company that weighs several different liquids in tank cars. This company now has a program of testing the scale "as used," continually monitors the performance of the scale by weighing a monitor car in many of its trains, maintains a control chart on the performance of the scale, and conducts comparison testing of CIM weights by weighing the same train twice. This type of process control information is believed to be very effective to determine the accuracy of a scale. The data provided by the user of the scale demonstrates that, with the proper testing of the scale and continually monitoring its performance, liquids in tanks cars can be weighed accurately over a CIM scale. The statistical process control together with the "as used" test procedures used by this company exceeds the controls contained in the recommended test procedures for CIM scales in Item 320-6. It is the view of the S&T Committee that, as a minimum, CIM scales used to weigh liquids in tank cars for custody transfer (as distinguished from weighing for the purposes of freight charges) should be required to be tested with the "as used" test procedures.

The Railroad Advisory Committee has recommended adding the following two user requirements to address the weighing of liquids in tank cars.

UR.3.8. IN-MOTION WEIGHING OF TANK CARS ON RAILWAY TRACK SCALES.- Weighing tank cars (liquids) on a multi-draft in-motion railway track scale when the lading is of an unstable nature is acceptable provided that tests between a static scale and the in-motion scale are comparable. The test must employ the same types of loaded tank cars and commodities that are intended to be weighed in the normal operation.

UR.3.9. MANUALLY CONTROLLED STATIC WEIGHING DEVICES ON RAILWAY TRACK SCALES.- The indication of a manually controlled static weighing device must be stable within plus or minus three graduations before the weight is recorded.

The Committee is also considering proposing a requirement that the weights from CIM scales used for the custody transfer of individual cars shall identify that the car(s) were weighed on a CIM scale. Identifying the specific scale is also being considered. Comments are requested on this point, but a recommendation for this requirement is not planned for the 1990 National Conference.

The S&T Committee has requested and continues to request that the industry notify it when tests are scheduled for CIM scales. So far the Committee has been notified only twice, limiting the opportunity to work with the industry. Whenever possible, the Committee members would like to observe the test process in order to gain a better understanding of the many considerations and difficulties involved. The Committee encourages weights and measures officials to work with the industry to better understand CIM weighing and the testing of CIM scales.

Committee Recommendation: The items addressing the custody transfer of liquids and mixed merchandise (mixed manifest) trains are information items in 1990. The Committee plans to present recommendations for vote in 1991. The recommendation is expected to be that the CIM scales used to determine individual car weights for custody transfer shall be tested with the "as used" test procedures. Presenting these items as information this year will permit further study of the S&T proposals and provide additional time to resolve some remaining concerns on these issues.

320-8 I Weighing Individual Railroad Cars for Custody Transfer; Mixed Manifest Trains

Discussion: The CIM weighing of mixed merchandise trains (mixed manifest trains) introduces even more variables into the weighing process than does the weighing of liquids in tank cars. While trains dedicated exclusively to weighing tank cars will generally have cars of very similar design, a mixed merchandise train may have empty and loaded cars, cars of differing design, cars with different types of couplers, and loaded cars of widely differing weights. Each of these variables introduces an additional source of potential errors. Unit trains have the advantage that the summed weight for groups of cars from one consignor to one consignee can have errors on adjacent cars which will cancel to some degree, hence the group weight may be accurate even though there are errors in the weights of individual cars.

The data provided to the Committee up to this time have not convinced the Committee that CIM weighing is appropriate for determining the weight of individual cars for custody transfer when weighed as part of a mixed merchandise train. Even if the Committee were ultimately convinced of the appropriateness of CIM weighing for this purpose, it is the view of the S&T Committee that, as a minimum, CIM scales used to weigh mixed merchandise trains for the custody transfer of individual cars (as distinguished from weighing for the purposes of freight charges) should be required to be tested with the "as used" test procedures. Efforts would have to be made to test CIM scales with a train with as many different types of cars as possible and, if possible, in a variety of car combinations to determine the performance of the scale.

The Committee is considering proposing a requirement that the weights from CIM scales used for the custody transfer of individual cars identify that the car(s) were weighed on a CIM scale and identify the specific scale (see Item 320-7).

Data received by the S&T Committee indicate that cars with rotary couplers may not be suitable for CIM weighing when individual cars in mixed merchandise trains are to be used for custody transfer. Additionally, changes in track configuration may have a significant effect on weights obtained from CIM scales. All of these issues must be considered as more variables are introduced for CIM weighing for custody transfer of individual cars.

The S&T Committee has requested and continues to request that the industry notify Committee members when tests are scheduled for CIM scales. The Committee has so far been notified only twice, limiting the opportunity to work with the industry. Whenever possible, the Committee members would like to observe the test process in order to gain a better understanding of the many factors and difficulties involved. The Committee encourages weights and measures officials to work with the industry to better understand CIM weighing and the testing of CIM scales.

Committee Recommendation: The items addressing the custody transfer of liquids and mixed merchandise (mixed manifest) trains are information items in 1990. The Committee plans to present recommendations for vote in 1991. The recommendation is expected to be that the CIM scales used to determine individual car weights for custody transfer shall be tested with the "as used" test procedures. Presenting these items as information items this year will permit further study of the S&T proposals and provide additional time to resolve some remaining aspects of these issues.

320-9 V T.1. Tolerances for Unmarked Scales; Reorganization

(This item was adopted.)

Discussion: The organization and structure of the T.1. tolerance section of the Scales Code have resulted in different interpretations as to whether or not the subparagraphs T.1.1.1., T.1.1.2. and T.1.1.3. apply to those scales that are referred to the T.N. section for their tolerances. It is the view of the industry members who participated in the SMA Technical Subcommittee that led to the current tolerances in Handbook 44 that the subparagraphs T.1.1.1., T.1.1.2. and T.1.1.3. do not apply to those devices. The S&T Committee agrees that unmarked devices that were referred to the tolerances for marked scales by paragraph T.1. should have the same tolerances applied as to marked scales. The Committee also believes that the tolerances for unmarked scales can be better understood by placing the bulk of the tolerance requirements into a table format.

The recommendations in this item do not change the tolerances that are to apply to unmarked scales; however, the reorganization will change the way the tolerances are applied by many weights and measures officials. Many weights and measures officials have been adding one-half scale division to digital scales and have been using the 1.5 multiplier for the decreasing load test for automatic indicating scales. The minimum tolerance specified in T.1.1.3. is not of significance to this issue since the minimum tolerance for marked scales is incorporated into Table 6 under T.N.3.1.

Committee Recommendation: The Committee recommends the current T.1. section be deleted and the tolerance requirements restated as follows.

T.1. Tolerance Values.

T.1.1. General. - The tolerances applicable to devices not marked with an accuracy class shall have the tolerances applied as specified in Table X.

T.1.1.1. Decreasing-Load Tests on Automatic Indicating Scales. - One and one-half (1.5) times the tolerance values shall be applied.

[Editor's Note: Paragraph T.1.1.1. was deleted from the Scales Code since the decreasing load multiplier is included in Table X for the specific devices to which it applies.]

T.1.1.2. To Tests Involving Digital Indications or Representations. - To the tolerances that would otherwise be applied, there shall be added an amount equal to one-half the minimum value that can be indicated or recorded. This does not apply to digital indications or recorded representations that have been corrected for rounding error using error weights.

T.1.1.3. Minimum Tolerance. - When not otherwise specified, the minimum tolerance to be applied shall be 0.05% (1/2000) of scale capacity or one-half "d", whichever is less.

T.1.2. Postal and Parcel Post Scales. - The tolerances for postal and parcel post scales are given in Table X and in the following table.

Table 5
Maintenance and Acceptance Tolerances for
Postal and Parcel Post Scales

Scale capacity	Test loads	Maintenance tolerance		Acceptance tolerance	
		(±)		(±)	
Pound	Pound	Ounce	Pound	Ounce	Pound
0 to 4, inclusive*	0 to 1, inclusive	1/32	0.002	1/32	0.002
	over 1	1/8	0.008	1/16	0.004
over 4*	0 to 7, inclusive	3/16	0.012	3/16	0.012
	7+ to 24, inclusive	3/8	0.024	3/16	0.012
	24+ to 30, inclusive	1/2	0.030	1/4	0.015
	over 30	0.1% of Test Load		0.05% of Test Load	

*See Table X for scales designed and/or used to weigh loads less than 2 lbs.

Table X: Tolerances for Unmarked Scales

Type of Device	Subcategory	Min. Tol.	Accept. Tol.	Maint. Tol.	Decreasing Load Multiplier ¹	Other Applicable Requirements
Vehicle, axle-load, Livestock, railway track (weighing statically), crane, and hopper (other than grain hopper)		Class III L, T.N.3.1 (Table 6) and T.N.3.2.			N/A	T.N.2., T.N.3., T.N.4.1, T.N.4.2, T.N.4.3, T.N.4.4, T.N.5, T.N.7.2.
Grain test scales	n ≤ 10,000	Class III, T.N.3.1. (Table 6) and T.N.3.2.			N/A	
	n > 10,000	Class II, T.N.3.1. (Table 6) and T.N.3.2.			N/A	
Railway track scales weighing in motion		T.N.3.6. except that for T.N.3.6.2. (a), no single error shall exceed four times the maintenance tolerance.			N/A	
Reverse-vending machines (T.1.10.)		± 5% of applied material test load.				
Wheel-load weighers and portable axle-load scales	Tested individually or in pairs ²	0.5d or 50 lb, whichever is greater	1% of test load	2% of test load	1.5	T.1.1.2.
Prescription scales	Graduated	0.1 grain (6 mg)	0.1 % of test load	0.1% of test load	1.5	T.1.1.2.
	Ungraduated	0.5d	0.05% of test load	0.05% of test load	1.5	T.1.1.2.
Jewelers' scales		Sensitivity or smallest weight, whichever is less				
Dairy-product-test scale	Loads < 18 g	0.2 grain	0.2 grain	0.2 grain	1.5	T.1.1.2.
	18 g load	0.2 grain	0.3 grain	0.5 grain		
Postal and parcel post scales Designed/used to weigh loads < 2 lb	Loads < 2 lb	15 grain, 1 g, 1/32 oz, 0.03 oz, or 0.002 lb	15 grain, 1 g, 1/32 oz, 0.03 oz, or 0.002 lb	15 grain, 1 g, 1/32 oz, 0.03 oz, or 0.002 lb	1.5	T.1.1.2.
	Loads > 2 lb	Table 5	Table 5	Table 5	1.5	T.1.1.2.
Other postal and parcel post scales	d < 1/16 oz, 0.005 lb, 2 g, or 35 grains	0.5d or 0.05% of scale capacity, whichever is less	Table 5	Table 5	1.5	T.1.1.2.
	n < 2,000	0.5d or 0.05% of scale capacity, whichever is less	Table 5	Table 5	1.5	T.N.2.5, T.N.4.1, T.N.4.2, T.N.4.3, T.N.5, T.N.7.2.
All other scales	n > 5,000	0.5d or 0.05% of scale capacity, whichever is less	Table 5	Table 5	1.5	T.1.1.2.
	2,000 ≤ n ≤ 5,000	Class III, Table 6 & T.N.3.2.	Class III, Table 6 & T.N.3.2.	Class III, Table 6 & T.N.3.2.	N/A	T.N.2., T.N.3., T.N.4.1, T.N.4.2, T.N.4.3, T.N.5, T.N.7.2.

1. The decreasing load test applies only to automatic indicating scales.

2. If marked and tested as a pair, the tolerance shall be applied to the sum of the indications.

320-10 V T.1. Tolerances for Unmarked Scales; Revision

(This item was adopted.)

Discussion: The Committee received one request in 1987 and three requests in 1988 to modify T.1.1., T.1.1.1., T.1.1.2., and T.1.1.3. to simplify the tolerance application to unmarked scales with less than 2,000 and more than 5,000 divisions. In 1989 the Committee reported Item 320-5 as information to provide an opportunity for further review of its proposal to simplify the tolerances for unmarked scales.

The Committee believes that it is better to substantially simplify the tolerance application for unmarked scales by making the tolerances for unmarked scales with less than 2,000 divisions the same as those for class III scales, although this simplification will result in significantly larger tolerances for some scales. The Committee recommends:

1. that the tolerances for all unmarked scales with 5,000 scale divisions or less, except those with tolerances specified in the current T.1.3. through T.1.11., be the tolerances in Table 6; and
2. further simplifying the tolerances and offsetting some of the increased tolerances for some scales, by dropping the additional one-half scale division tolerance given to digital indicating scales as specified in T.1.1.2.

In general, the effect of the additional 0.5 division tolerance on scales with less than 2,000 divisions is small on unmarked scales because fractions of a division are truncated when the tolerance is applied. For scales with more than 5,000 scale divisions, the additional one-half division tolerance represents only a very small part of the tolerance applied to the scale and can be considered negligible. The extra tolerance for the decreasing-load test would be retained for scales with more than 5,000 scale divisions. Scales with less than 5,000 scale divisions would lose the 1.5 multiplier for the decreasing-load test; however, the increase in the tolerances resulting from applying Table 6 to these scales would adequately compensate for the elimination of the decreasing-load test multiplier for scales with less than 2,000 divisions. Scales with 2,000 to 5,000 divisions, inclusive, already have the tolerances specified in Table 6 as their tolerances. The minimum tolerance for scales with more than 5,000 divisions is included in the amended T.1.2. Table 5 would remain in the Scales Code, but it would apply only to postal and parcel post scales (T.1.8.). The tolerances for the unmarked scales that have specific tolerances given in section T.1. would not be affected by this change, i.e., wheel-load weighers and portable axle-load scales, prescription scales, jewelers' scales, dairy-product-test scales, and postal and parcel post scales.

There has been general support for the proposed revision. Some comments oppose the change, primarily due to the larger tolerances that would apply to some scales with less than 2,000 scale divisions. It was stated that these larger tolerances would prolong the use of older scales that may not be suitable for today's commercial needs.

The Committee received another suggestion to delete the special tolerances established for postal and parcel post scales to further simplify the tolerances. This suggestion states that there are relatively few postal and parcel post scales that would be affected, and that the impact would be within acceptable limits.

The examples given in the 1989 S&T report of scale capacities by scale divisions that would be most significantly affected by this change are listed below.

9 x 0.005 lb	2 lb x 1/4 oz	10 lb x 1 oz	18 lb x 1 oz
24 lb x 1 oz	30 lb x 1 oz	1 lb x 1/8 oz	15 lb x 1/4 oz
15 lb x 1 oz	6 x 0.01 lb	4 lb x 1/4 oz	20 lb x 1/2 oz
390 x 0.2 lb	5 lb x 1 oz	5 lb x 1/2 oz	60 lb x 1 oz

Committee Recommendation: Change T.1.2. as follows.

T.1.2. SCALES WITH LESS THAN 2000 SCALE DIVISIONS OR MORE THAN 5000 SCALE DIVISIONS.

- Except for scales specified in paragraphs T.1.3. through T.1.11., the maintenance ~~and acceptance~~ tolerances shall be ~~as shown in Table 5 (next page)~~ 0.1 percent of an applied test load; the acceptance tolerance shall be 0.05 percent of the applied test load. In any case, the tolerance shall not be less than 0.5 scale division. Paragraphs T.N.2.5., T.N.4.1., T.N.4.2., T.N.4.3., T.N.5., and T.N.7.2. also apply.

If Item 320-9 is not accepted by the Conference, then as part of this item, the Committee recommends that: (1) the heading for Table 5 be changed to:

Maintenance and Acceptance Tolerances for Postal and Parcel Post Scales

and (2) T.1.1.2. and T.1.1.3. be deleted.

If Item 320-9 is adopted, then consistent with the table format for the tolerances recommended in Item 320-9, the text of T.1.2. would not appear in Handbook 44. Instead, the tolerance change would affect Table X as shown in the table headed Item 320-10: Revised Tolerances for Unmarked Scales.

320-11 V T.N.1. Principles; Multiple-Weighing Devices Interfaced with a Single Indicator

(This item was adopted.)

Discussion. The number of vehicle scales consisting of three or more individual weighing elements used simultaneously to obtain a gross weight for commercial transactions is increasing. The individual weighing elements are used to obtain axle-load weights to determine compliance with highway laws and, because the entire vehicle is weighed as a single draft, the summed weight may be used for commercial transactions. The classification of the system as a single scale would mean that the entire system shall not exceed the maximum number of scale divisions for the application. A vehicle scale consisting of three weighing devices would then also have to meet T.N.4.4. across all of the sections.

This approach to weighing has raised the question of how the number of scale divisions permitted in class III or III L scales should be applied. For example, a vehicle scale may have three platforms with the following capacities: 100,000 x 20 lb, 100,000 x 20 lb, and 60,000 x 20 lb. The sum of these scale capacities is 260,000 lb for a total of 13,000 divisions. Should the maximum number of divisions for class III scales apply to the summed indication? An argument can be made that the total is only the sum of digital indications, hence the 10,000 division limitation should not apply. However, a request had been received to permit four 20,000-lb x 5-lb capacity scales to be used in combination to provide a scale with a capacity of 80,000 x 5 lb, essentially to circumvent the class III L limit on the number of scale divisions. Consequently, the 10,000-division limit should apply to the summed indication, which is being used as the basis for commercial trade.

There is a similar situation in railroad weighing when rail cars are weighed in motion in multiple drafts. Each set of axles is weighed separately and combined to obtain the total weight of the car. It is the industry practice and the position of the Office of Weights and Measures that the capacity of the scale is the summed total of the anticipated maximum weights of the axles of the rail cars intended to be weighed on the scale. The 10,000 division limitation applies to the capacity rating of the scale although the static weighing capacity of the scale is a fraction (usually one-half) of the capacity rating of the scale.

Committee Recommendation: Multiple weighing elements (e.g., three axle-load scales permanently installed adjacent to one another or with a dead space between the weighing elements) used simultaneously to obtain a single weight in commercial applications shall be deemed to be a single system which shall meet the requirements of the applicable accuracy class.

The classification of a scale or weighing system into an accuracy class should be based upon its application and method of use, not on the design of the device. Although this item does not contain a recommendation for change to Handbook 44, this interpretation is presented to the Conference for a vote to obtain a clear statement of the requirements that are to apply to these weighing systems. The Committee is aware that a number of jurisdictions test each scale as an independent scale, not as a single weighing system. The significance of this interpretation is that not only must each independent weighing device meet the requirements of Handbook 44, but the entire weighing system must meet all requirements that would apply if the device were a single scale.

Revised Tolerances for Unmarked Scales

Table for Item 320-10

Type of Device	Subcategory	Min. Tol.	Accept. Tol.	Maint. Tol.	Decreasing Load Multiplier ¹	Other Applicable Requirements
Vehicle, axle-load, Livestock, railway track (weighing statically), crane, and hopper (other than grain hopper)			Class III L, T.N.3.1 (Table 6) and T.N.3.2.		N/A	T.N.2., T.N.3., T.N.4.1, T.N.4.2, T.N.4.3, T.N.4.4, T.N.5, T.N.7.2.
Grain test scales	n ≤ 10,000		Class III, T.N.3.1. (Table 6) and T.N.3.2.		N/A	
Railway track scales weighing in motion	n > 10,000		Class II, T.N.3.1. (Table 6) and T.N.3.2.		N/A	
Reverse-vending machines (T.I.10.)			T.N.3.6. except that for T.N.3.6.2. (a), no single error shall exceed four times the maintenance tolerance.		N/A	
Wheel-load weighers and portable axle-load scales	Tested individually or in pairs ²	± 5% of applied material test load.				
		Average error on 10 or more test loads ≤ 2.5%.		2% of test load	1.5	T.N.2.
Prescription scales	Graduated	0.5d or 50 lb, whichever is greater	0.1 % of test load	0.1% of test load	1.5	T.N.2.
Jewelers' scales	Ungraduated	Sensitivity or smallest weight, whichever is less	0.05% of test load	0.05% of test load	1.5	T.N.2.
Dairy-product-test scale	Loads < 18 g	0.2 grain	0.2 grain	0.2 grain	1.5	T.N.2.
	18 g load	0.2 grain	0.3 grain	0.5 grain		
Postal and parcel post scales	Loads < 2 lb	15 grain, 1 g, 1/32 oz, 0.03 oz, or 0.002 lb	15 grain, 1 g, 1/32 oz, 0.03 oz, or 0.002 lb	15 grain, 1 g, 1/32 oz, 0.03 oz, or 0.002 lb	1.5	T.N.2.
	Loads > 2 lb	Table 5	Table 5	Table 5	1.5	T.N.2.
Other postal and parcel post scales	d < 1/16 oz; 0.005 lb, 2 g, or 35 grains	Table 5	Table 5	Table 5	1.5	T.N.2.5, T.N.4.1, T.N.4.2, T.N.4.3, T.N.5, T.N.7.2.
All other scales	n < 2,000	0.5d or 0.05% of scale capacity, whichever is less	Table 5	Table 5	1.5	T.N.2.
	n > 5,000	0.5d or 0.05% of scale capacity, whichever is less	Table 5	Table 5	1.5	T.N.2.
	2,000 ≤ n ≤ 5,000	Class III, Table 6 & T.N.3.2.	Class III, Table 6 & T.N.3.2.	Class III, Table 6 & T.N.3.2.	N/A	T.N.2., T.N.3., T.N.4.1, T.N.4.2, T.N.4.3, T.N.5, T.N.7.2.

1. The decreasing load test applies only to automatic indicating scales.

2. If marked and tested as a pair, the tolerance shall be applied to the sum of the indications.

The Committee recommends that the following criteria be applied to multiple-weighing devices interfaced with a single indicating element:

1. The number of divisions in the weight indicator displaying the summed weight of all weighing elements of a scale consisting of multiple weighing elements (weighing simultaneously) shall not exceed the maximum permitted for the accuracy class (10,000 for class III and III L). The capacity by division must be marked on the weight display of the summing indicator.
2. Separate weight displays for individual weighing elements must have separate capacity statements. The number of divisions for each weighing element must satisfy the requirement for the number of scale divisions for the accuracy class. The scale division values for each weighing element and the weight display that is summing the weight values must be the same.
3. The capacity of the summed weight display shall not exceed the sum of the capacities of the individual weighing elements.
4. If one weighing element is overloaded and blanks out, then the summing weight display must also blank out.
5. All scale sections in the multiple weighing elements used simultaneously must agree within the absolute value of the maintenance tolerances (T.N.4.4.) as if the scale had a single weighing element.

Multiple weighing devices that are independent and used separately to weigh components that are mixed to obtain a final product shall be treated as separate scales, and each scale must meet the requirements of the applicable accuracy class.

[Editor's Note: The failure to reference specific paragraphs as a basis for these interpretations was identified as a deficiency in this item. For reference purposes, the applicable paragraphs are General Code G-S.1. Identification; G-S.5.2.2. Digital Indication and Representation; Scales Code S.1.7. Capacity Indication, Weight Ranges, and Unit Weights; S.5. Design of Weighing Devices, Accuracy Class; Table 3; T.N.1. Principles; and T.N.4.4. Shift or Section Tests.]

320-12 V T.N.8.1.3. Temperature Effect on Zero-Load Balance

(This item was adopted.)

Discussion: Competition in the marketing of large capacity scales is driving scale manufacturers to offer vehicle scales with the maximum number of scale divisions (10,000) permitted for class III L scales. This, in turn, pushes load cell manufacturers to offer class III L load cells with 10,000 verification intervals. The requirement of T.N.1.8. becomes very stringent when a load cell has 10,000 verification intervals.

The National Type Evaluation Program has provided some relief to load cell manufacturers by recognizing the cancellation of random errors on the temperature effect on minimum dead load output of the load cells, but at the same time introduced a technical inconsistency into the process. This technical inconsistency stems from permitting a 1.0 multiplier to be used when applying the scale tolerances to load cells (a separate main element falling under T.N.3.5.) and applying the same concept when requiring the minimum verification scale interval of the load cell (v_{\min}) to be less than or equal to the verification scale division of the scale (e) divided by the square root of the number of load cells (N) used in the scale ($v_{\min} \leq e/\sqrt{N}$).

To correct this technical inconsistency and to provide a less stringent performance requirement on class III L load cells with 10,000 verification intervals, the Committee recommends a change in the performance requirement for class III L devices. This change is expected to have only a small impact on class III L scales used commercially because most of them are equipped with an automatic zero-setting mechanism (AZSM). The greatest effect of this change will be on class III L hopper scales, which are not permitted to have AZSM. These scales are normally under load for long periods of time; a significant temperature change when a load is on the scale could change the scale indication, but if the weight of interest is a net weight determined by measuring the difference between two weights over a short period of time, even a change in the indication will not be significant because the difference will still be correct.

Committee Recommendation: The Committee recommends that T.N.1.8.3. be replaced by the following:

T.N.8.1.3. Temperature Effect on Zero-Load Balance. - The zero-load indication shall not vary by more than:

- (a) three divisions per 9 °F (5 °C) change in temperature for class III L devices; and
- (b) one division per 9 °F (5 °C) change in temperature for all other devices.

320-13 I UR.1.1. Selection Requirements; Suitability of Equipment

Discussion: The S&T Committee has expanded a table (see next page) submitted by a regional weights and measures association to propose some initial criteria to be used to determine the suitability of equipment for various applications. Many of the requirements for various applications were extracted from existing requirements in Handbook 44; others were included for discussion purposes. The table includes a listing for on-board weighing systems because it is a separate item in the report (Item 320-14). The inclusion of on-board weighing systems is for the purpose of discussion and is not to be interpreted as acceptance by the S&T Committee in any accuracy class other than class III or III L.

Committee Recommendation: Guidelines to determine the suitability of equipment for different applications should be established. The Committee recommends that these guidelines be discussed, revised, and expanded at the meetings of the regional weights and measures associations to establish suitability of equipment criteria. A table listing possible categorization for scales is given below. Entries with question marks are main points of discussion.

These guidelines should be based upon the accuracy required for transactions which may include the cost of the commodity, the accuracy of the devices available for the measurement, the quantity division that will relate to the minimum quantity to be measured, and the minimum quantity that is normally measured. Several items in this report involve these concepts, namely, 320-12, 320-14, 320-16, 330-5, and 360-1. These issues are suggested for discussion at the meetings of the regional weights and measures associations.

Suitability of Equipment Criteria

Scales

<u>Device and Commodity</u>	<u>Loads or Deliveries</u>	<u>Maximum Division Value</u>	<u>Minimum Load or Delivery</u>	<u>Accuracy (Tol.) Required</u>
Digital computing scale or POS scale	Up to 50 lb	0.01 lb	20d	class III
Animal scale	Up to 2,500 lb	1 lb	20d	class III
Livestock Scales	≥ 100 lb	2 lb	50d	class III L
	≥ 250 lb	5 lb	50d	
	≥ 5,000 lb	10 lb	500d	
	≥ 10,000 lb	20 lb	500d	
Grain hopper scales	≥ 20d but up to 50,000 lb	10 lb	20d	class III
	over 50,000 lb	20 lb	20d	
Hopper scales (not grain)	≥ 50d		50d	class III L
Vehicle scale				class III L
Grain	≥ 1000 lb	20 lb	50d	
	≥ 100,000 lb	50 lb	50,000 lb ?	
Sand and gravel	≥ 50 d	100 lb	5,000 lb	
Solid waste	≥ 50 d	100 lb	5,000 lb	
On-Board weighing systems	≤ 500 lb	?	?	?
	> 500 lb	?	?	
Railway track scales	≥ 50,000 lb	200 lb	50d	class III L
Belt-conveyor scales	1,000 scale divisions		1000d	0.5%
Grain-test scale	≤ 500 g	0.2 g ?	20d	class III
	> 500 g	0.5 g	20d	class III

320-14 I UR.1.1. Selection Requirements; On-Board Weighing Systems

Discussion: The Committee has been requested to establish unique tolerances for on-board weighing systems. The argument for unique tolerances is based on the extensive abuse these devices must withstand due to highway travel, bumps, and other types of shock loading to the system. A tolerance larger than class III or III L, but still within the accuracy needed for the intended application, is requested. On-board weighing systems could be used effectively in some commercial applications, such as weighing liquid feed and fertilizers, solid waste products, and LP gas. These weighing devices are suitable for weighing some commodities based upon the tolerances permitted for particular commodities.

The Committee is opposed to creating a separate accuracy class for these devices. The Committee continues to study the proposal that suggests revising the tolerances for class III scales and then permitting class III scales to be used for some commercial applications. The suitability of equipment issue is critical to this discussion.

Committee Recommendation: This issue should be studied further through the regional weights and measures associations. These discussions should address the suitability of equipment for the commodities being weighed, the accuracy required to weigh the commodities, and the potential impact of competition with class III L where suitability of equipment has dictated that class III L scales be used in specific applications. Manufacturers of on-board weighing systems are requested to submit test data obtained in cooperation with weights and measures officials to document the performance of the devices that have been permitted for use by individual States. This information could then be used as a basis to further analyze the request to establish different tolerances for on-board systems.

320-15 VC UR.3.1. Recommended Minimum Load; Weight Classifiers

(This item was adopted as part of the consent calendar.)

Discussion: A scale must perform within tolerance at any test load. The tolerance for any scale includes error resulting from scale rounding, the internal resolution of the scale, and the weighing error in the scale. Weight classifiers are programmed to round weight indications up to the next higher digit once the nominal value of an indication is exceeded. This approach reduces the round-off error at the points where postal and rate charts change from one rate to another. The remaining primary sources of error in weight classifiers at the weights at which rates change are (1) the internal resolution of the scale and (2) the weighing error of the scale. Although the acceptance tolerance of any marked scale is 0.5d at 10d and 20d, the inherent weighing error of the scale must be much less to enable the scale to be within tolerance at 500d.

Because weight classifiers eliminate the round-off error for small loads, the S&T Committee recommends that a minimum load of 10d be recognized for these types of scales. The effect of this change is that scales intended for use in postal applications may have divisions of 0.1 oz instead of 0.05 oz. This slightly larger division value makes it easier for the scale manufacturer to produce a scale with a higher capacity at lower cost for the postal and parcel post applications. Although it has been cited that West Germany has accepted a minimum load of 10d for weight classifiers, apparently they have not accepted the minimum load of 10d for weighing letters.

The Committee has some concerns about recommending a minimum load of 10d for weight classifiers. These are that:

1. it sets a precedent of a 10d minimum load for a class III scale;
2. these scales will have double the tolerance for larger loads than a scale that rounds off to the nearest division; and
3. this smaller minimum load appears to give weight classifiers a competitive advantage in postal and parcel applications.

In any event, the Committee has not received comments against this proposal. Consequently, the Committee is recommending the change in the recommended minimum load for weight classifiers.

Committee Recommendation: The Committee recommends that a footnote be added to Table 8 for class III scales:

A minimum load of 10d is recommended for a weight classifier marked in accordance with a statement identifying its use for special applications.

320-16 I UR.3.1.1. Minimum Load, Grain Dockage Determination; Value of the Scale Division

Discussion: The Committee was asked to specify the maximum value of a scale division that is suitable for use on grain-test and grain-dockage scales. In general, two types of scales used for these applications appear to present problems. Both are fan-type automatic-indicating scales; one has a 5-g division, and the other has a 2.5-g division. The errors resulting from the lack of resolution may have a significant effect on the final price paid to the farmer. The value of the scale division permitted on grain-test scales was specified in the 1979 edition of Handbook 44, but the values were dropped after the 1985 edition when Tables 7a and 7b were adopted as part of the revised Scale Code.

For Handbook 44 applications, the NTEP type evaluation checklist permits percent calculations to be displayed only when the value of the scale division is less than or equal to 0.2 g for loads up to 500 g and less than or equal to 0.5 g for loads greater than 500 g. For FGIS applications, the following requirements must be satisfied:

1. To calculate and display percent values, the verification scale division shall not exceed 0.01 g for loads up to 120 g and 0.5 g for loads in excess of 120 g through 1 000 g.
2. The percent values shall be rounded and displayed to at least 0.1 percent.
3. To calculate and display test weight values, the verification scale division shall not exceed 0.5 g.
4. For official weighing, the FGIS has three categories of electronic laboratory scales used as grain test scales: precision, moisture, and general. The accuracy classes and scale divisions used for these scale categories shall not exceed those given in the following table.

Category	Accuracy Class	Scale Division
Precision	II	$e \leq 0.01 \text{ g}; d \leq 0.01 \text{ g}$
Moisture	II, III	$e \leq 0.1 \text{ g}; d \leq 0.1 \text{ g}$
General	II, III	$e \leq 0.5 \text{ g}; d \leq 0.5 \text{ g}$
Note: For Class III scales, $e \leq d$.		

More study is required before maximum division values can be specified for these scales.

Committee Recommendation: Study this issue.

320-17 I T.1. Tolerance Values; In-Motion Weighing, Monorail Scales

Discussion: In 1985 the Tolerances Section of the Scales Code was separated into sections for marked and unmarked scales. Due to an oversight, there is no reference to unmarked monorail scales that weigh while the carcass is moving across the scale; this tolerance is expressed in the paragraph T.N.3.7. Assuming that Item 320-10 is adopted, an entry in the table in Item 320-10 will be added editorially to specify the tolerance for these scales as the tolerances in T.N.3.7.

321 Belt-Conveyor Scale Systems

321-1 VC N.3.3. Simulated Load Tests

(This item was adopted as part of the consent calendar.)

Discussion: The number of required simulated load tests and the agreement required among these tests were deleted from the Note paragraph N.3.3. last year when simulated load tests as recommended by the manufacturer were specified. Requirements are needed to specify a minimum level of testing and performance. The Committee recommends establishing a requirement on the repeatability of the simulated load test. This recommendation would require a simulated load test to be run shortly after the material test to establish the factor that relates the results of the simulated load test to the results of the material test.

Committee Recommendation: The Committee recommends that N.3.3. be amended to read:

N.3.3. Simulated Load Tests. -

- (a) As required by the certifying authority, simulated load tests as recommended by the manufacturer are to be conducted between material tests to monitor the system's operational performance, but shall not be used for official certification.
- (b) A simulated load test consisting of at least three consecutive test runs shall be conducted as soon as possible, but not more than 12 hours after the completion of the material test, to establish the factor to relate the results of the simulated load test to the results of the material tests.
- (c) The results of the simulated load test shall repeat within 0.1 percent.

330

Liquid-Measuring Devices

330-1

I S.3. Discharge Lines and Valves

Discussion: Stage II vapor recovery is required in more cities and States. The S&T Committee has been asked to provide a statement that nothing in Handbook 44 prevents the use of a single delivery hose on a multi-product dispenser. A single delivery hose on a multi-product dispenser reduces the cost of a dispensing system and reduces customer difficulty in handling a heavy hose if no other hoses interfere. The sampling method established in 1989 by the Laws and Regulations (L&R) Committee for the octane level of product dispensed by blend dispensers shall also be used for multi-product dispensers using a single delivery hose. Device manufacturers are considering using one delivery hose on multi-product dispensers because they can meet the octane requirements when a minimum of 0.3 gallon product is delivered before the sample is taken for the octane test.

See Item 237-1 in the 1989 L&R Committee report for further information on this issue.

Committee Recommendation: After having reviewed the issue, the Committee has concluded that nothing in Handbook 44 prevents a single delivery hose from being used on a multi-product dispenser; however, a single delivery hose cannot be used for dissimilar products, such as gasoline and diesel fuel.

330-2

VC S.3.9. Antidrain Means

(This item was adopted as part of the consent calendar.)

Discussion: The National Fire Protection Association requires that the nozzle on a wet-hose device used in self-service applications cannot be opened unless there is pressure on the hose. Nozzle manufacturers have designed a nozzle that cannot be opened unless there is pressure on the hose. It is possible to release a very small amount of liquid if the liquid in the hose expands when the hose is in the sunlight on a hot day, but the quantity is very small and the design of the nozzle prevents the draining of the hose.

A manufacturer provided the S&T Committee with a cut-away example of this type of nozzle. The Committee is convinced that the nozzle appears to be as effective as an antidrain valve to prevent the draining of the hose. Consequently, the Committee recommends permitting this type of nozzle to be used instead of requiring an antidrain valve in the nozzle.

Committee Recommendation: To be more general and recognize methods other than an antidrain valve to prevent draining of the hose, the Committee recommends amending S.3.9. to read:

S.3.9. Antidrain Valve Means. - In a wet hose, pressure-type device, ~~an antidrain valve~~ means shall be incorporated ~~in or immediately adjacent to the discharge valve~~ to prevent the drainage of the discharge hose.

330-3 W UR.2.5. Product Storage Information

(This item was withdrawn.)

Discussion: This item proposed requiring the fill pipes for product storage tanks be marked as to the product contained by means of a color code that complies with the codes outlined in the American Petroleum Institute (API) Recommended Practice 1637 and API Bulletin No. 1542. Uniform coding would reduce the potential of contaminating fuel supply tanks with the wrong product and increase the confidence of the weights and measures official that the product is being returned to the correct storage tank after a test of the dispensers. This proposal was submitted to the S&T Committee in 1987 (Item 330-17) and was not proposed for adoption because the Committee believed weights and measures jurisdictions could require the fill lines to be marked, but that it was inappropriate for Handbook 44 to specify the markings or codes that must be used. The position of the Committee has not changed.

Committee Recommendation: Withdrawn.

330-4 V UR.3. Use of Device; UR.3.3. (b) Computing Device

(Voting item 1 failed, voting item 2 was adopted.)

Discussion: In 1989 the Conference adopted changes to require that:

1. after January 1, 1990, any dispenser (with limited exceptions) placed into a multi-tier pricing (typically cash/credit pricing) application must either compute the sales price for all unit prices for which the product is offered for sale or be dedicated to those sales for which it can compute (UR.3.3.);
2. effective January 1, 1991, a new computing device shall compute the total sales price at any single-purchase unit price (with limited exceptions) for which the product is offered for sale (S.1.6.5.); and
3. effective January 1, 1991, new computing devices used in multi-tier pricing applications shall have controls on the device or other user-activated controls to select the unit price for the transaction (S.1.6.5.4.).

The Conference adopted policy to require dispensers to compute the sales price at which the product is offered for sale, but did not agree upon a date by which single unit price dispensers used in multi-tier pricing applications prior to January 1, 1990, must either (1) be modified or replaced to be able to compute at all of the unit prices for which product is sold through the device or (2) be dedicated to those sales for which the dispenser can compute the sales price. Three regional weights and measures associations have suggested a cutoff date of January 1, 1995, and one association has suggested January 1, 1999. It is clear to the Committee that the Conference wants to establish a cutoff date by which all devices used in multi-tier pricing applications must be able to compute the sales price for which the product is being sold.

The Committee has debated the many facets to this issue and is well aware of the impact on the industry. The Committee supports January 1, 1999 as a final date for dispensers to compute at the unit price or prices at which the product is offered for sale. Thereafter, all devices would either (1) be able to compute at all of the unit prices for which product is sold through the device or (2) be dedicated to those sales for which the dispenser can compute the sales price. It is emphasized that this would not require that dispensers be converted; however, some stations may choose to discontinue the marketing practice of multi-tier pricing if it is not economically practical to convert to multi-tier pricing equipment or to dedicate dispensers or hoses to sales at a single unit price.

As part of this issue, the Committee received some comments suggesting that the January 1, 1990 date stated in UR.3.3. be changed to coincide with the final date by which all dispensers must compute the sales price for the unit prices at which product is offered for sale through the device. The motivation behind the UR.3.3. requirement adopted in 1989, was to prevent an increase in the number of devices that the Conference considers not suitable for multi-tier pricing applications. The Committee does not support a change in the January 1, 1990 date, and is not aware of sufficient support within the Conference to reconsider the 1989 decision.

Specifications and Tolerances Committee

Committee Recommendation: The S&T Committee is offering the Conference the selection of the effective date of this requirement as either January 1, 1995 or January 1, 1999, as separate voting items. Based upon economic and other factors, the Committee believes the January 1, 1999 date is the most realistic choice of dates. The January 1, 1995 date will be presented first. If it is accepted, the vote on the January 1, 1999 date will be withdrawn. If neither the January 1, 1995 date nor the January 1, 1999 date are adopted, the proposed addition of UR.3.3.(b) will fail and a final date for the implementation of this deadline will not be established at this Annual Meeting.

Voting Item 1:

The Committee recommends that a part (b) be added to UR.3.3. to read:

- (b) A computing device shall be used only for sales for which the device computes and displays the sales price for the transaction.
(Effective and retroactive as of January 1, 1995)

(This voting item failed.)

Voting Item 2:

The Committee recommends that a part (b) be added to UR.3.3. to read:

- (b) A computing device shall be used only for sales for which the device computes and displays the sales price for the transaction.
(Effective and retroactive as of January 1, 1999)

(This voting item was adopted.)

330-5 I Definitions of Retail and Wholesale

Discussion: The S&T Committee has expanded a table, submitted by a regional weights and measures association, proposing some initial criteria for determining the suitability of equipment for various applications. Many of the requirements for various applications come from Handbook 44; others were included for discussion purposes. The Committee recommends that these tables (see also Item 320-13) be discussed, revised, and expanded at the meetings of the regional weights and measures associations to establish suitability of equipment criteria. A table listing possible categorization for liquid-measuring devices follows.

Suitability of Equipment Criteria

Liquid-Measuring Devices

<u>Device and Commodity</u>	<u>Loads or Deliveries</u>	<u>Maximum Division Value</u>	<u>Minimum Load or Delivery</u>	<u>Accuracy (Tol.) Required</u>
Motor-fuel device				
Analog	≤ 100 gallon	0.1 gallon	?	0.5%
Digital	≤ 100 gallon	0.01 gallon	100d	0.5%
Either	> 100 gallon	0.1 gallon	500d	
Loading rack	≤ 1,000 gallon	0.1 gallon	500d	0.3%
	> 1,000 gallon	1 gallon	500d	0.3%
VTM				
gas, fuel	≤ 1,000 gallon	0.1 gallon	500d	0.22%
	> 1,000 gallon	1 gallon	500d	0.22%
Agri-chem	See below	See below	See below	1.0%
Milk	≤ 1,000 gallon	1 pint	?	0.2%
	> 1,000 gallon	1 gallon	1000d	0.2%
LPG & NH ₃				-1.5% / +1.0%
Agri-chemical	≤ 100 gallon	0.01 gallon	500d*	-1.5% / +1.0%
	≥ 100 but ≤ 1000 gallons	0.1 gallon	500d	1.0%
	> 1,000 gallons	1 gallon	500d	1.0%
Mass Flow Meters				
gas, fuel oil				0.3%
Agri-chemical				1.0%
Milk				0.2%
LPG/NH ₃				-1.5% / +1.0%
Hydrocarbon vapor				-3.0% / +1.5%

*Italics means nonretroactive

Committee Recommendation: The terms "retail" and "wholesale" should be removed from the code and criteria for suitability of equipment be established. However, terms are needed to replace "retail" and "wholesale" before their removal, since those terms are used to delineate specific requirements applying to certain devices. The regional weights and measures associations are requested to discuss these issues and to recommend terminology.

Guidelines for suitability of equipment for different applications should be based upon the accuracy required for transaction, which may include the cost of the commodity, the accuracy of the devices available for the measurement, the quantity division that will relate to the minimum quantity to be measured, and the minimum quantity that is normally measured. Several items in this report involve these concepts, namely 320-12, 320-14, 320-16, 330-5, and 360-1. These issues are suggested for discussion at the meetings of the regional weights and measures associations.

332-1

(This item was adopted as part of the consent calendar.)

Committee Recommendation: Reorganize S.14.2., delete the reference to retail motor-fuel device, and replace the words with stationary retail device so S.14.2. will read as follows:

(a) Primary indicating elements shall be readily returnable to a definite zero indication. Means shall be provided to prevent the return of primary indicating elements, and of primary recording elements if these are returnable to zero, beyond their correct zero position.

(b) Primary recording elements on a ~~retail motor-fuel~~ stationary retail device, if the device is equipped to record, shall be readily returnable to a definite zero indication.

333

333-1

(This item was adopted as part of the consent calendar.)

The Committee has been advised that the meter performance for the low-flame test is typically a pass or fail situation. Either the meter registers quantity throughout the test cycle or it ceases to operate at some point in the test. Consequently, the tolerances specified for the low-flame test (T.1.1.) are not needed; the proposal substitutes a performance requirement for the low-flame test that looks for continuous registration of flow at a very low pressure to determine if the meter ceases to register at some point during the test. At least one revolution of the tangent arm is needed to test the meter performance throughout one measurement cycle of the meter. All vapor meters will make one complete cycle of the tangent arm within 60 minutes. This is ample time to demonstrate any mechanical binds or internal leakage within the meter housing.

N.3. Test Drafts. - Except for low-flame tests, test drafts should be at least equal to one complete revolution of the largest capacity proving indicator, and shall in no case be less than 2 cubic feet or 0.05 cubic meter. All flow rates shall be controlled by suitable outlet orifices.

168

N.4.2.2. Low-Flame Test. - The device shall be tested at an extremely low-flow rate as given in Table 1. The test shall consist of passing air at a pressure of 1.5 inches water column through the meter for not less than 60 minutes. The quantity of air registered by the meter shall be determined at a minimum of three approximately equal time intervals. (See T.1.1. for the performance requirement for this test.)

Delete the existing text of T.1.1. and replace it with the following:

T.1.1. On Low-Flame Test. - ~~The maintenance and acceptance tolerances shall be 20 percent on underregistration and 10 percent on overregistration.~~ The quantity registered during the time intervals for the low-flame test shall agree within 30 percent.

333-2 VC LPG Vapor Meters Installed Adjacent to Heaters Vaporizing LP Gas

(This item was adopted as part of the consent calendar.)

Discussion: A gas-fired heater is sometimes used to vaporize LPG prior to metering the vapor. A vaporizer may be used to generate a higher pressure to overcome the use of undersized piping in the vapor distribution system when the system is unable to supply adequate product to meet the demand. The vapor discharged from the vaporizers can be very warm (70 °F to 90 °F). A customer purchasing gas through a gas-fired vaporizer/metering system will pay for more gas than if the product were metered at ambient temperature.

The National Propane Gas Association (NPGA) has stated that LPG tanks are located at least 50 feet from the nearest building or property line for safety and operational reasons. Thus, in most cases the vapor will have cooled to ambient temperature before it is measured. In those instances where the vapor meter is located close to the vaporizer, the NPGA agrees that the vapor should be temperature-compensated to 60 °F.

The Committee recommends that when vaporizers are used and vapor meters are installed close to the vaporizers such that the product does not cool to the ambient temperature, then the meter shall automatically temperature-compensate the product. Additionally, a thermometer well to measure the temperature of the product being metered may be required if deemed necessary by the weights and measures official.

The NPGA has provided a detailed analysis of the heat loss from vapor through bare steel pipe of various sizes buried underground. This information may assist the weights and measures official to determine when an automatic temperature compensation system may be needed. The analysis shows that, for a vaporizer load of 80 gallon/hour being converted to 2909 ft³ of LP gas vapor heated to 120 °F, the length of pipe needed to cool the vapor to the ground temperature of 55 °F ranges from 24 to 41 feet. The length of pipe needed will depend upon the load on the vaporizer, the temperature to which the vapor is heated, and the size and type of pipe. Copies of the equations and the analysis are available from the Office of Weights and Measures.

Committee Recommendation: The Committee recommends adding a new paragraph UR.2.5. to read:

UR.2.5. Use of Auxiliary Heated Vaporizer Systems. - Automatic temperature compensation shall be used on hydrocarbon gas vapor meters equipped with an auxiliary heated vaporizer system unless there is sufficient length of underground piping to provide gas at a uniform temperature to the meter inlet. When required by weights and measures officials, a thermometer well (appropriately protected against freezing) shall be installed immediately up-stream of the meter.

336 Water Meters

336-1 VC N.4.1. Normal Tests

(This item was adopted as part of the consent calendar.)

Discussion: Some water meters are rated for flow rates higher than those shown in Table 1. Some meters pass the tolerance requirements when tested at the Table 1 values, but fail when tested at the manufacturer's rated capacity.

These meters shall be accurate over the range of flow rates specified by the manufacturer. Whenever possible, these meters should be tested at flow rates above the Table 1 ratings, but not to exceed the meter rating.

Committee Recommendation: The Committee recommends that N.4.1. be amended to read:

N.4.1. Normal Tests. The normal test of a meter shall be made at the maximum discharge rate developed by the installation. Meters with maximum gallon per minute ratings higher than Table 1 values may be tested up to the meter rating.

353 Odometers Code

353-1 VC S.1.6. Digital Indications and Representation

(This item was adopted as part of the consent calendar.)

Discussion: A digital odometer submitted for type evaluation was found to truncate the mileage values (drop any fraction of a mile until the nominal distance was actually reached). These odometers may be used on rental cars and are commercial devices when used to determine mileage charges. Odometers that truncate mileage values currently violate the General Code requirement G-S.5.2.2.(c).

The Committee believes that odometers that truncate values are appropriate for car rental use because most mileage charges are for a sizable number of miles, hence the error due to rounding down is relatively small as a percentage of the total miles driven. Moreover, the truncation always favors the customer when the trip odometer is used. The Committee has been advised that digital odometers are commonly designed to truncate the mileage. Consequently, the Committee recommends adopting a new requirement in the Odometers Code to supersede G-S.5.2.2.(c) for digital odometers.

Committee Recommendation: The Committee recommends adding a new paragraph S.1.6. to the Odometers Code to read:

S.1.6. Digital Indications and Representation. - Digital indicating odometers (discontinuous registration) shall "round off" indications to the nearest minimum division or truncate indications to the lower minimum division.

354 Taximeters

354-1 VC S.1.3.2. Lighting of Indications

(This item was adopted as part of the consent calendar.)

Discussion: Based upon the current language of S.1.3.2., taximeters are required to provide illumination of fare indications, the operational controls of the taximeter, and other indications of passenger interest. The "other indications of passenger interest" referenced in S.1.3.2. includes the operating status of the taxicab, that is, whether or not the taxicab is vacant, hired, or operating in the time-off mode. The lighting of these various indications and controls must be integral to the meter. The requirement that the lighting be integral to the meter developed from the design of some taximeters that were to have a light source mounted on the meter to illuminate the indications and controls (as specified in UR.2.), but frequently the light source was not supplied.

Taximeter manufacturers generally design meters to have the fare indications illuminated, but the operational controls are usually not illuminated. It has been argued that there is little justification to require lighting of operator controls, such as the print key, keys to recall operator information (totals and other operator statistics), the credit card reader, and keys for tip entry. Additionally, the phrase "other indications of passenger interest" in S.1.3.2. is vague and open to subjective interpretation. The Committee recommends that S.1.3.2. be amended to delete the requirement to illuminate the operator controls and to specify which indications must be illuminated.

Committee Recommendation: The Committee recommends that S.1.3.2. be amended to read:

S.1.3.2. Lighting of Indications. Integral lighting shall be provided for illuminating the fare, ~~extras, the rate or rate code, and the taximeter status~~ indications, ~~operational controls, and other indications of passenger interest (i.e., vacant, hired, and time off, etc.).~~

[Nonretroactive as of January 1, 1989]

354-2 VC S.6. Short-Term Power Interruption, Electronic Taximeters

(This item was adopted as part of the consent calendar.)

Discussion: In some municipal areas, taximeters are mounted on slide mounts to permit the taxicab operator to remove the taximeter from the cab to discourage theft of the meter. These meters can be easily disconnected and reconnected in 3 seconds. Municipal areas with heavy taximeter use can have passenger turnover in 5 to 7 seconds. The 10-second time period for power interruptions allows these slide-mounted meters to be disconnected at the termination of one fare and reconnected as the initiation of the next fare, thereby defrauding a passenger. A shorter time period for a power interruption while still permitting the taximeter to advance would reduce the potential for fraud.

The acceptable methods of taximeter operation after short and long term power interruptions are specified in paragraphs S.6 and S.7. A proposal was made to establish a shorter time period (3 seconds) for the power interruption as it applies to removable taximeters as compared to a 10-second time period for permanently-installed taximeters.

The Committee concluded that no distinction in the duration of the power interruption requirement should be made based upon the method of mounting the meter; the power interruption criterion should be the same for permanently installed and removable taximeters. Consequently, the Committee recommends combining S.6. and S.7. into one paragraph consisting of two parts. Taximeter manufacturers have also stated through the NTEP type evaluation laboratories that they need more time to incorporate the design change of S.6. into their taximeters. Many models of taximeters do not meet the S.6. requirement. To afford more time for manufacturers to change the design of their taximeters, the Committee recommends that the requirements of S.6. and S.7. (as modified by the following recommended change to the Conference) become effective and nonretroactive on January 1, 1994. The changes are to become retroactive on January 1, 1999.

Committee Recommendation: The Committee recommends amending S.6. and S.7. by:

- (1) combining paragraphs S.6. and S.7. into a single paragraph;
- (2) making the requirement of S.6. nonretroactive and effective on January 1, 1994, but to become retroactive on January 1, 1999; and
- (3) base the acceptable meter operations upon power interruptions of three seconds.

The following language is recommended.

S.6. Short-Term Power Interruption, Electronic Taximeters.

- (a) After a power interruption of ± 3 seconds or less, the fare and extras indications shall return to the previously displayed indications and may be susceptible to advancement without the taximeter being cleared.*

S.7. Long-Term Power Interruption, Electronic Taximeters:

- (b) After a power interruption exceeding ± 3 seconds, the fare and extras indications shall return to the previously displayed indications and shall not be susceptible to advancement until the taximeter is cleared.*

[Effective and nonretroactive as of January 1, 1994. Retroactive after January 1, 1999.]

354-3

I T.1.2.2. On Average Time Interval Computed After Excluding the Initial Interval

Discussion: Although the electronic timing devices used in taximeters are quite accurate, errors of either overregistration or underregistration may occur. The electronic timing devices usually do not have any adjustment mechanism for accuracy, consequently the zero tolerance on overregistration is not practical. All devices, no matter how accurate, will have some overregistration or underregistration error. The tolerance for a device must also recognize the uncertainty in the test process used to test the time feature on taximeters.

In its Interim Report, the Committee recommended establishing a small fixed tolerance on overregistration consistent with the tolerance in the Timing Devices Code.

Committee Recommendation: The Committee recommends amending T.1.2.2. to read:

T.1.2.2. On Average Time Interval Computed After Excluding the Initial Interval. - Maintenance and acceptance tolerances on the average time interval excluding the initial interval shall be as follows:

- (a) On Overregistration: ~~0~~ 5 seconds for any time interval of 1 minute or more; and
- (b) On Underregistration: 3 seconds per minute (5 percent).

Change in Proposed Committee Action:

The Committee has received a more detailed explanation of the objection to this item from the State of California. Based upon the explanation and further analysis, the Committee has concluded that the change recommended in the Committee report is inappropriate and would need modification before a change should be made to T.1.2.2. Consequently, the Committee requests the permission of the Conference to change this item to an information item. As an information item, no change is made to T.1.2.2. at this time.

The Committee adds the following explanation of this item so any future proposal can consider the problem that has been brought to the attention of the Committee.

The request to recognize a tolerance for overregistration for the timers used in taximeters is based upon the desire to recognize that the timing mechanisms used in electronic taximeters are probably typical off-the-shelf mechanisms for which the manufacturing process targets zero error in timing as the optimum. Assuming that a normal distribution applies to the manufacturing process means that some production devices will overregister and some will underregister, although the overall accuracy of the timing mechanisms may be very good. If a tolerance of zero applies to overregistration, then timing mechanisms would have to be sorted to select only those timing mechanisms that underregister to be used in taximeters, or the manufacturing process would have to be changed to target production to underregister slightly. Since off-the-shelf timing mechanisms are probably used in many applications where it is best to target zero error in the operation of the timing mechanism, it appears reasonable to recognize a small tolerance for overregistration. A small tolerance for overregistration would have the additional benefit of addressing the small uncertainty in the test process that can affect the test on timing devices.

The Committee based its recommendation for the tolerance on overregistration on the tolerance expressed in the Timing Devices Code. It was the intent of the Committee that the overregistration tolerance of 5 seconds applies to the test of any time period regardless of length. However, the use of the term "time interval" in the Taximeter Code differs from the use in the Timing Devices Code.

The time intervals in the Taximeter Code address the intervals of the money drops based upon time, whereas the time intervals in the Timing Devices Code apply to any time interval selected for a test which can be long periods of time up to the capacity of the timing device. The Taximeter Code Note N.2. specifies that the time test of a taximeter consist of the following.

1. Check the initial time interval for the initial time drop.

2. Check at least four individual time intervals (time drops) after the initial time interval. Normally the first four consecutive time intervals following the initial time interval are tested for the accuracy of the individual interval. The tolerances stated in T.1.2.1. apply, which includes a nonzero tolerance for overregistration.
3. At least four consecutive time intervals after the initial time interval are tested and the average time for these four time intervals is computed. The four time intervals used to compute the average time for the time interval are usually the four time intervals checked for individual accuracy. The tolerance for the average time interval stated in T.1.2.2. applies. The overregistration tolerance on the average time for a time interval is zero.

Based upon the use of "time interval" in the Taximeter Code as the time interval of the taximeter time drop, which may be relatively short, the tolerance of 5 seconds for overregistration on the average time interval is excessive and undesirable. Consequently, the Committee recommends that the tolerances expressed in T.1.2.2. remain unchanged until the issue receives further study.

354-4 VC S.2.1. Initial Time and Distance Interval; UR.3. Statement of Rate

(This item was adopted as part of the consent calendar.)

Discussion: The programming of rates in some of the new types of electronic taximeters is very flexible. The programming permits the cost for the initial time interval to differ from the cost for the initial distance interval. In addition, the cost of the initial distance interval (or the initial time interval) may be different from the cost for subsequent distance (or time) intervals. The rates for these initial intervals are usually not posted.

The Committee recommends requiring the ratio of the initial time interval to the subsequent intervals to be equivalent to the ratio of the distance of the initial mileage interval to the subsequent intervals. It is recommended that paragraph UR.3. also be amended to require the rates for the initial time interval and the initial distance interval to be posted. If adopted, these changes will take effect on January 1, 1991.

Committee Recommendation: The Committee recommends adding a new subparagraph S.2.1. and amending UR.3. to read:

S.2.1. Initial Time and Distance Intervals. - The time and distance intervals of a taximeter shall be directly proportional as expressed in the following formula:

$$\frac{\text{Seconds of Initial Time Interval}}{\text{Seconds per Non-Initial Time Interval}} = \frac{\text{Distance of Initial Mileage Interval}}{\text{Distance per Non-Initial Mileage Interval}}$$

UR.3. Statement of Rates. - The distance and time rates for which a taximeter is set, including the initial distance interval and the initial time interval, and the schedule of extras when an extras indication is provided, shall be conspicuously displayed inside the front and rear passenger compartments. The words "Rate," "Rates," or "Rates of Fare" shall precede the rate statement. The rate statement shall be fully informative, self-explanatory, and readily understandable by the ordinary passenger, and shall either be of a permanent character or be protected by glass or other suitable transparent material.

360 Other Items

360-1 I Draft Code for Mass Flow Meters

Discussion: A separate code for mass flow meters is still under development. The draft code will be based upon the draft OIML recommendation and requirements for mass flow meters already in Handbook 44. Copies will be available from the Office of Weights and Measures upon request after the draft is completed.

360-2 I Lubricating Oil Meters

Discussion: The use of meters to sell lubricating oils is increasing. Special field standards and test procedures are needed to facilitate the testing of meters used in these applications.

Information has been submitted to the S&T Committee from the Measuring Industry Sector of the Technical Committee on National Type Evaluation and by the State of California. This information will be sent to the regional weights and measures associations for study. The S&T Committee requests comments and recommendations for uniform standards and test procedures to test lubricating oil meters.

360-3 I Draft Carbon Dioxide Liquid-Measuring Devices Code

Discussion: Delivery of liquid carbon dioxide to restaurants is increasing. The code is needed to provide adequate regulation of measuring devices for this product. The Office of Weights and Measures has not been able to do additional work on this code. A brief comparison of the draft code to the Cryogenics Liquid-Measuring Devices Code indicates many similarities. The Committee will continue to explore the possibility of incorporating the differences required for liquid carbon dioxide meters into a separate set of requirements within the Cryogenic Meter Code. Comments and the rationale regarding the unique requirements for liquid carbon dioxide meters and the justification for a separate code for these devices are requested.

360-4 I OIML Report

The following information was provided by Mr. O. K. Warnlof, Standards Management, NIST.

Discussion: The OIML schedule of activities for 1989/1990 has been extremely heavy and is expected to continue for the next several years, primarily because of "EC'92." The cooperation and interest of members of the NCWM is appreciated and your continued participation is encouraged. The following is an outline of activities for 1989/1990.

OIML WORK PROGRAM - 1989/1990

PS5D "Dynamic Measurement of Liquids"

RS1 "Meters With Measuring Chambers or Turbines"

Pre-Draft International Recommendation (IR) " Combined Document" circulated to National Working Group (NWG) - 6/21/89

Comments on 1st Pre-Draft "Combined Document" due Reporting Secretariat (RS) - 10/89

Comments received on 1st Pre-Draft and sent

2nd Pre-Draft "Combined Document" to be circulated by RS - 3/15/90

2nd Pre-Draft "Combined Document" received and circulated to NWG - 7/7/90

Meeting of NWG - 8/13-15/90, NIST, Gaithersburg, MD (Lecture Room D)

Comments on 2nd Pre-Draft due RS - 8/90

Meeting of International Working Group (IWG) - 10/24-26/90, NIST Gaithersburg, MD (Lecture Room A)

RS3 "Water Meters"

2nd Pre-Draft Revision R49 circulated to NWG - 8/17/89

Comments due to RS - 12/31/89

Comments received on 2nd Pre-Draft from AWWA, Badger Meter and sent - 1/90

Meeting of IWG - Late 1990

RS6 "Electronic Devices"

1st Draft IR "Electronics" circulated to NWG - 6/21/89

Comments and vote due to RS - 9/15/89
U.S."no" vote and comments sent - 9/7/89

RS7 "Methods & Devices for Verification" & RS9 "Vortex Meters"

- | | | |
|--|---|--|
| <p>(a) <u>Meeting of IWG - 11/6-10/89, Japan</u>
2nd Pre-Draft "Test Procedures, Gas Pumps"</p> <p>(b) 2nd Pre-Draft "Pipe Provers"</p> <p>(c) 1st Pre-Draft "Vortex Meters"</p> | } | <p>Due from RS for comment
prior to 11/89 meeting.</p> |
| <p>Received & Circulated to NWG - 9/20 for comments by 10/27/89
Comments Received - (a), API, Gilbarco; (b) and (c), NIST; comments sent to RS - 11/14/89</p> | | |

RS10 "Direct Mass Flow Meters"

Meeting of NWG - 10/23-24/89; NIST, Gaithersburg, MD (Metrology, A-340) to develop 2nd Pre-Draft.
Meeting of NWG - 3/20/90; NIST, Gaithersburg, MD (Lec A) to finalize 2nd Pre-Draft.
2nd Pre-Draft circulated to IWG 3/22/90 for comment by 8/1/90
Meeting of NWG - 8/15-16/90 NIST, Gaithersburg, MD, to review comments received.
Meeting of IWG - 10/22-23/90 NIST, Gaithersburg MD (Lec A)

PS5S "Static Measurement of Liquids"

RS12 "Static Direct Mass Measurement of Quantities of Liquids"

1st Pre-Draft IR received from RS - 12/27/89
Comments due to RS - 7/1/90

PS6 "Measurement of Gas"

RS4 "Measurement of Hydrocarbon Gases Distributed by Pipe-Line"

2nd Pre-Draft IR circulated to NWG - 8/8/89
Comments due to RS - 9/15/89; delay requested.
Comments received from AGA & API, 10/3/89; sent 10/10/89

PS7 "Measurement of Mass"

RS2 "General Problems. Electronic Devices"

R74 comments for revision to IWG - 7/31/89
Response from IWG due - 11/1/89
Responses received: CECIP, U.K., Switzerland, Finland, Australia, Netherlands, Belgium, Canada, Sweden & Hungary
NWG Meeting - 1/17/90, Scottsdale, AZ
Ballot to IWG - 2/2/90
IWG Meeting - 7/16-19/90, NIST, Gaithersburg, MD

RS4 "Non-Automatic Weighing Instruments"

R76 comments of IWG on proposed revisions due RS - 5/31/89. Sent.
R76 Revision to be circulated by RS - 10/31/89 (received 12/10/89); circulated to USNWG.
R76 Revision comments of IWG due to RS - 1/20/90 (U.S., 3/10/90)
NWG Meeting - 2/27 - 3/1/90 (Tu-Th) NIST, Gaithersburg, MD
R76 Collated comments and responses of RS - (received 4/8/90); circulated 4/9/90 to U.S. delegation to IWG meeting.
Weighing Seminar - 5/15-18/90, PTB, Braunschweig. (Tu-Fr)
IWG Meeting - 5/21-23/90, PTB, Braunschweig. (M-W)

Specifications and Tolerances Committee

NWG Meeting 12/5-7/90, NIST, Gaithersburg, to develop comments on 3rd Pre-Draft Revision of R76
IWG Meeting, 1/91, PTB, Braunschweig, to discuss 3rd Pre-Draft revision of R76

RS5 "Automatic Weighing Instruments"

1st Draft IR "Hoppers" circulated to PS & NWG for vote - 11/1/89

vote: Yes - 10, No - 0, Comments - 5. (Members - 11)

Edited version sent to RS - 1/5/90

1st Draft IR "RR Track" circulated to PS & NWG for vote - 11/1/89

Vote: Yes - 7, No - 2 (U.S., USSR,) Abs - 1 (Austria).

3rd Pre-Draft Revision R50 "Belt Weighers" - received 11/7/89, circulated to NWG 11/20/89

Comments due to RS - 2/19/90. Sent.

1st Pre-Draft Revision R61 "Gravity Filling Machines" - 9/30/89 (due from RS)

Actually received - 1/5/90; comments due RS - 3/23/90

1st Pre-Draft proposed IR "Catchweighers" - received 4/2/90.

NWG Meeting Beltweighers & Gravity Filling Machines - 1/18-19/90, Scottsdale, AZ

IWG Meeting - 5/7-11/90, NWML, U.K. (M-F)

NWG Meeting - 3/91, NIST, Gaithersburg, MD, to review succeeding Draft Documents on Belt Weighers, Catchweighers, etc.

IWG Meeting - 5/91, NWML, U.K. - to discuss succeeding Draft Documents

RS8 "Load Cells"

Revised R60 submitted to CIML for vote. Results: 30 yes, 1 no (FRG), with comments from 6 Countries, Australia, Japan, France, Norway, FRG, Finland & CECIP

RS response to comments sent - 12/1/89.

Test procedures and report forms for certificate system.

Revised R60 to be voted on by CIML at meeting in Paris, 9/91.

PS8 "Weights"

Combined Document received from Belgium - 10/10/89

Circulated to NWG - 10/11/89

Comments due to RS - 12/31/89

Comments sent 12/21/89

Revised Combined Document received from Belgium 6/20/90 and circulated to NWG for comment 6/22/90.

IWG Meeting - Combined Document on Weights - NIST 7/19/90 (Th).

David Watson, City of Fort Worth, Texas, Chairman

Charles Carroll, Massachusetts

Ray Helmick, Arizona

Jack Jeffries, Florida

James Truex, Ohio

Henry Oppermann, NIST, Technical Advisor

Specifications and Tolerances Committee

Report of the Committee on Education, Administration, and Consumer Affairs

G.W. Diggs, Chairman
Supervisor, Weights and Measures
State of Virginia

REFERENCE KEY NO.

400 Introduction

This is the Final Report of the Committee on Education, Administration, and Consumer Affairs for the 75th Annual Meeting of the National Conference on Weights and Measures. The Report consists of the Interim Report offered in the Conference "Program and Committee Reports" as amended by the Addendum Sheets issued during the Annual Meeting.

Table A identifies all of the items contained in the Report by Reference Key Number, Item Title, and Page Number. Item 402-7 (identified in the table by the suffix "V") was the Committee's only voting item. It was adopted by a separate vote of the membership as follows: House of State Representatives - 44 yea, 0 nay ; House of Delegates - 64 yea, 0 nay. Item 402-8, which is marked with a "W," was withdrawn. All other items, which are marked with an "I" after the Reference Key No., were informational and required no formal action by the membership. The membership adopted the report in its entirety as follows: House of State Representatives - 44 yea, 0 nay; House of Delegates - 62 yea, 0 nay.

Table A
Reference Key Items and Index

Reference Key No.		Title of Item	Page
401	I	Regional Weights and Measures Activities	178
402		National Training Program (NTP)	178
402-1	I	NTP Status Report	178
402-2	I	Certification Program Implementation	181
402-3	I	Registry Summary	181
402-4	I	Module Revisions	181
402-5	I	Training for Trainers	183
402-6	I	NCWM Training Needs Survey	183
402-7	V	Awarding of Continuing Education Units to Associate and Advisory Members	184
402-8	W	Training Award	184
402-9	I	Scale Tolerances	184
402-10	I	Certification of NTP Instructors	184
402-11	I	Identification of Supplemental Visual Aids Used with NTP Modules	185
402-12	I	Development of Policy on Review of Comments on Published Modules	185
402-13	I	Awarding of NTP Certificates	185
403	I	Review of Recommendations of the Task Force on Fraud	185
404	I	Review of NTP Production Schedule/Planning	186

In addition, the Report contains four appendices that are related to specific Reference Key Numbers as follows:

Table B
Appendices

App.	Title	Reference Key No.	Page
A.	NTP Certification Summary	402-2	187
B.	NTP Registry Summary of Activity	402-3	191
C.	Excerpts From: The NCWM Training Needs Survey Summary of Responses	402-6	197
D.	Outlines of Parts I and II of Module 23	404	205

Details of All Items
(in order of Reference Key Number)

401 I Regional Weights and Measures Activities

The Committee reviewed and discussed the following:

1. The final report of the Education and Consumer Affairs Committee to the 32nd Annual Technical Conference of the Western Weights and Measures Association (August 1989).
2. The final report of the Education Committee to the 44th Annual Conference of the Southern Weights and Measures Association (October 1989).
3. A letter from Bill Slamon, Chairman of the Northeastern Weights and Measures Association (NEWMA), on issues proposed at NEWMA's Interim Meeting for inclusion on the Education Committee's agenda.
4. The final report of the Committee on Education, Administration, and Consumer Affairs to the 18th Annual Conference of the Northeastern Weights and Measures Association (May 1990).

The Committee thanks the regional weights and measures associations for their input. Items that were raised by these groups prior to the 1990 Interim Meeting are covered in separate items in this report. Two new proposals included in the NEWMA report will be discussed at the Committee's 1991 Interim Meeting.

402 National Training Program (NTP)

402-1 I NTP Status Report

The status of the National Institute of Standards and Technology (NIST) grants to the NCWM as of June 30, 1990, was as follows:

Grant 1 - NB83NAHA4003

Net outlays to date:	\$472,231.66
Total unliquidated obligations:	3,500.00
(money committed to contractors)	
Total outlays & unliquidated obligations:	475,731.66
Total grant funds authorized:	515,189.00
Unobligated balance of funds:	39,457.34
(money available for future module development)	

Grant 2 - 70NANB8H0869

Net outlays to date:	\$ 31,868.13
Total unliquidated obligations:	----
(money committed to contractors)	
Total outlays & unliquidated obligations:	31,868.13
Total grant funds authorized:	180,000.00
Unobligated balance of funds:	148,131.87
(money available for future module development)	

Total funds available for future module development (grants 1 & 2):	\$187,589.21
---	--------------

In January 1990, the NCWM requested the third and final \$60,000 increase in Grant 2 from NIST. David Edgerly, Deputy Director of Technology Services, announced at the Interim Meeting that NIST had approved this request. This brings the total funds available under Grant 2 to \$180,000 and the total funds allocated by NIST for the development of training modules to \$695,189. NIST's continued generous support of the NCWM's National Training Program is greatly appreciated by the Committee.

The status of all training modules under development as of June 30, 1990, is given in Table C.

Table C
Training Module Status Report
(As of 6/30/90)

<u>Module No.</u>	<u>Subject</u>	<u>Status</u>
1	Mechanical Computing Scales	Project completed.
2	Electronic Computing Scales	Project completed.
4	Medium-Capacity Scales	Project completed.
5	Vehicle and Axle-Load Scales	Project completed.
6	Monorail Scales	Project completed.
7	Livestock and Animal Scales	Project completed.
8	Retail Motor-Fuel Dispensers	Project completed.
10	Package Checking	Project completed.
13	Hopper Scales	The working group is developing a new draft of the module.
19	Loading-Rack Meters	The contractor delivered the final version of the module. Copies will be mailed to the States in summer 1990.
20	Vehicle-Tank Meters	Project completed.
21	LPG Liquid Meters	Project completed.
22	Commodity Regulations	Project completed.
23	Weights and Measures Admin.	The Education Committee met in March 1990 to develop an outline of this module. Plans are being made to assign topics listed in the outline to volunteer individuals and groups for development.
24	Introduction to Handbook 44	Project completed.
27	Electronic Weighing and Measuring Systems	Project completed.

402-2 I Certification Program Implementation

As of June 30, 1990, the following 52 jurisdictions had signed Letters of Agreement with the NCWM and had been accepted as participants in the NTP Certification Program:

Alabama	Kentucky	Ohio
Alaska	Louisiana	Oklahoma
Arizona	Maine	Oregon
Arkansas	Maryland	Pennsylvania
California	Massachusetts	Puerto Rico
Colorado	Michigan	South Carolina
Connecticut	Minnesota	South Dakota
Delaware	Mississippi	Tennessee
District of Columbia	Missouri	Texas
Florida	Montana	Utah
Georgia	Nebraska	Vermont
Hawaii	Nevada	Virginia
Idaho	New Hampshire	Virgin Islands
Illinois	New Jersey	Washington
Indiana	New Mexico	West Virginia
Iowa	New York	Wisconsin
Kansas	North Carolina	Wyoming
	North Dakota	

Information summarizing participation in the NTP Certification Program is provided in Appendix A.

402-3 I Registry Summary

A summary of information in the NTP Registry as of June 30, 1990, is found in Appendix B. The Registry serves as a permanent record of NCWM courses successfully completed and Continuing Education Units (CEUs) earned under the NTP.

402-4 I Module Revisions

The revision status of all published NCWM training modules as of June 30, 1990, is shown in Table D. The Education Committee and the NIST Office of Weights and Measures (OWM) are dedicated to maintaining the usefulness of the modules by keeping them up to date through regular revisions.

OWM, which provides administrative and technical support for module revisions, has put a great deal of effort into the revision process and, as indicated in Table D, has made excellent progress despite the fact that major Handbook changes adopted by the Conference membership over the past several years have unavoidably delayed several important revisions and have resulted in a whole series of modules needing of revision at the same time. An example is the major restructuring of the Liquid-Measuring Devices Code in Handbook 44 in 1989 that resulted in extensive wording and numbering changes affecting the modules based on that code. Another example is the changes to the tolerances in the Scales Code of Handbook 44 that were adopted at the 75th NCWM. Consideration of these changes delayed publication of the revision of Module 2, and now their adoption will necessitate major revisions to all six of the published scales modules. The Education Committee and OWM are planning how to proceed now that the tolerances have been changed (see Item 402-9). OWM has been advocating a 2-year revision cycle for the major handbooks adopted by the Conference, partly to allow more time for module revisions.

Table D
Module Revision Status
 (As of 6/30/90)

<u>Module</u>	<u>Date of Pub</u>	<u>Date of Last Rev</u>	<u>Rev Stat*</u>	<u>Comments</u>
27	1/28/85	10/86	N	
1	11/20/85	11/86	P	This module will be affected by proposed changes to the tolerances in the Scales Code of Handbook 44.
10	11/29/85		U	This module is currently being revised by OWM staff. The revision is scheduled for completion in September 1990.
2	2/26/86	9/89	P	This module will be affected by proposed changes to the tolerances in the Scales Code of Handbook 44.
8	7/14/86		U	This module is being revised by a contractor. The scheduled completion date is August 1990.
5	10/17/86		U	The Committee will be issuing a contract to complete the revision of this module.
20	10/31/86		N	
6	4/3/87		P	This module will be affected by the proposed tolerance changes in the Scales Code.
7	5/27/87		P	This module will be affected by the proposed tolerance changes in the Scales Code.
21	8/5/87		N	
4	6/22/88		P	This module will be affected by the proposed tolerance changes in the Scales Code.
24	5/18/89		U	This module is being revised to be consistent with the 1990 edition of Handbook 44. The projected completion date for the revision is August 1990.

*Key to module revision status abbreviations: N = No revision planned in 1990, U = Revision is underway, P = Partial revision is planned for 1990 if NCWM members approve the changes to the tolerances in the Scales Code of Handbook 44 that are being proposed.

OWM has also put a lot of effort into improving the efficiency of the revision process. Revisions have been somewhat complicated by the fact that development of the NCWM training modules was begun long before computer technology had stabilized to the point that the NCWM could select the best computer hardware and software for the modules. Consequently, many modules were developed in formats that were not completely compatible with today's equipment and software. Over the past year, OWM has used in-house staff and outside contractors to convert modules to a standard format so that they can be revised more quickly and easily and so that changes to the handbooks can be readily incorporated in the modules. In its joint meeting with the NCWM Executive Committee at the Interim Meetings, the Education Committee requested that the Conference make funds available in 1990/1991 to facilitate the rapid completion of this conversion process.

In an effort to ensure that all suggested changes to the modules are given full consideration and that appropriate action is taken on them as quickly as practical, the Education Committee is taking steps to formalize the review of module comments (see item 402-12). All members of the Conference can help speed the revision process and improve the modules by providing feedback on them. Both weights and measures officials and industry members who teach the modules and must update them for presentation to a class could help the NCWM by sending copies of their marked modules to the Committee's Technical Advisor.

402-5 I Training for Trainers

In 1989, the Committee purchased a comprehensive videotape program on Training the Trainer using \$10,000 that the Executive Committee had allocated specifically for training trainers. This program, consisting of 14 1/2-hour tapes and accompanying student work books, is now available for loan to NCWM members for use in in-house training programs. Each State was sent a letter announcing the availability of the program and a preview tape of the program. In 1990, the Committee also made a special mailing to county and city weights and measures groups to describe the program and provide reservation forms.

At the Interim Meeting, possible uses for a second \$10,000 allocation made by the Executive Committee for training trainers were discussed. The Education Committee recommended that funds up to \$2,500 be made available to any regional weights and measures association planning to sponsor a train-the-trainer course. The funds could be used to pay the expenses of an instructor for the course, but not to pay travel costs of the participants. After the Interim Meeting, detailed information on how to obtain these funds was sent to each regional group.

402-6 I NCWM Training Needs Survey

The Committee would like to thank everyone who responded to the NCWM's Training Needs Survey. The information obtained from the survey will be useful in planning future training. Excerpts from a summary of the responses to the survey are provided in Appendix C.

402-7 V Awarding of Continuing Education Units to Associate and Advisory Members

(This item was adopted)

At the present time, only State and local weights and measures officials are eligible to receive Continuing Education Units (CEUs) for successfully completing NCWM training module courses. The rules for awarding CEUs require that permanent records be kept of all credits given. In order to meet this requirement, the NCWM uses The American College Testing Program (ACT) National Registry Service in Iowa City, Iowa. The ACT Registry Service currently charges \$3 to process each Registry entry. This fee is paid by the Conference. To date, the NCWM has spent over \$10,000 on the processing of Registry information (see Appendix B graph on NTP Registry Costs). It has been suggested that NCWM Associate and Advisory Members should also be able to receive credit for the NCWM courses they successfully complete. The Committee feels it would be appropriate to award CEUs to all individuals who successfully complete official NCWM module courses and, therefore, proposes the following:

That, beginning on August 1, 1990, the National Conference on Weights and Measures expand its Continuing Education Units program by awarding such units to any individual who successfully completes an NCWM training module course sponsored by a group participating in the NCWM's National Training Program (NTP) Certification Program; and that the NCWM pay the cost of recording the CEU information in the NTP Registry for all weights and measures officials and NCWM Associate and Advisory Members and permit individuals who are not weights and measures officials or members of the NCWM to receive CEUs and be entered in the NTP Registry if they pay the fee charged by the Registry.

402-8 W Training Award

In 1989, the Committee proposed the initiation of an NCWM Award for Training Achievements. (For details on this award, see item 402-8 in the Committee's Report to the 74th NCWM, 1989.) Due to lack of support for this item by the regional weights and measures associations, the Committee has decided to withdraw the item; however, other ways of collecting and disseminating information on innovative approaches to implementing the National Training Program will continue to be explored.

402-9 I Scale Tolerances

The changes to the tolerances for unmarked scales being considered by the Specifications and Tolerances Committee were reviewed by the Committee at the 1990 Interim Meeting. Because these changes were adopted by the Conference at the 75th NCWM, extensive revisions will have to be made to all of the existing NCWM training modules on scales. Due to the length of time it will take to revise all of the scales modules, the Committee is considering interim measures to permit the modules to be used during the revision period. One proposal is to publish updated EPOs and tolerance work sheets for each scale module before beginning a comprehensive revision of any one module. The Committee would appreciate other suggestions on how to deal with this problem.

402-10 I Certification of NTP Instructors

The Committee requests information from the regional weights and measures associations or from any group or individual on the pros and cons associated with establishing a certification program for individuals who teach NCWM training modules.

402-11 I Identification of Supplemental Visual Aids Used with NTP Modules

The Committee would like to compile a list of supplemental visual aids developed by State and local jurisdictions for use with NTP training modules so that this information can be shared. If you have materials that you are willing to share with other jurisdictions, please contact the Education Committee's Technical Advisor.

402-12 I Development of Policy on Review of Comments on Published Modules

In an effort to ensure careful consideration of all comments received on the training modules, the Committee is establishing the following policy on the submittal and handling of comments:

1. All proposed changes to a module that are of a technical nature must be submitted in writing.
2. Copies of all such proposals will be distributed to members of the Education Committee by the Committee's Technical Advisor.
3. The Technical Advisor will review the comments with technical experts as directed by the Committee.
4. A response will be sent to each individual who submits comments even if an issue cannot be addressed immediately.
5. Issues involving the interpretation of NIST Handbooks adopted by the NCWM will be referred to the appropriate NCWM Standing Committee for an official response.

402-13 I Awarding of NTP Certificates

The Committee received two separate requests regarding the awarding of NTP certificates. The first request was that Associate Members who successfully complete NTP training modules be given some type of certificate as a record of their achievement. At present, Associate Members are not eligible to receive either certification by the NCWM for completing classroom and field training or Continuing Education Units (see item 402-7 for proposed change in the CEU policy); consequently, they have not received any documentation from the NCWM to indicate that they have successfully completed an NCWM course. The Committee agrees that such documentation should be provided and therefore plans to give certificates of completion to Associate Members who successfully complete training sponsored by participants in the NCWM's NTP Certification Program.

The second request was that certificates of completion be given to all weights and measures officials who successfully complete an NCWM module training course for which Conference certification is not available, for example, Module 22, Commodity Regulations; Module 24, Introduction to NIST Handbook 44; and Module 27, Introduction to Electronic Weighing and Measuring Systems. The Committee has developed a Certificate of Training that can be used for both of the purposes mentioned above. Copies will now be provided upon request for associate members taking any NCWM module or for weights and measures officials taking Module 22, 24, or 27.

403 I Review of Recommendations of the Task Force on Fraud

This is a carryover item from last year. Recommendations of the NCWM Task Force on Fraud that were directed to the Education Committee were discussed. These recommendations included the following:

- Develop a uniform definition of fraudulent activities,
- Develop a uniform method of classifying types of fraudulent activities,
- Establish a mechanism by which information on fraudulent activities could be collected and made available at the national level.

Because of limited time and resources available to undertake a project such as this at the present time, the Committee is postponing action on this item.

404 I Review of NTP Production Schedule/Planning

Due to the continuing interest shown by Conference members in the development of a training module on Weights and Measures Administration, the Committee met in March 1990 to develop an expanded outline of the contents of the module (see Appendix D). The Committee is asking for volunteers to write sections of the module. Anyone who would like to volunteer should contact the Committee's Technical Advisor.

G. W. Diggs, Virginia, Chairman

M. Gray, Florida

C. Greene, New Mexico

R. Kalentkowski, Connecticut


S. Malone, Nebraska

J. Koenig, NIST, Technical Advisor

**Committee on Education, Administration, and
Consumer Affairs**

Appendix A

States that have signed Letters of Agreement To participate in the NTP Certification Program




Certification Summary

As of June 30, 1990

State	Total No. of Certif.	Total No. of People	Modules								
			<u>1</u>	<u>2</u>	<u>4</u>	<u>5</u>	<u>7</u>	<u>8</u>	<u>10</u>	<u>20</u>	<u>21</u>
AL	35	18		15	12		4	4			
AK	10	10						10			
AZ	28	28		28							
AR	121	38	20	20		8	4	37	12	17	3
CO	7	7					7				
CT	56	22		15	19	2			15	3	2
DC	3	3						3			
FL	32	22	6	8	2	4			12		
GA	29	24				8	4	17			
ID	9	9						9			
IL	17	17		8		9					
IN	30	30				30					
KS	21	9	7	7		4		1	2		
LA	1	1							1		
MD	28	28						28			
MI	42	14				9	12			14	7
MN	15	15						15			
MO	24	23						5	19		
NE	24	12		2				12	10		
NH	32	8	6	5	5	2		6		8	
NM	8	8		1				7			
NC	19	19							19		
ND	3	3						3			
OH	75	46		26		5		35	5		4
OR	54	16	16	15		6		10	6		1
P&S	14	14					14				
PA	11	11							11		
PR	80	47		32				33	15		
SD	27	12			7	12		7	1		
TN	41	30				5	6	30			
UT	72	16	15	15	2	11	4	12	12		1
VA	2	2									2
WA	21	16		5				16			
WI	4	4									4
<u>34</u>	<u>995</u>	<u>582</u>	<u>70</u>	<u>202</u>	<u>47</u>	<u>115</u>	<u>55</u>	<u>300</u>	<u>140</u>	<u>42</u>	<u>24</u>

Module Certification (Percentage of Total)



Data as of 6/30/90

Appendix B

NATIONAL TRAINING PROGRAM REGISTRY SUMMARY OF ACTIVITY (As of June 30, 1990)

Courses Listed in Registry:

Module 1, Retail Computing Scales - Mechanical
 Module 2, Retail Computing Scales - Electronic
 Module 4, Medium-Capacity Scales
 Module 5, Vehicle and Axle-Load Scales
 Module 6, Meat Beams and Monorail Scales
 Module 7, Livestock and Animal Scales
 Module 8, Retail Motor-Fuel Dispensers and Consoles
 Module 10, Checking the Net Contents of Packaged Goods
 Module 20, Vehicle-Tank Meters
 Module 21, LPG Liquid-Measuring Devices
 Module 22, Commodity Regulations
 Module 24, Introduction to NIST Handbook 44
 Module 27, Introduction to Electronic Weighing the Measuring Systems


INDIVIDUALS TRAINED - BY MODULE

State	Module No													Totals
	1	2	4	5	6	7	8	10	20	21	22	24	27	
AL		15	12	4		4	14						26	75
AK				1			10	8						19
AZ		27				6	17			25				75
AR	20	20		8		4	37	12	17	3				121
CA						1								1
CO						9	1	1						11
CT		22	20	2			16	18	6	2	26			112
DE			1											1
DC	4	4					3							11
FG													13	13
FL	13	22	14	13		10	24	19	8				41	164
GA			11	8		4	17						7	47
HI								14					4	18
ID		9		10			10			10			8	47
IL		8	1	9			7	2						27
IN		43	46	41			56						48	234
LA							4				1			5
KS	9	10	14	5			17	25	2			3	8	93
KY	16	8	1	5			19							49
LA								1						1
ME			3	9			8			2			4	26
MD							28					6		34
MA		23	4	5			14	3	31	1	2		12	95
MI		50		13		19	2	29	22	12		18	53	218
MN							12				1			13
MS			2	3		3								8
MO			13				32	26				60	22	153
MT			5				6			1			8	20
NE		17	4	13			15	10			15	16	20	110
NH	6	5	7	2			6		8				6	40
NJ		21	21				108		26				147	323
NM		12				13	15	25		2				67


Education Committee

State	Module No													Totals
	1	2	4	5	6	7	8	10	20	21	22	24	27	
NY		74						92		9				175
NC								19						19
ND							3						12	15
OH		40		13	4	8	42	14		9	2	29	58	219
OK			2				5	22					2	31
OR	18	17		8			12	16		16		17	16	120
PS				2		14							3	19
PA	34	69	51				56	39		1	13		82	345
PR		32					33	15				27		107
RI		1		1					1					3
SC		25				2	28							55
SD			7	12			7	10			10		10	56
TN		27		6		6	32						5	76
TX						8	24			4		5		41
UT	16	15		11		4	12	13		1			16	88
VT	5		3	2			7	1			2		5	25
VA			24	16		2	9	38	25	4		5	43	166
WA	13	8		16			16			1		6	16	76
WV						3								3
WI	56	53		13			28		26	5			65	246
WY			11				16			10			3	40
Total	210	677	277	251	4	120	811	489	172	118	72	192	763	4156

Growth of NTP Registry (Annual and Cumulative Data)




NTP Registry Costs* (Annual and Cumulative Data)



Data as of 6/30/90

Year

*Registry fee is \$3 per entry



Data as of 6/30/90

**Continuing Education Units (CEUs) Awarded
By the National Conference on Weights and Measures
(As of June 30, 1990)**

Module	CEUs*	No. of Partic.	1985 Total	1986 Total	1987 Total	1988 Total	1989 Totals	1990 Totals	Grand Totals
1	3.1	210	-	306.9	77.5	117.8	99.2	49.6	651.0
2	3.1**	677	-	65.1	857.9	759.5	173.6	161.2	2017.3
4	3.1	277	-	-	-	492.9	198.4	167.4	858.7
5	3.1	251	-	-	96.1	133.3	381.3	167.4	778.1
6	3.1	4	-	-	12.4	-	-	-	12.4
7	3.1	120	-	-	12.4	-	248.0	111.6	372.0
8	2.8	811	-	288.4	856.8	260.4	739.2	126.0	2270.8
10	2.8	489	75.6	372.4	302.4	128.8	417.2	72.8	1369.2
20	2.8	172	-	-	156.8	109.2	109.2	106.4	481.6
21	3.5	118	-	-	105.0	129.5	147.0	31.5	413.0
22	2.45	72	-	-	-	-	-	176.4	176.4
24	1.5	192	-	-	-	-	15.0	273.0	288.0
27	1.1	763	155.1	402.6	165.0	66.0	36.3	14.3	839.3
Totals		4156	230.7	1435.4	2642.3	2197.4	2564.4	1457.6	10527.8

*One CEU is equivalent to 10 contact hours of participation in an organized continuing education experience under responsible sponsorship, capable direction, and qualified instruction.

**One Module 2 class with 74 participants was given only 2.0 CEU's.

Appendix C

Excerpts From:

THE NCWM TRAINING NEEDS SURVEY

Summary of Responses

January 3, 1990

In mid-September, 1989, a Training Needs Survey was sent to 775 heads of State, county, and city weights and measures agencies along with a request for completion and return to NCWM. A total of 89 surveys has been received from 39 State, 28 county, and 22 city officials. A summary of some of the responses to the survey is given below.

1. Provide the following demographic information regarding your agency:

Number of personnel

	<u>State/County/City</u>	<u>State</u>	<u>County</u>	<u>City</u>
Total	3,051	2,072	151	828
Range	1 to 750	5 to 580	1 to 53	1 to 750
Average	34	53	5	38

Number of weights and measures personnel (including petroleum quality/quantity)

	<u>State/County/City</u>	<u>State</u>	<u>County</u>	<u>City</u>
Total	1,381	1,189	127	65
Range	<1 to 120	<1 to 120	1 to 44	1 to 23
Average	16	30	5	3

What is your annual training budget?

	<u>State/County/City</u>	<u>State</u>	<u>County</u>	<u>City</u>
Total	\$182,046.00	\$129,495.00	\$10,751.00	\$41,800.00
Range	\$0.00-\$31,500.00	\$0.00-\$31,500.00	\$0.00-\$2,500.00	0.00-\$17,000.00
Average	\$2,045.00	\$3,320.00	\$384.00	\$ 1,900.00

When does your fiscal year commence?

	<u>01/01</u>	<u>07/01</u>	<u>10/01</u>	<u>Other</u>
State	0	35	3	1
County	19	8	0	0
City	4	14	1	2

2. In which NTP modules have your personnel received training (city/county officials only)?

	<u>County</u>	<u>City</u>	<u>Total</u>		<u>County</u>	<u>City</u>	<u>Total</u>
Module 2:	58	49	107	Module 20:	10	12	22
Module 1:	51	42	93	Module 4:	10	8	18
Module 8:	62	26	88	Module 24:	11	7	18
Module 10:	48	9	57	Module 21:	4	1	5
Module 27:	14	41	55	Module 6:	1	0	1
Module 5:	12	12	24	Module 7:	1	0	1

3. In which NTP modules will you want to train your personnel within the next three years?

	<u>State</u>	<u>County</u>	<u>City</u>	<u>Total</u>		<u>State</u>	<u>County</u>	<u>City</u>	<u>Total</u>
Module 24:	530	76	56	662	Module 1:	187	33	10	230
Module 2:	481	46	14	541	Module 5:	113	60	5	178
Module 4:	413	63	16	492	Module 7:	125	5	0	130
Module 10:	365	35	53	453	Module 21:	57	64	3	124
Module 8:	401	31	12	444	Module 22:	85	0	2	87
Module 20:	337	56	5	398	Module 13:	20	1	0	21
Module 27:	168	76	13	257	Module 19:	15	0	2	17
Module 6:	190	43	0	233					

4. Which of the modules under development will be of interest when available (shown in order of interest):

Module 22: Commodity Regulations

	<u>Interested</u>	<u>No Interest</u>	<u>No Response</u>
State	31	6	2
County	24	3	1
City	14	6	2
Total	69	18	6

Module 13: Hopper Scales

	<u>Interested</u>	<u>No Interest</u>	<u>No Response</u>
State	32	5	2
County	15	5	8
City	5	5	12
Total	52	15	22

Module 19: Loading-Rack Meters

	<u>Interested</u>	<u>No Interest</u>	<u>No Response</u>
State	29	10	0
County	7	19	2
City	6	14	2
Total	42	43	4

5. In what subject areas do you need weights and measures training that is not provided by current or planned training modules?

	<u>State</u>	<u>County</u>	<u>City</u>	<u>Total</u>
Weights & measures administration	4	2	4	10
Taximeters and mileage inspections	3	3	2	8
Investigative techniques, evidence collection	4	2		6
Weights & measures violations, legal aspects, fines, court procedures, case studies	4	1		5
Grain moisture meters	4			4
Petroleum quality testing/sampling	2	1		3
Safety procedures	1	1	1	3
Electric, vapor, and water meter testing		2		2
Interpersonal relationships			2	2
Introduction to weights & measures		2		2
Linear measuring devices		1	1	2
Test equipment		1	1	2
Timing devices	1	1		2
UPC scanning	2			2
Weights & measures communications	1	1		2
Belt conveyor scales	1			1
Bulk meters	1			1
Combined cash register, UPC pricing, open pricing		1		1
Developing professionalism			1	1
Handbook 44 update		1		1
Metric measurement	1			1
Metrology		1		1
Milk tanks	1			1
Railroad track scales		1		1
Retail motor fuel dispensing		1		1
Train-the-trainer	1			1

7. Although training modules have been designed for beginning inspectors, most jurisdictions have found it beneficial to deliver modules to their entire staff. Suggestions have been made to the Conference to develop more advanced modules for more experienced inspectors and develop short courses that update inspectors on changes, for example, to Handbook 44, that impact the testing and inspection of a given type of device or class of devices. In light of your near-term (next 3 years) training needs, how would you rank the following (1=highest priority). (The responses have been listed in the order of how many ranked the item number 1 priority.)

The NCWM should complete development of the modules next on the list of priorities (namely Weights and Measures Administration and Communications) before tackling other new tasks (1=highest priority):

<u>State</u>	Total Responses: 39	Ranking 1:	26
		Ranking 2:	5
		Ranking 3:	8
<u>County</u>	Total Responses: 18	Ranking 1:	11
		Ranking 2:	3
		Ranking 3:	4
<u>City</u>	Total Responses: 15	Ranking 1:	5
		Ranking 2:	2
		Ranking 3:	3

The NCWM should develop short courses, 1/2 to 2-day duration (1=highest priority):

<u>State</u>	Total Responses: 32	Ranking 1:	12
		Ranking 2:	17
		Ranking 3:	2
		Ranking 5:	1
<u>County</u>	Total Responses: 16	Ranking 1:	5
		Ranking 2:	6
		Ranking 3:	5
<u>City</u>	Total Responses: 12	Ranking 1:	6
		Ranking 2:	5
		Ranking 3:	1

The NCWM should develop advanced modules in selected areas:

<u>State</u>	Total Responses: 29	Ranking 1:	4
		Ranking 2:	10
		Ranking 3:	13
		Ranking 5:	1
		Ranking 10:	1
<u>County</u>	Total Responses: 16	Ranking 1:	6
		Ranking 2:	4
		Ranking 3:	5
		Ranking 8:	1
<u>City</u>	Total Responses: 8	Ranking 1:	3
		Ranking 2:	2
		Ranking 3:	2
		Ranking 6:	1
		Ranking 10:	1

8. Are you able to meet all of your current training needs with in-house training staff?

<u>State</u>	Yes 12	No 26	No response 1
<u>County</u>	Yes 3	No 23	No response 2
<u>City</u>	Yes 5	No 17	No response 0
Total	Yes 19	No 66	No response 3

9. If no, do you get help from outside organizations?

Note: Contradictory information is contained in this response (i.e., some respondents indicated "Yes" they are able to meet current training needs with in-house staff but do receive help from other organizations).

<u>State</u>	Yes 27	No 7	No response 6
<u>County</u>	Yes 24	No 2	No response 2
<u>City</u>	Yes 15	No 5	No response 2
Total	Yes 66	No 14	No response 10

<u>State</u>					
OWM	Yes 23	No 7	No response 9	Man-hours per year	912
IWM	Yes 4	No 9	No response 25	Man-hours per year	100
Other	Yes 10	No 17	No response 11	Man-hours per year	-

<u>County</u>					
OWM	Yes 9	No 10	No response 9	Man-hours per year	277
IWM	Yes 4	No 13	No response 11	Man-hours per year	80
Other	Yes 18	No 5	No response 5	Man-hours per year	300

<u>City</u>					
OWM	Yes 9	No 10	No response 3	Man-hours per year	320
IWM	Yes 4	No 15	No response 3	Man-hours per year	180
Other	Yes 11	No 8	No response 3	Man-hours per year	80

<u>Total</u>					
OWM	Yes 41	No 27	No response 21	Man-hours per year	1,509
IWM	Yes 12	No 37	No response 18	Man-hours per year	360
Other	Yes 39	No 30	No response 18	Man-hours per year	380

"Other" training sources include:

USDA Packers and Stockyards
 Private industry
 Other States
 State or regional associations
 Other departments within the agency
 State or county weights and measures jurisdictions

10. Is training from outside organizations sufficient?

<u>State</u>	Yes 17	No 12	No response 10
<u>County</u>	Yes 13	No 12	No response 3
<u>City</u>	Yes 11	No 8	No response 3
Total	Yes 41	No 32	No response 16

12. I would like to see the NCWM sponsor/provide training packages which would include providing the trainer (not just furnish modules). There may be a cost associated.

<u>State</u>	Yes 31	No 4	No Response 4
<u>County</u>	Yes 15	No 9	No Response 4
<u>City</u>	Yes 13	No 4	No Response 5
Total	Yes 59	No 17	No Response 13

13. A. If the Conference arranged for the presentation of a Train-the-Trainer course at an acceptable location, would you send any of your trainers?

<u>State</u>	Yes 34	No 4	No Response 1
<u>County</u>	Yes 13	No 5	No Response 10
<u>City</u>	Yes 9	No 6	No Response 7
Total	Yes 56	No 15	No Response 18

E. Location - For each of the locations listed below, please indicate "Yes" if you could send a trainer for training or "No" if you could not:

Within your region:

	<u>Yes</u>	<u>No</u>	<u>No Response</u>
State	35	1	3
County	10	7	11
City	11	3	8

Within your State:

	<u>Yes</u>	<u>No</u>	<u>No Response</u>
State	30	2	7
County	16	1	11
City	10	5	7

At NIST in Gaithersburg, MD:

	<u>Yes</u>	<u>No</u>	<u>No Response</u>
State	21	11	7
County	2	16	10
City	3	9	10

At another location in the central United States:

	<u>Yes</u>	<u>No</u>	<u>No Response</u>
State	13	16	10
County	1	16	11
City	2	10	10

15. What weights and measures magazines, periodicals, and newsletters do you presently read on a regular basis?

The publications mentioned most frequently were:

<u>Publication</u>	<u>Number of Responses</u>
Weighing & Measurement Magazine	32
Weights & Measures Today Newsletter	21
Southern Weights & Measures Assn Newsletter	17
Western Weights & Measures Assn Newsletter	16
New York State W & M Assn Newsletter	16
Northeastern Wts & Measures Assn Newsletter	13
IWM Newsletter	11
NCWM Publications	10
NIST Publications	9
SMA's Newsletter	9
Massachusetts Wts & Measures Assn Newsletter	9



Appendix D - Outlines of Parts I and II of Module 23

Weights and Measures Administration

**Part I - An Introduction to Weights and Measures
For New Weights and Measures Officials**

I. Introduction

- A. Description of the purpose and significance of weights and measures activities
- B. Objectives of the module

II. Historical Background

- A. History of standards
- B. Hierarchy of standards
- C. History of weights and measures legislation

III. Weights and Measures in the United States

- A. Structure
- B. Description of weights and measures regulatory groups in the United States
 - 1. USDA
 - a. Packers and Stockyards
 - b. Federal Grain Inspection Service
 - 2. FDA
 - 3. FTC
 - 4. BATF
 - 5. EPA
- C. NIST
- D. NCWM
 - 1. Background and purpose
 - 2. Activities
 - a. Uniform laws and regulations
 - b. National Type Evaluation Program
 - c. National Training Program
 - d. Liaison with other groups
 - 3. Input to the NCWM
 - a. Regional and State Associations, local jurisdictions, NASDA, individuals
 - b. Industry
 - c. Consumers
 - d. Federal agencies
 - e. International (Canada, OIML)

IV. Legal Basis for Weights and Measures

- A. State laws and regulations
- B. Relationship between State law and uniform laws
- C. Local ordinances (counties and cities)
- D. Jurisdiction specific information
- E. Federal preemption

V. State and Local Weights and Measures Programs

- A. Organization - first model law identified three types of W&M organizations:
 - 1. State only
 - 2. State and some local groups under State control
 - 3. State and a number of local groups that are largely independent
- B. Funding
- C. Scope of operations - types of activities performed by W&M programs
- D. Jurisdiction specific information

VI. Role of the Weights and Measures Official

- A. Device inspection vs. process verification (e.g., checking gasoline pumps vs. checking packages)
- B. Fundamental considerations
 - 1. Regulatory actions (approval, rejection, condemnation)
 - 2. Penalties
 - 3. Documentation and records
 - 4. Chain of evidence
- C. Education/communication
 - 1. Public
 - 2. Industry
- D. Professionalism
 - 1. Attitude
 - 2. Training
 - 3. Appearance (of official and equipment)
 - 4. Safety
- E. Jurisdiction specific information

Weights and Measures Administration

Part II - Organization and Management of Weights and Measures Programs For Weights and Measures Supervisors and Administrators

I. Introduction

- A. Scope of Part II (who and what does it cover)
- B. Purpose and significance of weights and measures activities

II. Functions of a Weights and Measures Program

- A. Maintain traceability of State standards
 - 1. Test secondary standards annually
 - 2. Assist industry
- B. Device regulation
- C. Quantity control
- D. Adopt rules and regulations
 - 1. Labeling
 - 2. Method of sale
 - 3. Weighmaster
 - 4. NTEP
 - 5. Open dating
 - 6. Unit pricing
 - 7. Registration of W&M servicepersons and service agencies
 - 8. Motor fuel
- E. Conduct investigations
- F. Enforce laws and regulations
- G. Perform other functions assigned by law

III. Structure

- A. Types
 - 1. State only
 - 2. State and local
 - a. State supervised
 - b. Local independent
- B. Placement
 - 1. State
 - a. Department of Agriculture
 - b. Department of Commerce
 - c. Department of Labor
 - d. Department of Consumer Protection
 - e. Other
 - 2. Local
 - a. Department of Agriculture
 - b. Department of Consumer Protection
 - c. Permits and Inspections
 - d. Other
- C. Philosophy of Organization
 - 1. Organization by geographical areas or by specialty areas
 - 2. Sample organizational charts

IV. Metrology

- A. Introduction - What every Director should know.
 - 1. Components
 - a. Facility
 - b. Standards
 - c. Personnel
 - 2. Purpose
 - a. Support W&M field program
 - (1) relation to national standards
 - (2) effects of international trade
 - b. Support Industry with calibration services
- B. The State Standards Program from NIST
 - 1. Standards
 - 2. Measuring equipment
 - 3. Additional equipment purchased by State
- C. The Hierarchy of Standards
 - 1. Definitions
 - 2. Measurement accuracy and the Transfer Ratio
 - 3. The hierarchy
 - a. International Standards (BIML)
 - b. National Standards (NIST)
 - c. State Primary Standards
 - (1) calibration certificates
 - (2) proper usage as reference standards
 - (3) appropriate use as working standards
 - d. State Working Standards
 - e. Field Standards
 - f. Commercial devices
 - 4. General capabilities - relative accuracies
 - a. Mass
 - b. Volume
 - c. Length
 - d. Other measurements
- D. Training, Certification and the LAP Program
 - 1. Training
 - a. Basic Seminar
 - b. Intermediate Seminar
 - c. NCWM Metrology Workshops
 - d. Continuing Training through RMAP's
 - 2. Certification by measurement area
 - 3. The Laboratory Auditing Program (LAP)
- E. The Metrologist
 - 1. Function - job description
 - 2. Exercise discretion
 - a. Choice of appropriate test procedure
 - b. Choice of standard
 - c. Choice of test equipment
 - 3. Good Laboratory Practices
 - a. Follow standard operating procedure
 - b. Provide necessary documentation
- F. Quality Assurance (use Chap. 3 of HB 145)
 - 1. Quality Assurance
 - 2. Quality Control
 - 3. Quality Assessment

G. Regional Measurement Assurance Programs (RMAP's)

1. Description
2. Functions
 - a. Quality circle organizations
 - b. Training provided by NIST OWM
 - c. Round Robin testing

H. Conclusions and Summary

V. Program Planning

A. Program definition

1. Identify activities for which the program is responsible
2. Decide on the relative importance of each activity

B. Program philosophy

1. Device inspection vs. process control
2. Administrative compliance vs. judiciary compliance

C. Establishment of goals and objectives

1. Statistics/Demographics (define the scope of the work)
 - a. Number of devices to be checked
 - b. Number of servicepeople
 - c. Number of businesses conducting commercial weighing and measuring
 - d. Geographic distribution of population
2. Long range
3. Short range
4. Periodic reevaluation

D. Program Justification

1. Output measures
 - a. Number of devices inspected
 - b. Number of packages inspected
 - c. Reinspection rate
 - d. Compliance rate
 - e. Number of complaints
 - f. Judiciary actions
 - g. Other
2. Cost/benefit assessment
 - a. Tangible benefits
 - b. Intangible benefits

E. Establishment of policies and procedures to help achieve goals and objectives

F. Program evaluation

VI. Budgeting and Funding

A. Funding sources and alternatives

1. Fees, licenses, permits
2. General fund
3. Grants and contracts

B. Funding philosophy

1. Use of cash funds (limit to weights and measures use)
2. Total funding from general fund (pluses and minuses)
3. Fee systems (pluses and minuses)
4. Using the budget process to achieve program goals

C. Typical budget categories

1. Personnel
2. Operating expenses
 - a. Travel
 - b. Postage
 - c. Telephone
 - d. Repairs
 - e. Oil, gas
 - f. Vehicle rental

Education Committee

- g. Training
- 3. Equipment and facilities
- D. Assessment of personnel needs

VII. Legislation

- A. Law vs. regulation vs. policy
- B. Adoption by reference
- C. Interactions with the Legislature

VIII. Personnel

- A. Position descriptions (describe why they are needed)
 - 1. Job duties
 - 2. Qualifications
- B. Selection Process
 - 1. Recruiting
 - 2. Physical requirements
 - 3. Examinations
- C. Agency personnel policies
 - 1. Unions
 - 2. EEO/AA
- D. Performance evaluation - establish standards
- E. Administrative control
 - 1. Establish itineraries
 - 2. Require reports of activity
 - a. Number of miles driven
 - b. Number of devices checked
- F. Motivation (use of quality circles)

IX. Training

- A. Planning, organization, and scope of the training program
- B. Sources of training and information
 - 1. NCWM National Training Program
 - a. Modules
 - b. Trainers List
 - 2. Department/Agency
 - 3. State W&M Association
 - 4. Regional W&M Association
 - 5. NIST Office of Weights and Measures
 - 6. Institute of Weights and Measures
 - 7. Federal agencies
 - a. USDA
 - (1) P&S
 - (2) FGIS
 - (3) USDA Graduate School
- C. Scope of training
 - 1. Training for Trainers (NCWM tapes and other sources)
 - 2. Safety training

X. Safety

- A. Establish safety policy/coordinator

- B. Evaluation
 - 1. Data collection
 - a. Accident reports
 - b. Medical testing
 - 2. Data review
 - 3. Recommendations for change
 - C. Training sources
 - 1. National Safety Council
 - 2. Occupational Safety and Health Administration
 - D. Resource library
 - E. Equipment
- XI. Communications
- A. Internal (staff/management)
 - B. External
 - 1. Public relations
 - 2. Public education
 - 3. Publicity
 - 4. Education
 - a. Device owner
 - b. Packager
 - c. Service agency
 - 5. Methods and tools
 - 6. Interactions with other agencies
 - a. State
 - b. Federal
- XII. Obtaining Compliance
- A. Voluntary compliance
 - B. Adjudicatory Process
 - 1. Administrative procedures
 - 2. Penalty Assessment
 - 3. Criminal vs. civil penalties
 - 4. Notice of violation
 - 5. Rights of accused
 - 6. Appeals process
- XIII. Investigations
- A. Chain of evidence
 - B. Complaint handling
 - C. Investigations initiated by W&M office
 - D. Cooperation/coordination with local authorities
 - E. Undercover and out-of-hours investigations
 - F. Development of policies/procedures
 - G. Equipment
- XIV. Records Management
- A. Determine the type of information needed
 - B. Types of records
 - 1. Inspection reports
 - 2. Complaint logs
 - 3. Correspondence logs
 - 4. Personnel records
 - 5. Training records
 - 6. Business records
 - a. Expense accounts
 - b. Purchase orders
 - c. Attendance reports
 - d. Mileage reports

Education Committee

- e. Itineraries
 - 7. Subject reference files
 - 8. Safety records (accident reports)
 - 9. Certificates of Conformance (NTEP)
 - 10. Case files
 - 11. Laboratory records
- C. Data processing
 - 1. Manual
 - 2. Electronic
 - 3. Coordination and sharing of data
- D. Records retention policies
- E. Organization of records (e.g., by device type, by towns, by inspector, by jurisdiction)
- F. Analysis of data

XV. Equipment

- A. Adequacy of test equipment
 - 1. Handbook 44
 - 2. Handbook 133
 - 3. Handbook 105 series
- B. Maintenance of equipment
- C. Scheduling replacement of equipment

XVI. Professionalism

- A. Conflict of interest
- B. Setting an example for staff to follow

XVII. Reference Materials

- A. Publications
 - 1. OWM
 - 2. NCWM
 - 3. Other
- B. Safety

Report of the Committee on Liaison

Peggy H. Adams, Chairman
Chief Sealer, Bucks County
Pennsylvania Department of Consumer Protection

Reference

Key No.

500 Introduction

This is the final report of The Committee on Liaison for the 75th Annual Meeting of the National Conference on Weights and Measures. This report results from the Interim Report, the Addendum Sheets issued at the meeting, and the actions taken by the membership at the meeting.

Reference Key Numbers, Item Titles, and Page Numbers are identified in Table A. Voting items are identified in **boldface print**, as well as by the suffix "V." Information items are identified by the suffix "I." Withdrawn items are identified by the suffix "W."

(This report was adopted in its entirety by a hand vote of the membership.)

Table A
Reference Key Items and Index

Reference Key No.	Title of Item	Page
501	Federal Agency Activities	214
501-1 I	Federal Grain Inspection Service (FGIS)	214
501-2 I	Federal Role in Net Content Compliance: USDA	215
501-3 I	Federal Agency Interaction	215
502 I	Public Liaison	216
503 I	OIML Activities	218
504 I	OWM Status Report	218
505 I	Railroad Freight Car Stenciled Tare Weights	218
506 I	The 75th Annual Meeting of the NCWM	218

Table A (Continued)

Reference Key No.		Title of Item	Page
507	I	Liaison with Regional Associations	219
508	I	Energy Allocation	219
509	I	Weights and Measures Week	219
510	I	Computer Information Systems	219
511	I	Liaison with Other NCWM Organizations and Committees	220
512	I	Task Force on Safety	220

Details of All Items

501 Federal Agency Activities

501-1 I Federal Grain Inspection Service (FGIS)

Railroad Track Scale Testing

Mr. Richard Pforr, Chief Weighing and Equipment Branch, Field Management Division, FGIS, reported the following activities for 1989:

1. All master scales (13) in service were tested during the year and test results were submitted to the American Association of Railroads (AAR), State Weights and Measures, and the appropriate railroad. State Weights and Measures Officials generally attended when the tests were conducted.
2. The master scale removed from Martinsburg, West Virginia, is being installed at Barboursville, West Virginia.
3. Two testing circuits were completed, during which approximately 90 tests were conducted on official railroad track scales.
4. FGIS continued the tolerance testing of standards owned by local scale companies at the Master Scale Depot in Chicago on a request basis. Reports of tests were provided to the owner of the standards and the State of Illinois.
5. The "Belt Line" railroad, which owns the railroad yard where the FGIS Master Scale Depot is located, has informed FGIS that it is in receivership and is reorganizing. Only minor delays of test car movement are expected because of the reorganization.
6. The Oregon Public Utilities Commission (OPUC) and the Washington Public Utilities Commission (WPUC), which have been responsible for testing railroad track scales in those States, will transfer testing responsibility to the Weights and Measures Departments of those States in the near future. We anticipate no change in FGIS service provided to the Oregon master scale.

7. FGIS continues to operate this program at capacity. Requests have been received from a number of agencies to have a third car built. To date, these requests have not been seriously considered.

Grain Quality

Mr. David Funk and Mr. Richard Pierce with the Quality Assurance Research and Development (QARD) Branch, FGIS, Kansas City, Missouri, met with the Committee to discuss the work done by their branch.

QARD, a branch of FGIS that checks quality of official grain samples, moisture meters, and protein measurement of grain samples, wanted to make NCWM members aware of this program and the possibility that Weights and Measures may become involved in these areas.

Mr. Funk was asked to continue to keep the Committee aware of FGIS activities and how NCWM could help them.

501-2 I Federal Role in Net Content Compliance: USDA

The U.S. Department of Agriculture (USDA) published a proposal to change its net weight regulations, with a comment period that ended in May, 1989. The draft proposal, developed with close NCWM cooperation and support, seeks to adopt Handbooks 133 and 44 to provide mandatory procedures for Federal inspectors in net content compliance determinations. The adoption of these handbooks should enable Federal, State, and local weights and measures officials to strengthen enforcement and compliance. Work on the analysis of the comments by the Food Safety Inspection Service (FSIS) of USDA has been completed. A final rule has been reviewed by the agency and will soon be going to OMB for policy review. It is hoped that the final rule will be published by October, 1990.

A problem with the labeling of hamburgers was brought to the attention of the Committee. Some boxes of hamburgers do not have a net weight statement on them, but only a designation of "Spec. 40-4." This designation is intended to indicate that the box contains 40 quarter pound hamburgers. Examination revealed that only 9-1/2 pounds of product was in each box. The USDA reports that it permits the above labeling because its meat regulations do not require a total net weight declaration. In contrast, Federal poultry regulations do require a complete net weight statement. The Committee recommended to the Executive Committee that the NCWM petition USDA to change its regulation to require a complete net weight declaration by adopting the requirements in the poultry regulations as requirements in the meat regulations. The Executive Committee agreed with the recommendation from the Liaison Committee and a petition has been sent to USDA.

501-3 I Federal Agency Interaction

Office of Metric Programs

The Office of Metric Programs (OMP), U.S. Department of Commerce, reported that most Federal Government departments are implementing plans to comply with requirements of the Metric Conversion Act of 1975 as amended in the 1988 Trade Act. The Amendment requires Federal agencies to convert to metric when feasible by 1992.

The OMP urged NCWM to continue to focus on metric issues as part of a public awareness program. The office urged NCWM to take a stand on metrication in all weights and measures areas.

Mr. Jerry Underwood of the U.S. Dept. of Commerce Office of Metric Programs updated the Conference on the federal activities toward Federal procurement in metric by 1992.

Federal Trade Commission (FTC)

Mr. Bret Smart, representing the FTC, discussed the Conference's concern with metric labeling. The Fair Packaging and Labeling Act (FPLA) requires that packages have inch-pound net content statements. It permits the addition of metric statement, but not metric statements alone. In order for Federal agencies to change their regulations to permit metric only statements, Congress would have to change the FPLA. Mr. Smart indicated that FTC is not in a position to lobby Congress for a law change and suggested that members of the Conference might contact members

Liaison Committee

of Congress to gain interest in changing the Act.

U.S. Postal Service (USPS)

Mr. Theodore H. Yaffee, USPS, Program Manager, Postal Service Engineering Division, reported on recent USPS scale activities. 30,000 integrated retail terminals which can weigh and calculate the proper postage for any single piece of first, third, or fourth class mail weighing between 1/2 ounce and 70 pounds have been installed in post offices throughout the country. A total of 45,000 - 50,000 terminals will be installed nationwide by the time USPS finishes this project. The scales will be used in all offices that have 2 or more postal windows.

The 25-pound electronic bulk mail acceptance scales are being updated as computing scales which calculate the weight of a single piece when a known number of identical pieces are added. If a bundle is weighed, the scale will tell how many pieces are in the bundle.

Food and Drug Administration (FDA)

The FDA indicated that work on the Conference's early petition to change requirements for aerosol net weight labeling has not progressed due to the need for additional information. FDA requested the Conference to include an economic and environmental impact statement with its petition. The Liaison Committee has prepared these materials and submitted them to FDA for the Conference.

Ms. Janice Oliver, FDA, discussed issues of concern to the National Conference. The FDA has had four hearings on labeling issues around the country. The agency has completed its hearings and is reviewing the comments. FDA was not ready to give any policy position at this time, but will do so after analyzing comments. The Committee requested that FDA review the food and nutrition labeling bills which have been introduced in Congress concerning the possibility of preemption of State regulations. This issue may also affect Handbook 130.

The Fair Packaging and Labeling Act was discussed as part of the FDA presentation. FDA, like FTC, must follow the requirements of the Act. FDA is not in a position to get Congress to change the Act, but recommended that members of the Conference might contact members of Congress directly.

U.S. Office of Consumer Affairs

Mr. Howard Selzer, U.S. Office of Consumer Affairs, met with the Committee and discussed their office priorities. They included privacy, more media coverage, and issues affecting senior citizens. Mr. Selzer meets with the 41 member Consumer Affairs Council which is comprised of representatives of Federal agencies and departments. National Consumer Week, traditionally held at the end of April each year may be moved to the fall in 1991. NCWC members will be encouraged to participate in activities in their area. The Conference will send "Weights and Measures Today" to the Office of Consumer Affairs to keep them informed.

502 I Public Liaison

National Industrial Scales Association (NISA)

Mr. Bill Gemeiner, president of NISA, outlined the organization of the Association and presented its goals and objectives. NISA, a group of users and manufacturers of heavy industrial scales, was organized in 1987 as an offshoot of the Railroad Division of the International Society of Weighing and Measurement (ISWM.) Currently, there are 190 members from the United States, Canada, and China. Two technical seminars are conducted each year. Several publications provide membership contact. NISA hopes to work with NCWM in its area of expertise and provide a united voice where applicable. Anyone interested in membership may contact NISA, c/o Mr. Max Casanov, Secretary/Treasurer, 1853 West County Road-C, St. Paul, Minnesota 55113.

Canada

Mr. Gilles Vinet, Program Officer, Weights and Measures, Legal Metrology Branch, attended the Interim Meeting to learn about the work of the Conference as a means of coordinating Canadian and U.S. weights and measures.

issues. He indicated that the contact was useful and his office intends to have someone attend Conference activities on a regular basis. Anyone with weights and measures issues concerning trade with Canada should contact Mr. Vinet by telephone (613) 952-2628, or in writing at 207 Queen Street, Ottawa, Ontario K1A 0C9 Canada, or call the Canadian Consumer Products Office (819) 997-1177.

International Association of Wiping Cloth Manufacturers (IAWCM)

Mr. Stuart Daniels, President of the IAWCM reported to the Committee that IAWCM wants to work with NCWM to resolve the industry's problems in selling wiping cloths by gross weight and to clear up any misunderstanding by either the industry or the Conference. He is going to take the Laws and Regulations Committee's comments back to the industry representatives and work toward resolution.

U.S. Metric Association

Mr. Louis Sokol, U.S. Metric Association, addressed the Committee concerning recent activities in the conversion towards and acceptance of metrication in the United States. The greatest activity within the Federal agencies is with the General Services Administration (GSA). A Federal Register notice for metrication programs has been published and no negative comments have been received. The U.S. Metric Association (USMA) and the American National Metric Council (ANMC) conducted a well-attended metric conference in October. A second National Metric Conference sponsored by the U.S. Metric Association, the American National Metric Council and the Department of Commerce Metric Program Office will be held October 29-30, 1990 in Arlington, Virginia. All members of the Conference are invited to attend.

Mr. Sokol stated that the Fair Packaging and Labeling Act (FPLA) provides a stumbling block for metrication. He has marked up a copy of the package labeling section (Section 4) to require that the contents be expressed in SI metric units and has forwarded it to Mr. James H. Turner, staff counsel of the Committee on Science, Space, and Technology, U.S. House of Representatives, Washington, DC.

Mr. Sokol has prepared and presented to the Executive Committee a mark-up of Appendixes B and C of H-44 to put the proper use of "mass" and "weight" into effect.

Mr. Sokol has also responded to FDA on nutritional labeling requesting the term calorie be changed to kilojoule.

Removal of Trade Barriers inside the European Community by 1992 (EC-92)

The Committee has sent to each State Director and officer of the NCWM an update of activities concerned with the 1992 deadline to remove barriers to free trade with the European Community (EC-92). The update included the following contacts: the Office of European Community Affairs, International Trade Administration, U.S. Department of Commerce, Room 3036, Washington, D.C. 20230 (202) 377-5279 or 377-5823; Ms. Debra Miller, Office of Industrial Trade Administration, U.S. Department of Commerce, Washington, DC. 20230 (202) 377-3703.

Task Force on Fraud

The report of the Task Force on the Prevention of Fraud is being reprinted. A copy of the publication and condensed information will be sent to the following organizations including:

- U.S. Office of Consumer Affairs
- National Association of District Attorneys
- National Association of Attorneys General
- National Association of Consumer Agency Administrators
- International Association of Chiefs of Police
- National Institute of Municipal Law Offices
- International Society of Weighing and Measuring
- Scale Manufacturers Association
- American Petroleum Institute
- Gasoline Pump Manufacturers Association

Discussions with these groups have revealed that they would like to receive materials for their newsletters as well

as copies of final reports. The Committee will place these and other associations interested in interacting with the Conference on the Weights and Measures Today mailing list.

503 I OIML Activities

Mr. Sam Chappell (NIST) described the OIML activities of interest to the NCWM. See the report of the Executive Committee for details.

504 I OWM Status Report

Mr. Albert Tholen, Chief, OWM, reported on the status of the OWM in terms of staffing and program changes. See the report of the Executive Committee for details.

505 I Railroad Freight Car Stenciled Tare Weights

Mr. John J. Robinson, Senior Assistant Vice President, Association of American Railroads (AAR), reported that during 1989, a total of 86,719 railroad freight cars were weighed and restenciled. The total represents 42,564 non-exempt (general service) cars and 44,155 exempt (specially equipped) cars. This was approximately 8 percent of the total serviceable fleet. Almost 14,000 covered hoppers and 24,000 open top hopper cars were restenciled. This is a substantial reduction from the 1988 total of over 141,000 cars restenciled.

The reduction is attributed in large part to a change in the railroad industry's Interchange Rule 70 governing the lightweighing/restenciling of freight cars made during the first half of 1989. The existing tolerances remain unchanged; however, the 60-month time limit for lightweighing non-exempt cars was eliminated, along with the authority for a car owner to weigh another's cars when the 60-month limit was exceeded. Accordingly, the responsibility for maintaining accurate tare weights now rests solely with the car owner.

In taking this action, the rail carriers noted the continuing trend in the railroad industry toward per-car rates and weight agreements. It was concluded that, where tare weights are still used, the individual railroads have sufficient incentive to maintain the necessary tare weight accuracy.

The AAR field force continues to spot check over 2,000 stenciled tare weights monthly for comparison with the applicable UMLER (computer based) tare weight. The AAR will continue to furnish each freight car owner a summary of its annual restenciling activity and will urge all railroads to continue their efforts in this area.

506 I The 75th Annual Meeting of the NCWM

Due to the special significance of the 75th Annual Meeting and the Conference's relationship with the National Institute of Standards and Technology (formerly the National Bureau of Standards), Washington, DC., has been selected as the site of the 1990 meeting.

In 1904, an invitation was sent to the Governor of each State by the Director of the National Bureau of Standards to send a representative to attend a meeting. The proposal was to effect a "close cooperation" between the State weights and measures inspectors and the National Bureau of Standards. The Conference was held in Washington, DC., January 16 and 17, 1905. This was the first National Conference on Weights and Measures. A videotape of the First National Conference was made under the direction of the Committee and shown as part of the opening ceremonies of the 75th Annual Meeting. Anyone who would like a copy of the tape should contact Karl Newell at (301)975-4013 for information and cost.

A souvenir program containing the proceedings from the First Conference and a letter of congratulations signed by President Bush was given out at the 75th Conference.

507 I Liaison with Regional Associations

The Committee heard a report from Mr. Ray Elliott, past President, for Mr. Bill Eldridge, President of the Southern Weights and Measures Association, on their activities. They are working on a history of the Association. Concern was expressed over the liaison and education role Dick Smith played with the regional associations and what the future direction of NIST may be in this area following Mr. Smith's retirement. The timeliness of getting information regarding the theme for Weights and Measures Week was discussed. The next Southern meeting will be held October 28 through November 1, 1990 in Jackson, Mississippi.

The report on the Western Weights and Measures Association was given by Mr. Pat Nichols, President. Plans for the 1990 meeting include participation of representatives from the United Kingdom. The meeting is scheduled for August, 1990 in Phoenix, Arizona.

Ms. Peggy Adams gave the report for the Northeast Weights and Measures Association for Chairman William Slamon. The Northeast's concern over the current NIST information distribution practice of sending policy letters only to State Directors, but not to major city and county jurisdictions, was discussed. Mr. Ronald Crust, Chairman of the Northeast Weights and Measures Association, reported that their Interim Meeting will be held on October 24 and 25 in Cromwell, Connecticut, and their Annual Meeting will be held at the Royce Hotel, Langhorn, Bucks County, Pennsylvania, May 20-24, 1991.

The Central Weights and Measures Association report was given by Mr. Jim Akey for Mr. Don Soberg, Chairman. The Central region also voiced concern over Dick Smith's retirement and its impact on interaction between the regionals and NIST. The Central region has forwarded its concerns regarding petroleum products (oxygenated additives) labeling to the Conference. Michelle Phillips, President of the Central Weights and Measures Association, reported that their Annual Meeting will be held in Indianapolis, Indiana, April 14-18, 1991.

508 I Energy Allocation

Representatives of the Task Force on Energy Allocation and the National Utilities Allocation Association (NUAA) met with the Committee to target national governmental, consumer, landlord/tenant, and technical organizations who should receive the "Recommended Regulation for Energy or Utilities Allocation Systems" (see 1989 Report of the NCWM, p. 92). A NUAA plan of action is in the process of implementation. NUAA's toll free number is 1 (800) 525-1124.

509 I Weights and Measures Week

All jurisdictions and members of NCWM received the third printing of NCWM Publication #7, "Weights and Measures Week Guide." All local and State jurisdictions received the 1990 Weights and Measures Week mailing. The theme was "Progress Through Consensus Among Consumers, Regulators and Industry."

Weights and Measures Week packets for 1991 were distributed to all delegates during the 75th Annual Meeting. The theme for 1991 is "Weights and Measures for the 21st Century." Any jurisdiction not receiving the packet should contact Peggy Adams, Box E, Bedminster, Pennsylvania 18910; (215)795-2149.

510 I Computer Information Systems

The need for computer information users groups at the regional meetings was reaffirmed. The Committee recommends that each regional association have a computer users meeting as part of its annual meeting; the meeting should be scheduled so as not to conflict with other meetings and should include a demonstration of a successful program by one of its members and used by that member's jurisdiction. The WAMIS electronic bulletin board will continue to be updated by OWM.

511 I Liaison with Other NCWM Organizations and Committees

Industry Committee on Packaging and Labeling (ICPL)

Mr. Chip Kloos and Mr. Irving Bell conducted a discussion of accuracy regarding labeling requirements and weights and measures practices. A letter from ICPL was presented concerning sampling plans and the use of sampling variations. ICPL is planning a request and proposal to the NCWM for the addition of a sampling variation provision to the Category B sampling plans similar to the Category A plans. Discussion was held on the accuracy and equity in the package filling process and how Category B, without an allowance for sampling variation, forces overfilling for assurance of compliance. Accuracy is required in packaging and labeling regulations. Category A sampling plans in H-133 provide for sampling variation. This will be incorporated into the Laws and Regulations Committee report as an informational item.

Associate Membership Committee

Chairman Bill Braun reported that the Committee's Vice Chairman, Max Casanova, had resigned due to other job responsibilities not allowing him time to complete his duties for the Committee. Ms. Dawn Brydon has been appointed to replace Mr. Casanova. Mr. Chip Kloos was elected as Secretary. Plans are proceeding smoothly for the industry reception in Washington, DC., for the 75th Annual Meeting. Mr. Braun commented that he had attended Module 22 (Commodity Regulations) training in South Dakota and found it to be excellent. He recommended that other industry personnel attend training of this nature as soon as they can.

Retiree's Group

Mr. Ray Wells reported on the activities of the retirees at the Regional Meetings and the National Conference. He is looking for a retired person to take over the organization of the groups. Retiree groups are active in the Western and Southern Associations, but more work is needed in the Central and Northeast. He hopes for a large turnout at the National Conference in Washington.

512 I Task Force on Safety

Members of the Task Force on Safety met with the Committee to discuss ways the Committee can provide assistance to the Task Force (see also the Executive Report). Task Force technical advisor, Ms. Tina Butcher, presented a list of goals and objectives of the Task Force. The Task Force wants to explore ways of working with the Occupational Safety & Health Administration, OSHA, loss control agencies, safety educational groups, and others to address the broad areas of safety programs. The Committee will contact Consumer Product Safety Commission, Federal agencies, industrial groups, loss control agencies, and others to determine resources for the Task Force.

The Committee and the Chairman of the Task Force on Safety met with Mr. Al Abadir, of the Directorate of Technical Support at OSHA. A good liaison was established. Future meetings will establish how the NCWM will interact with OSHA. Several possibilities were discussed including OSHA review of NCWM publications, particularly EPOS's, use of OSHA libraries and technical centers, and use of the OSHA Training Center in Chicago, Illinois.

P. Adams, Bucks County, Pennsylvania, Chairman

J. Akey, Wisconsin

R. Davis, James River Corporation

J. McCutcheon, USDA

K. Thuner, San Diego County, California

K. Newell, NIST, Technical Advisor

Committee on Liaison

Annual Committee Reports



Report of the Resolutions Committee

O. R. Elliott, Chairman
Director, Agricultural Products Division
Oklahoma Department of Agriculture

REFERENCE KEY

700

GENERAL

The resolutions committee wishes to express the appreciation of the members of the National Conference on Weights and Measures to those who contributed their time and talents toward the arrangements for the conduct of, and the success of this 75th Annual Meeting. Special votes of thanks are extended:

- (1) to President George Bush for his letter of greeting to Conference participants and his praise for Conference efforts toward the growth of American commerce from the time of the first meeting in 1905 until this Diamond Anniversary meeting;
- (2) to Representative Tim Valentine, Jr., of North Carolina for his gracious welcome to the conference members and guests and his laudatory remarks regarding the activities of the National Institute of Standards and Technology and, since its inception, the splendid accomplishments of the National Conference on Weights and Measures;
- (3) to Dr. John Lyons, the Director of the National Institute of Standards and Technology (NIST), for his continuing the custom of addressing the membership, and for perpetuating the NIST partnership with the NCWM; to Dr. Lyons for his vision for the future of weights and measures and commitment to maintaining the NIST traditional function of support of the states, business and the Conference; to Dr. Lyons for his appointment of Dr. Edward C. Heffron, State of Michigan, to the NIST Visiting Committee;
- (4) to Dr. Don Johnson, Director, NIST Technology Services, for his attendance at the annual meeting and his presentation of this year's President's and Honor Awards;
- (5) to officers and appointed officials of the National Conference on Weights and Measures for their assistance and service toward progress on national issues;
- (6) to committee members for their efforts throughout the past year preparing and presenting their reports; to the subcommittees and task forces for their discerning and appropriate recommendations;
- (7) to regulatory officials of State and local jurisdictions for the advice, interest, and support of weights and measures administration in the United States;
- (8) to representatives of business and industry for their cooperation and assistance in committee and Conference work; to the associate membership organization for the hospitality exhibited in sponsored social functions;
- (9) to the staff of the J. W. Marriott Hotel for their assistance and courtesies, all of which contributed to the enjoyment and comfort of the delegates within their fine facilities; and

Resolution's Committee

- (10) to the National Institute of Standards and Technology and the Office of Weights and Measures for their outstanding assistance in planning and conducting the work and program of the National Conference on Weights and Measures, especially to Ann Heffernan-Turner and Terry Grimes for their professional and hospitable operation of the administrative operations of the meeting; to the Liaison Committee, the actors, NIST staff, and all those involved in the recreation on videotape of the first meeting of the Conference of 85 years past.

The following resolution is presented in its entirety for consideration of the members of the Conference:

NEWSLETTER EDITORS

Whereas, weights and measures newsletters are a professional and informative source of communication; and

Whereas, weights and measures publishers and editors through their dedication, research, and personal attention bring knowledge and information to those weights and measures enforcement personnel unable to attend seminars and conferences; and

Whereas, weights and measures publishers and editors through their services aid and enhance the professional and technical expertise of weights and measures personnel in the performance of their assignments in respective jurisdictions; and

Whereas, weights and measures publishers and editors of newsletters represent a valuable means of communication on laws and regulations, type approval of devices, inspection and testing procedures of devices set forth by the National Institute of Standards and Technology to be administered throughout the United States of America; Therefore, be it

Resolved by the 75th Annual Conference that recognition be given to publishers and editors of weights and measures newsletters for the donation of their time, talent, and expertise in assembling, validating, and publishing items of interest and importance to members of the weights and profession.

O. R. Elliott, Chairman

D. Ely, Pennsylvania
S. McFarlane, Washington
S. McGuire, Illinois
C. Pittman, Tennessee
A. Thompson, Alaska

J. Mindte, NIST, Coordinator

Resolutions Committee

Report of the Nominating Committee

John J. Bartfai, Chairman
Director, Bureau of Weights and Measures
State of New York

REFERENCE

KEY NO.

800

The Nominating Committee met during the Interim Meeting at the SunBurst Resort Hotel and Conference Center, Scottsdale, Arizona, and nominated the persons named below to be officers of the 76th Conference. In the selection of nominees from active membership, consideration was given to professional experience, qualifications of individuals, prior Conference attendance and participation, regional representation, and other factors considered to be important.

CHAIRMAN-ELECT:

Sidney A. Colbrook, Illinois

VICE-CHAIRMEN:

Kenneth S. Butcher, Maryland
Lynda Maurer, Rhode Island
Glen H. Jex, Idaho
Mike Deisley, Nebraska

EXECUTIVE COMMITTEE:

Patrick E. Nichols, California
Ross J. Andersen, New York

TREASURER:

Charles Gardner, Jr., Suffolk County, NY

John J. Bartfai, New York, Chairman

F. Clem, Columbus, OH
L. DeGrange, Maryland
C. Greene, New Mexico
D. Guensler, California
E. Keeley, Delaware
T. Kelly, New Jersey

Nominating Committee

On motion of Mr. Bartfai, Chairman, the report of the Nominating Committee, voting key item 800, was adopted in its entirety by the Conference.

Report of the Auditing Committee

Gerald Hanson
Director of Weights and Measures, San Bernardino County, California

Reference
Key No.

900

The Auditing Committee met on Tuesday afternoon, July 10, 1990, for the purpose of reviewing the financial reports of the Conference Treasurer, Charles A. Gardner, Jr. Committee members S. Casto and E. Murphy were unable to attend the annual meeting. Carol P. Fulmer, South Carolina, and Richard L. Davis, James River Corporation, Neenah, Wisconsin, were appointed on-site to serve in their absence. The gentlemen graciously accepted.

The Auditing Committee finds the financial reports of the Conference Treasurer to be in accordance with Conference procedure and correct.

G. Hanson, San Bernardino, California, Chairman

C. Fulmer, South Carolina

R. L. Davis, James River Corporation, Neenah, Wisconsin

J. Mindte, NIST, Coordinator

Auditing Committee

(On motion of Mr. Hanson, the Report of the Auditing Committee, Reference Key Item 900, was adopted by the Conference.)

**National Conference On Weights and Measures
Listing of Expenses
FY 74 (1989 - 1990)**

July 11, 1990

2.0 Annual Meeting

2.1 Hotel/Food Services	\$9,659.79	
2.2 Audio/Visual	750.00	
2.3 Personnel	1169.00	
2.4 Printing	592.03	
2.5 Photos	415.00	
2.9 Miscellaneous	180.90	<u>12,766.72</u>

3.0 Interim Meeting

3.1 Hotel/Food Service	6,301.86	
3.3 Personnel	701.43	
3.4 Printing	1,172.26	<u>8,175.55</u>

4.0 Committee Operations

4.1 Executive	7,376.10	
4.2 Laws and Regulations	2,843.13	
4.3 Specifications and Tolerances	7,806.88	
4.4 Education	5,152.17	
4.5 Liaison	2,100.57	
4.7 Nominating	502.21	
4.8 Printing	3,742.20	<u>29,523.26</u>

5.0 Special Programs

5.1 NTEP	8,284.30	
5.2 OIML	645.67	
5.3 75th Anniversary Video	4,772.65	
5.6 TF on Safety	4,734.86	
5.7 TF on Energy Allocations	1,282.70	<u>19,720.18</u>

6.0 Chairman's Expenses

6.1 Chairman	4,272.68	
6.2 Chairman-Elect	2,757.12	
6.3 Annual Reception	4417.22	
6.4 Regional Breakfasts	881.25	<u>12,328.27</u>

7.0 Membership Programs

7.2 Contract Work	2,131.03	
7.3 Banners	2,525.15	
7.5 Invoices	817.00	
7.6 Printing	347.03	<u>5,820.21</u>

Treasurer's Report

8.0 Printing and Publications

8.1 Annual Meeting	9,633.56	
8.3 Letterhead	245.00	
8.4 Membership	120.00	
8.9 Miscellaneous	104.00	<u>10,102.56</u>

9.0 Administration

9.1 Equipment	1509.00	
9.2 Services/Contract	2434.26	
9.3 Mailing	82.50	
9.4 Supplies	76.60	
9.5 Bank Charges	7.00	
9.6 P.O. Box Rental	159.00	
9.7 Modules	4,024.45	
9.8 Travel	158.00	
9.9 Miscellaneous	155.14	<u>8,605.95</u>

10.0	Special Events	10,722.72	10,722.72
------	----------------	-----------	-----------

11.0	Promotional Items	3,667.42	3,667.42
------	-------------------	----------	----------

12.0	Training Modules	14,914.15	14,914.15
------	------------------	-----------	-----------

TOTAL DISBURSEMENTS			<u>\$136,346.99</u>
---------------------	--	--	---------------------

**Treasurer's Report
Fiscal Year 74 (1989-1990)
National Conference on Weights and Measures**

July 11, 1990

Grant Account

Start		\$5082.89
-------	--	-----------

Deposits

Grant #1 HA 4003	\$30,570.20	
Grant #2 8H 0869	3,000.00	
Total		<u>33,570.20</u>

Interest

Grant #1 HA 4003	136.81	
Grant #2 8H 0869	103.64	
Total		<u>240.45</u>
Total		<u>\$38,893.54</u>

Payments

Grant #1 HA 4003	\$25,241.77	
Grant #2 8H 0869	6,871.77	
Total		<u>32,113.54</u>

Close		<u>\$6,780.00</u>
-------	--	-------------------

Date Submitted: July 13, 1990

(signed) Charles A. Gardner
Charles A. Gardner, Treasurer

Treasurer's Report

National Conference on Weights and Measures
Treasurer's Report
Fiscal Year 74 (1989-1990)

July 11, 1990

CASH \$90,942.70

(BUDGET)

RECEIPTS:

(\$30,000)	1.1 Registrations	<u>25,315.00</u>
(67,550)	1.2 Memberships	<u>96,883.50</u>
(6,500)	1.3 Training Modules	<u>8,667.00</u>
(3,000)	1.4 Interest	<u>5,064.40</u>
(1,000)	1.5 Promotional	<u>-0-</u>
(5,000)	1.6 Special Events	<u>14,174.71</u>
(300)	1.9 Miscellaneous	<u>115.00</u>
(113,350)		
	TOTAL RECEIPTS	<u>150,219.61</u>
	TOTAL INCOME	<u>241,162.31</u>

DISBURSEMENTS:

(14,000)	2.0 Annual Meeting	<u>12,766.72</u>
(4,000)	3.0 Interim Meeting	<u>8,175.55</u>
(20,000)	4.0 Committee Operations	<u>29,523.26</u>
(18,000)	5.0 Special Programs	<u>19,720.18</u>
(12,550)	6.0 Chairman's Expense	<u>12,328.27</u>
(6,000)	7.0 Membership Expense	<u>5,820.21</u>
(6,000)	8.0 Printing & Publications	<u>10,102.56</u>
(12,500)	9.0 Administration	<u>8,605.95</u>
(5,000)	10.0 Special Events	<u>10,722.72</u>
(1,300)	11.0 Promotions	<u>3,667.42</u>
(14,000)	12.0 Training Modules	<u>14,914.15</u>
(113,350)		
	TOTAL DISBURSEMENTS	<u>136,346.99</u>
	BALANCE	<u>104,815.32</u>

BANKS

European American (New York)	<u>49,260.18</u>
Signet (Maryland)	<u>314.24</u>
Certificate of Deposit #1 (6 Mo.)	<u>23,374.94</u>
Certificate of Deposit #2 (3 Mo.)	<u>11,088.46</u>
Certificate of Deposit #3 (3 Mo.)	<u>20,777.50</u>

BALANCE 104,815.32

Date Submitted: 7/12/90 Charles A. Gardner
Charles A. Gardner, Treasurer

Date Audited: 7/10/90 Meredith W. Hanson
Auditing Committee Chairman

JOAN MINDTE
Staff Advisor

New Chairman's Message

July 12, 1990

N. David Smith
Director, Standards Division, North Carolina Department of Agriculture

I am the first Chairman-elect to have had the privilege of accompanying the Chairman to the regional meetings. From close, personal observation, I can say that Fred Gerck has been a tremendous Chairman.

Fred has been a great friend and advisor. As Chairman, you have certain perks, one of which is to create awards. Thus, I am giving Fred a personal award - The Great Example Award.

Fred and I have a great working relationship. The same will continue with me and Sid Colbrook, your Chairman-elect. We have known each other for several years and share many common philosophies. I hope you will give Sid and me your advice and criticism.

The earliest record I have of the National Conference is the report of the 10th Annual Conference which was held in Washington, DC in 1915. From that report, I have found some interesting information.

During a discussion of when and where to schedule future conferences, the delegate from the District of Columbia made the following declaration. "The only reduced rate at this season of the year that can be counted on, year by year, is the reduction that comes on all trips to Washington around Decoration Day. There is the prime argument for setting the date in the month of May. The summer rates go in effect in June, but if you come here once in June you will never come again. There is no one who spends a week here in Washington after June if they can help it."

Mr. L.A. Fischer, Chief, Division of Weights and Measures, NBS, reported that "at the last conference, the committee on tolerances and specifications was given authority to reword the tolerances and specifications without changing their meaning, and the committee promptly set about carrying out the instructions of the conference. After carefully studying the subject, the committee found it highly desirable and necessary to make amendments involving some changes in the meaning of the original tolerances and specifications." Today, we know that changes to meaning are the result of granting "editorial privilege".

The delegate from New York offered a resolution to expand the committee on tolerances from 3 to 5 members and change the committee's name to the board of control. Thankfully, the resolution was defeated.

Lastly, in the comments of William C. Redfield, Secretary of Commerce, he noted the following, "nearly half of the world is on fire. The citizens of Europe, of Africa, of Asia, and of Australia are engaged in destruction. I wonder if you have ever thought, as I used to think, that now is a very ordinary time in which to live, that all the interesting things happened in the time about which the books were written, and that this was a very humdrum day. We, none of us, think so now, for America is the only continent in which a great many people are not trying to destroy one another. Neither your fathers nor yourselves ever saw such a condition as we face every time we pick up our morning newspaper. Men's lives, men's property are being destroyed at a rate which is appalling. Sciences are being utilized to produce disaster on a scale which we have never known. Nothing could be more contrasted than the spirit in which we meet here to help one another and the spirit with which, across the sea, men are trying to destroy one another. there can be no sharper difference made between the spirit of America and spirit of militancy than that."

As we meet in 1990, the citizens of Europe are again engaged in destruction, but this time they are destroying a form of government while throwing out the welcome mat to the citizens of the world.

In preparing my remarks, I decided to review the annual conference reports at the beginning of each decade since 1920. In each of those reports, there are pleas for national uniformity of weights and measures requirements, for agreement on device type evaluation, and for more help from the Bureau in the area of training. Weights and measures officials complained about the lack of staff and resources and the imposition of fees. The integrity of the S & T Committee was called into question in virtually every report. Has anything changed? Yes, great problems have been solved and much progress has been made. Yet, the National Conference continues to be a much undervalued organization and one that perhaps consciously avoids publicity. As we prepare for the 21st Century, I feel that the National Conference must take stock of itself and plot a course of where we want to go or others will surely plot that course for us.

If being President of the United States means that George Bush doesn't have to eat broccoli, then being chairman of the National Conference means I can exercise a moment of personal privilege. At this time, I want my son, Eric, to come forward. Eric is 10 years old and is a rising fifth grader at Lead Mine Road Elementary School. However, I want us to examine Eric as he will be in the year 2000. In 10 years, Eric will be 20 years old and if everything goes according to plan, he will be out of college and ready to support his parents.

Let's look at Eric at the beginning of the 21st Century and what weights and measures may mean to him.

First, Eric the weights and measures inspector. After graduating from college with a degree in computer science, engineering, statistics, accounting, or mathematics, now the required degrees for a weights and measures position, Eric begins his career in weights and measures. However, things are different for Eric since he spends the majority of his time auditing weights and measures transactions. From his office, he plugs into the quality control program of a major packager and audits production runs from several day's production. There is no longer a need for the weights and measures inspector to weigh individual packages since each package is weighed separately by the manufacturer and is given a unique number. When Eric detects a short weight lot or even individual short weight packages, a notice of violation is electronically transmitted to the manufacturer. Settlement of the shortweight discovery is immediate since according to prior agreement, the results of electronic auditing are not contestable. You ask, "What about testing weighing and measuring devices"? This practice has been virtually eliminated due to the introduction of devices which are self calibrating. Eric needs only to audit a company's calibration schedule. For the few devices which are not self calibrating, Eric relies on a sampling plan which targets troublesome devices. The remainder of Eric's time? Weights and measures has broadened its scope to include many areas of consumer fraud such as travel promotions and rent of leisure property. In addition, Eric is responsible for monitoring compliance with product safety laws and for providing assistance to firms interested in introducing new products to the international market.

Now, Eric the weights and measures device manufacturer. Eric's company competes freely in Europe and is a major supplier of weighing systems. Regardless of the country, the system is exactly the same, save for an interchangeable key pad which is available in 15 languages. Eric's current assignment is to analyze the domestic market and make recommendations to upper management on how to improve U.S. profitability. Armed with facts on the high cost of making 6 different versions of the same model to satisfy domestic weights and measures requirements, Eric is prepared to recommend that his company join a growing list of firms advocating that Congress enact a national weights and measures law. This law will move NTEP from voluntary to mandatory status, but will also standardize equipment design and requirements and require that the states recognize an NTEP certified device.

A look at Eric the packager. With the ability to weigh and identify each package, Eric regards the quarterly weights and measures audit as routine. At the appointed time, the weights and measures inspector accesses Eric's computer system. Eric already knows which lots will be questioned and he is prepared to offer a 0.01% overfill for the next 3 months to compensate customers in Wake County, North Carolina who purchased short measure product. This is easy to do since a record is maintained on where each package is sold, and if the purchase is by credit card or debit card, the name and address of the purchaser is known. The weights and measures official agrees to this approach and, after verifying that production computers have been reprogrammed, he signs off the system.

What about Eric the consumer? Eric is concerned with health care costs, the environment, and food and product safety. When asked about weights and measures issues, Eric explains that accurate measurement is

important, but its importance is down the list. His thinking simply means that in 10 years, consumer concerns have not changed. In the Fall, 1989, issue of MOBIUS, the Journal of the Society of Consumer Affairs Professionals in business, none of the articles in the issue, which was devoted to the consumer agenda for the 90's, mentioned weights and measures or a concern which can be readily identified with weights and measures. Are we satisfied with the state of weights and measures because our needs are being met or is weights and measures one of those effective programs that no one knows about yet is one of the first to be found when the budget knives are being sharpened?

At this point, I must inject an editorial comment. While researching consumer trends, I found an article which dealt with Federal agencies and their consumer agenda for the next decade. According to Secretary Mosbacher, "the mission of the Department of Commerce is to encourage economic growth, promote international trade, and further technological advancement. To carry out these goals, the Commerce Department works closely with both the business and consumer communities." While I didn't expect the National Conference to be mentioned, I must wonder if the Secretary is aware that through the National Conference there is a great opportunity for the Department of Commerce to interact with consumers and industry. Better yet, cities, counties, states, and private industry are footing the lion's share of the cost. With a potential membership of 5,000 in the next 3 years, the National Conference can be a very potent force in helping the Commerce Department meet its mission.

Now for perhaps the most important Eric of all, Eric the taxpayer. On what programs will Eric demand that his tax money be spent? What level of performance will he require? Most likely, Eric the taxpayer will reflect the concerns of Eric the consumer. Remember, health costs, the environment, and food and product safety dominate his agenda. In the year 2000, will any weights and measures program be a general fund obligation or will the programs be solely supported by inspection and registration fees or from some other imaginative means designed to separate people from their money?

In 10 short years, Eric and his classmates will be moving into these roles. The 21st Century will be here. I have chosen this year's theme to be "Weights and Measures for the 21st Century." To help plot a course, some very fine people have agreed to give freely of their time and talents.

Education Committee	Martin Coile, Georgia 5-year term
Laws and Regulations Committee	Sharon Rhoades, Indiana 5-year term
Specifications & Tolerances Committee	Dick Suiter, Nebraska 5-year term
Liaison Committee	Clayton Davis, Maine 5-year term
	John Lacy, Packers/Stockyards USDA 4-year term
	Aves Thompson, Alaska 3-year term
Auditing Committee	Ed Hanish, Indiana 3-year term
Credentials Committee	Guy Tommasi Middletown, Connecticut 3-year term
Resolutions Committee	Michelle Phillips, Indiana 3-year term

New Chairman's Message

Nominating Committee

Mike Grenier, New Hampshire
3-year term

Glen Jex, Idaho
2-year term

Ed Price, Texas
2-year term

Steve Malone, Nebraska
1-year term

L.F. Eason, North Carolina
1-year term

Alan Rogers, Virginia
1-year term

Don Soberg, Wisconsin
1-year term

Charlie Gardner, Suffolk County, New York
1-year term

Carl Conrad, New Jersey
1-year term

Budget Review Committee

Fred Gerk, New Mexico
2-year term

Chaplain

Cordell Robinson, Columbus, Ohio

Assistant Treasurer

Gerry Hanson, San Bernadino County, California

Sergeants-At-Arms

Jim Noone, Philadelphia, Pennsylvania

Ron Roof, Pennsylvania

Parliamentarian

Clayton Davis, Maine

The Safety Task Force will continue its work. According to Chairman Gardner, the Task Force should complete its assignment and have a final report for the next conference.

I have said much about preparing for the 21st Century. We need to discuss our vision of the future. We need a plan. To put ideas on the table, I have asked Darrell Guensler of California to chair a task force of wild-eyed dreamers. Their goal is to rock the boat and not be satisfied with the status quo. Among many tasks, I want the task force to:

determine the interest in including a session on motor fuel quality during the annual meeting;

make some predictions on the future of traditional weights and measures;

suggest new areas which could come under the weights and measures umbrella;

suggest how we can take the National Conference to the membership rather than the membership coming to the National Conference;

investigate avenues that will put the value of the National Conference before our political and civic "movers

and shakers";

consider the impact of biodegradable, recyclable, and safety packaging on existing weights and measures requirements; and

be a "blue sky" committee that will cause us to engage in debate and discussion on the future of weights and measures.

Joining Darrell in this assignment are Bruce Martell of Vermont, Tom Geiler of the Town of Barnstable, Chip Kloos of Beatrice/Hunt-Wesson Foods, Inc., and a yet to be named representative from the Department of Commerce.

I look forward to serving the National Conference. As previously stated, your advice and criticism is welcomed. Just pick up the phone and give me a call.

At the conclusion of the meeting, Al Tholen is expecting me to say "Sine Die." but I feel a more appropriate ending is "Y'all Come Back." There being no further business to come before this assembled 75th Annual Meeting of the National Conference on Weights and Measures, I declare the meeting adjourned.

Registration List for 75th Annual Meeting

Deidre Adams Staff Product Planner IBM 2020 Yonkers Road Raleigh, NC 27604 Telephone: 919-664-5120 FAX: 919-664-5004	700	Jerry L. Bane Acting Bureau Chief Iowa Dept Agriculture Henry A. Wallace Bldg, E 9th Des Moines, IA 50319 Telephone: 515-281-5716 FAX: 515-281-6236	10636	Melvin Bighthumb Weights & Measures Inspector The Navajo Nation PO Box 663 Window Rock, AZ 86515 Telephone: 602-871-6714 FAX: 602-871-7381	4248
Michael F. Adams Manager of Technical Support Fairbanks Scales 711 E St Johnsbury Rd St Johnsbury, VT 05819 Telephone: 802-748-5111 x326 FAX: 802-748-5216	11447	Salvatore A. Barbera President Digi Matex Inc 80 Oak St Norwood, NJ 07648 Telephone: 201-784-3400 FAX: 201-784-3770	287	James R. Bird Deputy State Supt NJ Retired Bella Bridge Rd, Box 194 Medford, NJ 08055 Telephone: 609-267-5520	82
Peggy H. Adams Chief Scaler Bucks County Consumer Protect. Box 340 Bedminster, PA 18910 Telephone: 215-795-2694 FAX: 215-538-1315	2735	Lester H. Barrows Director Bureau of Weights & Measures PO Box 630 Jefferson City, MO 65102 Telephone: 314-751-4316 FAX: 314-751-8307	3926	Harold Birgy Metrologist MI Dept of Agriculture PO Box 30017 Lansing, MI 48909 Telephone: 517-373-1060 FAX: 517-335-0628	2471
James H. Akey State Metrologist WI Department of Agriculture PO Box 7883 4702 University Ave(05) Madison, WI 53707 Telephone: 608-267-3510 FAX: 608-266-1560	2414	John J. Bartfai Director Bureau of Weights & Measures Bldg 7A State Campus Albany, NY 12235 Telephone: 518-457-3452 FAX: 518-457-4780	23	Del W. Bissett Vice President SGS Control Services PO Box 1328 Kenner, LA 70063 Telephone: 504-469-6401 FAX: 504-469-8485	16251
Frederick T. Allen Manager, Reg Affairs LC27-00 Pinney Bowes Walter Wheeler Dr Stamford, CT 06926 Telephone: 203-925-5044 FAX: 203-925-5080	12094	Irving Bell Senior Executive Staff Rep Coca-Cola Co PO Drawer 1734/One Coca-Cola Plaza Atlanta, GA 30313 Telephone: 404-676-2623 FAX: 404-676-8265	4473	Michael Blalik Acting Dir Weights & Measures State Of Minnesota 2277 Highway 36 St Paul, MN 55113 Telephone: 612-341-7200 FAX: 612-297-1659	8924
Ross J. Andersen Metrologist NY State Bureau of Wts & Meas Bldg 7A State Campus Albany, NY 12235 Telephone: 518-457-4781 FAX: 518-457-4780	2994	Anthony F. Belmont Sealer of Weights & Measures Town of Greenwich Con Aff 101 Field Point Road Greenwich, CT 06830 Telephone: 203-622-7713	2547	Paul Blixt Assistant Manager Corp QA Carnation 5045 Wilshire Blvd. Los Angeles, CA 90036 Telephone: 213-932-6334	16245
Sydney D. Andrews Private Consultant 1133 Myers Park Dr Tallahassee, FL 32301-4525 Telephone: 904-878-3928	41	F. Michael Belue President Belue Associates PO Box 701, 2004 Liberty St Bonham, TX 75418 Telephone: 214-583-9082	691	Barbara J. Bloch Special Assistant CA Div of Measurement Standard 8500 Fruitridge Rd Sacramento, CA 95826 Telephone: 916-366-5119 FAX: 916-366-5179	7004
Wanda E. Armstrong Auditor Clinton County Auditor 46 South Street Wilmington, OH 45177 Telephone: 513-382-2250 FAX: 513-382-7530	8473	Celeste Bennett MFQ Coordinator Wts & Meas Michigan Dept of Agriculture PO Box 30017 Lansing, MI 48909 Telephone: 517-373-1060	9286	Roger B. Bognar Manager Tissue Division American Paper Institute 260 Madison Ave New York, NY 10016 Telephone: 212-340-0618 FAX: 212-689-2628	727
Ron Balaze Metrologist Michigan Dept of Agriculture PO Box 30017 Lansing, MI 48909 Telephone: 517-373-9897	8988	David N. Bigley Research Engineer Consolidation Coal Co Consol Plaza Pittsburgh, PA 15241 Telephone: 412-831-4972	13743	Harold D. Bradshaw Inspector Weights & Measures Dept of Weights & Measures City County Bldg, Room 314 Jeffersonville, IN 47130 Telephone: 812-283-6289	2738

William D. Brasher Senior Quality Control Analyst Southern Co Services Inc PO Box 2625 Bin B852 Birmingham, AL 35202 Telephone: 205-877-7653 FAX: 205-877-7288	4417	Tina Gaver Butcher Weights & Measures Coordinator Natl Inst of Sids & Tech A617 Administration Building Gaithersburg, MD 20899 Telephone: 301-975-2196 FAX: 301-926-0647	8236	Lavar Clegg Director of Engineering Revere Transducers Inc 14030 Bolsa Lane Cerritos, CA 90701 Telephone: 714-739-1991 FAX: 714-522-0931	9406
William H. Braun Packaging Section Manager Procter & Gamble 5299 Spring Grove Ave Cincinnati, OH 45217 Telephone: 513-627-5476 FAX: 513-627-5534	2983	Charles H. Carroll Assistant Director MA Division of Standards One Ashburton Place Boston, MA 02108 Telephone: 617-727-3480 FAX: 617-227-6094	4393	Fred P. Clem Weights & Measures Inspector City of Columbus 50 W Gay St Columbus, OH 43215-2821 Telephone: 614-645-7144 FAX: 614-645-6675	169
Carroll S. Brickenkamp Program Manager Natl Institute of Sids & Tech A617 Admin Gaithersburg, MD 20899 Telephone: 301-975-4005 FAX: 301-926-0647	239	Charles D. Carter Program Administrator W & M Agricultural Products Division 2800 N Lincoln Blvd Oklahoma City, OK 73105-3861 Telephone: 405-521-3864 x294 FAX: 405-521-4912	9838	Martin T. Coile State Metrologist Georgia Dept Agriculture Atlanta Farmers Market Forest Park, GA 30050 Telephone: 404-363-7685	3895
Robert W. Brooks VP Administration Colombo Inc. 3 Riverside Drive Andover, MA 01810 Telephone: 508-682-7115 FAX: 508-685-6543	16000	Max C. Casanova Manager Technical Service Ramsey Technology Inc 1853 W County Rd C Saint Paul, MN 55113 Telephone: 612-638-2264 x264 FAX: 612-638-2275	362	Sidney A. Colbrook W&M Program Manager Illinois Dept of Agriculture PO 19281, 801 E Sangamon Ave Springfield, IL 62794-9281 Telephone: 217-782-3817 FAX: 217-524-4882	47
Robert Bruce Chief Weights & Measures Canadian Cons & Corp Affairs 207 Queen St, Ottawa Canada K1A 0C9, 026 Telephone: 613-952-2625	3932	H. Penny Causgrove Retired Sealer of Wts & Meas City of New Haven 18 Davis St New Haven, CT 06515 Telephone: 203-387-4913	3847	Robert L. Collette Assoc Dir Science & Technology National Fisheries Institute 1525 Wilson Blvd Suite 500 Arlington, VA 22209 Telephone: 202-524-8883 FAX: 202-524-4619	9405
Robert T. Brumbaugh President Systems Associates Inc 1932 Industrial Dr Libertyville, IL 60048 Telephone: 708-367-6650 FAX: 708-367-6960	297	Darrel E. Cavender Metrologist Div of Measurement Standards 12050 Ind Wy Bi O/POB 111686 Anchorage, AK 99511 Telephone: 907-345-7750 FAX: 907-345-2641	7277	Carl P. Conrad, Jr. Chief Supervisor Office of Weights & Measures 1261 U.S. Rte 1 & 9 South Avenel, NJ 07001 Telephone: 201-815-4840 FAX: 201-382-5298	2487
Dawn M. Brydon Director of Marketing Milk Ind Fdn/Intl IC Assn 888 16th St, NW Washington, DC 20006 Telephone: 202-296-4250 FAX: 202-331-7820	9099	Samuel E. Chappell Standards Management Natl Institute of Sids & Tech Bldg 101, Room 625 Gaithersburg, MD 20899 Telephone: 301-975-4024	10610	Donald O. Cripe Sealer of Weights & Measures Madera County 332 Madera Ave Madera, CA 93637 Telephone: 209-675-7876 FAX: 209-674-4071	9794
Howard Burgess Quality Assurance Manager Friskies Petcare/Carnation Co 150 Riverview Dr Jefferson, WI 53549 Telephone: 414-674-4100 x139 FAX: 414-674-5022	11169	Barbara Charnes Director Coloradans for Clean Air 1985 Grape St. Denver, CO 80220 Telephone: 303-388-4858 FAX: 303-388-4858	13800	Ronald R. Crust Centre County W&M Box 574 Milesburg, PA 16853 Telephone: 814-355-5750	2886
Charles Burns, Jr. Chief Inspector City of Birmingham W & M 710 20th St No. Room 207 Birmingham, AL 35203 Telephone: 205-254-2246 FAX: 205-254-2925	7575	Phillip R. Chisholm Executive Vice President Petroleum Marketers Assoc. 1120 Vermont Ave. N.W. Washington, D.C., 20005 Telephone: 202-331-1198	16249	A.R. Daniels Director Industry Stds & Rel NCR Corp 1700 S Patterson Blvd WHQ-5 Dayton, OH 45479 Telephone: 513-445-1310 FAX: 513-445-1418	343
		Richard H. Claussen Director Rm 105 Porter County Weights & Meas Court House Annex 1401 N Calumet Av Valparaiso, IN 46383 Telephone: 219-465-3585	103	Gerald E. Davis System Supvr Scale Insp Conrail 6 Pen center Plaza Room 1634 Philadelphia, PA 19103-2959 Telephone: 215-977-1617	968

Richard L. Davis Manager Product Compliance James River Corporation 1915 Marathon Avenue Neenah, WI 54957 Telephone: 414-729-8174 FAX: 414-729-8161	3806	L.F. Eason Metrologist NC Dept of Agric Standards Division PO Box 27647/SD Raleigh, NC 27611 Telephone: 919-733-4411 FAX: 919-733-0999	3886	Robert K. Feezor Superintendent Scales Norfolk Southern Corp Building Box 142, 99 Spring Sreet Atlanta, GA 30303 Telephone: 404-527-2537 FAX: 404-527-2589	11200
Mike Deisley Agric Program Supervisor Nebraska Weights & Measures 301 Centennial Mall S. PO Box 94757 Lincoln, NE 68509 Telephone: 402-471-4292 FAX: 402-471-3252	4428	David E. Edgerly Acting Deputy Dir/Tech Serv Natl Instit of Stds & Tech Bldg 221 Room A363 Gaithersburg, MD 20899 Telephone: 301-975-4500 FAX: 301-975-2183	2999	Sy Feinland SMTS Pitney Bowes Inc Parrot Dr Shelton, CT 06484 Telephone: 203-925-5211 FAX: 203-925-5333	7048
R.F. Demory Weights & Measures Bureau State of Virginia 234 W Shirley Ave Warrenton, VA 22186 Telephone: 703-349-8310 FAX: 703-347-5868	8408	William P. Eldridge Director Wts & Meas Division MS Dept of Agric & Commerce PO Box 1609 Jackson, MS 39215-1609 Telephone: 601-354-7080 FAX: 601-354-6001	33	Catherine Finch Food/W&M Specialist MI Dept of Agriculture 16615 S Harrison East Lansing, MI 48823 Telephone: 517-373-8782	11197
G.W. (Wes) Diggs Superv, VA Weights & Measures VA Weights & Measures PO Box 1163 Room 402 Richmond, VA 23209 Telephone: 804-786-2476 FAX: 804-371-7793	9034	John J. Elengo, Jr. VP Engr, Wallinford Operations Revere Transducers Inc 845 N Colony Rd PO Box 5041 Wallingford, CT 06492 Telephone: 203-284-5102 FAX: 203-284-5142	440	Beatrice H. Florczyk Deputy Inspector Dept of Weights & Measures City County Bldg Room 1760 Indianapolis, IN 46204 Telephone: 317-236-4272	11607
Loren Dobyns Manager Plant & Electrical Thunder Basin Coal Co PO Box 406 Wright, WY 82732 Telephone: 307-939-1300	12941	O. Ray Elliott Director Agric Products Div OK Dept of Agriculture 2800 N Lincoln Blvd Oklahoma City, OK 73105 Telephone: 405-521-3864 x301 FAX: 405-521-4912	9097	Robert L. Fonger Senior Field Representative Bennett Pump Co PO Box 597 Muskegon, MI 49445 Telephone: 616-733-1302 FAX: 616-739-8832	3919
Louis D. Draghetti Inspector of Wts & Meas Town of Agawam 36 Main St Town Hall Agawam, MA 01001 Telephone: 413-786-0400 x232	2673	Dean F. Ely District Supervisor PA Dept of Agriculture 675 Rose St Williamsport, PA 17701 Telephone: 717-327-3560	9648	Cleveland C. Forde Director Dept Weights & Measures 1157 Scottsville Rd Rochester, NY 14624 Telephone: 716-436-1330	9841
Irv Dubinsky USDA FSIS/USDA Washington, DC 20250 Telephone: 202-447-2378	11240	Larry J. Enfield Directro Quality Control General Mills Inc. Number One General Mills Blvd Minneapolis, MN 55440 Telephone: 612-540-2729 FAX: 612-540-4925	15874	Ken L. Fraley Metrologist Lab Div Bur of Standards 2800 N Lincoln Blvd Oklahoma City, OK 73105 Telephone: 405-521-3864 x370 FAX: 405-521-4912	4148
Clyde L. Duncan President Deka Scale Inc 5655 Opportunity Dr, Suite 30 Toledo, OH 43612 Telephone: 419-478-5001 FAX: 419-478-4633	15337	Alexander Eska Superintendent City of Linden Wts & Meas 301 N Wood Ave Linden, NJ 07036 Telephone: 201-474-8403	3934	Bob Fuehne Sr Qual Assurance Technologist Ralston Purina Co Checkerboard Square - 4RN St Louis, MO 63164 Telephone: 314-982-2916 FAX: 314-982-4072	10443
Donald S. Duncan Deputy Sealer Sacramento Co W & M 4137 Branch Center Rd Sacramento, CA 95827 Telephone: 916-366-2003 FAX: 916-366-4150	7010	James H. Eskew Chief Metrologist TX Dept of Agriculture 119 Cumberland Rd Austin, TX 78704 Telephone: 512-462-1441	3435	Carol P. Fulmer Assistant Commissioner SC Dept of Agriculture PO Box 11280 Columbia, SC 29211 Telephone: 803-737-2080 FAX: 803-734-2192	4463
Michael Dynia Metrologist Weights & Measures Rm G-17 St Off B1, 165 Capitol Hartford, CT 06106 Telephone: 203-566-5230 FAX: 203-566-7630	7196	Dexter A. Fedor Director Quality Control CA Cedar Products Co 1340 W Washington St, PO Box 528 Stockton, CA 95201 Telephone: 209-944-5800 FAX: 209-948-6758	11314	James O. Funderburk Manager Regulatory Affairs First Brands Corporation 88 Long Hill Street East Hartford, CT 06108 Telephone: 203-728-6182 FAX: 203-728-6083	11613

Charles A. Gardner Director Wts & Measures Suffolk County Consumer Affair County Ctr/N Bldg 340 Hauppauge, NY 11788 Telephone: 516-360-4621 FAX: 516-360-7470	3438	John Gould American Meat Institute 1700 N Moore St Arlington, VA 22209 Telephone: 703-841-2400	15317	Edwin M. Hanish Inspector Laporte County Indiana Weights & Measures 2700 Franklin St Michigan City, IN 46350 Telephone: 219-874-7197	109
Charles H. Gardner President Seraphin Test Measure 30 Indel Ave Rancocas, NJ 08073 Telephone: 609-267-0922 FAX: 609-261-2546	9660	Maxwell H. Gray Chief Bureau of W&M FL Dept of Agric & C S 3125 Conner Blvd Tallahassee, FL 32301 Telephone: 904-488-9140	7991	Melvin C. Hankel Manager of Mechanical Engr Liquid Controls Corp Wacker Park North Chicago, IL 60064-3599 Telephone: 708-689-7302 FAX: 708-689-0540	9094
Thomas F. Geiler Scaler of Weights & Measures Town of Barnstable 367 Main St Hyannis, MA 02601 Telephone: 508-790-2521 FAX: 508-775-3344	219	Richard D. Greek Agri Commissioner/Sealer San Luis Obispo County 2156 Sierra Way Suite D San Luis Obispo, CA 93401 Telephone: 805-549-5910 FAX: 805-549-5911	2875	Gerald W. Hanson Director San Bernardino County Wts/Meas 777 E Rialto Ave San Bernardino, CA 92415-0790 Telephone: 714-387-2136 FAX: 714-889-6449	116
William G. GeMeiner Scales Engineer Chicago & North Western RR 165 N Canal Street Chicago, IL 60606 Telephone: 312-559-6133 FAX: 312-559-7185	562	Charles H. Greene Director General Services NM Dept of Agriculture PO Box 30005, Dept 3GSD Las Cruces, NM 88003-0005 Telephone: 505-646-2787 FAX: 505-646-3303	64	James D. Harnett Agricultural Commissioner Dept of Weights & Measures 1010 S Harbor Blvd Anaheim, CA 92805-5597 Telephone: 714-447-7110 FAX: 714-774-2741	7774
Victor L. Gerber Metrologist Wyoming Dept of Agriculture 2219 Carey Avenue Cheyenne, WY 82002-0100 Telephone: 307-777-7324	2455	Terry L. Grimes Secretary Natl Inst of Sids & Tech A617 Admin Bldg Gaithersburg, MD 20899 Telephone: 301-975-4027 FAX: 301-926-0647	6275	Jim Harrington Inspector Weights & Measures Michigan Dept of Agriculture 8918 Dolphin Drive Kalamazoo, MI 49002-6133 Telephone: 616-323-0747	8984
Fred A. Gerk Dir Div Sids & Consumer Svcs NM Dept of Agriculture PO Box 30005, Dept. 3170 Las Cruces, NM 88003-0005 Telephone: 505-646-1616 FAX: 505-646-3303	63	Christopher B. Guay Regulatory Affairs Procter & Gamble Co 11511 Reed Hartman Highway Cincinnati, OH 45241 Telephone: 513-626-2222 FAX: 513-626-2407	13666	Georgia Harris Metrologist, Office Wts & Meas Natl Instit Sids & Technology A617 Admin Bldg Gaithersburg, MD 20899 Telephone: 301-975-4004 FAX: 301-926-0647	9324
Joeseh A. Giannina Manager Bulk Terminal Port of Corpus Christi Auth PO Box 1541 Corpus Christi, TX 78403 Telephone: 512-883-1162 FAX: 512-883-1652	3905	Darrell A. Guensler Assistant Director CA Measurement Standards 8500 Fruitridge Rd Sacramento, CA 95826 Telephone: 916-366-5119 FAX: 916-366-5179	38	Jack Harshman Manager Measurement Eng Daniel Flow Products Inc 9720 Katy Rd Houston, TX 77224 Telephone: 713-827-5131 FAX: 713-827-3880	4454
Carl W. Gile Assistant Metrologist Kansas Weights & Measures Lab 2016 SW 37th St Topeka, KS 66611-2570 Telephone: 913-267-0278	11221	Robert Gunja Standards Administrator City of Kansas City W&M 701 North 7th St Kansas City, KS 66101 Telephone: 913-573-5080 FAX: 913-573-5005	9956	Stephen Hasko 10707 Glenhaven Dr Silver Spring, MD 20902 Telephone: 301-649-5163	238
Ronald M. Gilman Agricultural Commissioner Director of Weights & Measures 263 Camino Del Remedio Santa Barbara, CA 93110 Telephone: 805-681-5600 FAX: 805-681-5603	7837	Paul Hadyka Industrial Specialist USDA/FGIS Room 0623-S PO Box 96454 1400 Ind. Ave Washington, DC 20250-6454 Telephone: 202-382-0262 FAX: 202-447-4628	9402	Ronald G. Hayes Petroleum Lab Supervisor MO Dept of Agriculture PO Box 630 Jefferson City, MO 65102 Telephone: 314-751-2922 FAX: 314-751-8307	9061
William V. Goodpaster Vice President Cardinal Detecto 1610 North C St Sacramento, CA 95814 Telephone: 916-441-0178 FAX: 916-441-5606	1607	Wayne E. Handy Inspector Weights & Measures Johnson County Courthouse Annex Franklin, IN 46131 Telephone: 317-736-3909	148	David K. Heck Coordinator-Policy Anal/Govt A Chevron USA Inc 575 Market St, Room 966 San Francisco, CA 94105-2856 Telephone: 415-894-0910 FAX: 415-894-8468	11242

Edward C. Heffron Director, Food Division MI Dept of Agriculture PO Box 30017 Lansing, MI 48909 Telephone: 517-373-1060 FAX: 517-373-9146	2452	Ward C. Hitchings Dir, Cons, Spec & Info Service National Forest Products Assn 1250 Connecticut Ave, NW Suite 200 Washington, DC 20036 Telephone: 202-463-2765	1742	Christopher L. Irving, Esq. Assistant General Counsel NY City Dept Consumer Affairs 80 Lafayette Street New York, NY 10013 Telephone: 212-566-4862	12809
Sid Hejzlar Vice President Engineering John Chatillon & Sons Inc 83-30 Kew Gardens Rd Kew Gardens, NY 11415 Telephone: 718-847-5000 FAX: 718-441-4365	4201	Herman R. Hochstetler Inspector Elkhart County Weights & Meas 117 N 2nd Goshen, IN 46526 Telephone: 219-534-3541	5855	Michael T. Jackelen Marketing Manager Poly-Tech Inc 1401 W 94th St Minneapolis, MN 55431 Telephone: 612-884-7281 FAX: 612-884-6438	3169
Raymond H. Helmick Director State of AZ Dept of W&M 1951 W North Lane Phoenix, AZ 85021 Telephone: 602-255-5211 FAX: 602-255-1950	10130	Lee Hock Manager Field Services BP Oil Co 4850 E 49th St Cleveland, OH 44125 Telephone: 216-271-8211 FAX: 216-271-8717	6238	David James Program Supervisor MO Dept Agri Dev & Comm Insp PO Box 630 Jefferson City, MO 65102 Telephone: 314-751-5639 FAX: 314-751-8307	9368
Marilyn J. Herman President Herman & Associates 2300 M St, NW, Suite 800 Washington, DC 20037 Telephone: 202-775-1630 FAX: 202-293-3083	9091	Frances P. Holland Authorities & Stan Admin Schlumberger Technologies 3601 Koppens Way Chesapeake, VA 23323 Telephone: 804-366-4400 FAX: 804-487-7350	15654	W. Terry James Vice Pres Engineering Services Cardinal/Detecto Scale Mfg Co 203 E Daugherty PO Box 151 Webb City, MO 64870 Telephone: 417-673-4631 FAX: 417-673-5001	3099
Arthur Hershbein Retired Director Dade County Consumer Protection Division 140 W Flagler St, Ste 1605 Miami, FL 33130 Telephone: 305-375-4222	133	Leonard T. Holtgreven President Loadmaster Scale Mfg 420 E Lincoln St Findlay, OH 45840 Telephone: 419-422-4779 FAX: 419-422-9036	11177	Jack Y. Jeffries Supervisor Division of Standards 7810 Alafia Dr Riverview, FL 33569 Telephone: 904-487-2634 FAX: 813-272-2287	2199
David M. Hershberger Load Cell Product Manager Toledo Scale Inc. 350 W. Wilson Bridge Rd. Worthington, OH 43085 Telephone: 614-438-4679 FAX: 614-438-4770	16257	Monty H. Hopper Director Dept. Of Weights & Measures 1116 E. California Avenue Bakersfield, CA 93307 Telephone: 805-861-2418 FAX: 805-324-0668	11132	Glen H. Jex Chief Bureau of Weights & Measures 2216 Kellogg Lane Boise, ID 83712 Telephone: 208-334-2345 FAX: 208-334-2170	7260
Richard Hewitt VP Sales & Marketing Ishida USA Inc. 6396 Overbrook Ave. Philadelphia, PA 19151 Telephone: 215-879-8284 FAX: 215-879-8238	12955	Richard M. Huff Vice President Electronics Universal Epsco Inc 1494 Ellsworth Ind Dr/Bx 93544 Atlanta, GA 30318 Telephone: 404-351-2740 FAX: 404-351-2899	10608	Mark R. Joelson General Counsel Morgan Lewis & Bockius 1800 M St, NW Washington, DC 20036 Telephone: 202-467-7240 FAX: 202-467-7176	4238
T.L. Hillburn Technical Representative Tumbow Engineering PO Box 1604 Bartlesville, OK 74005 Telephone: 918-333-8475 FAX: 918-333-8879	12772	Clayton H. Hughey Inspector of Weights & Measur Hendricks County 3421 Indiana Rd Plainfield, IN 46168 Telephone: 317-839-4752	9618	Jean Johnson Measurement Assistant American Petroleum Institute 1220 L St NW Washington, DC 20005 Telephone: 202-682-8147 FAX: 202-682-8154	11232
Sam F. Hindsman Director Arkansas Bureau of Standards 4608 W 61st St Little Rock, AR 72209 Telephone: 501-371-1750	45	Randall L. Hutton Associate Director/Comnty Affr Winn-Dixie Stores Inc 5050 Edgewood Ct Jacksonville, FL 32205-0297 Telephone: 904-783-5408 FAX: 904-783-5294	11660	Ted F. Johnson Director of Marketing Sensortronics Inc 677 Arrow Grand Circle Covina, CA 91722 Telephone: 818-331-0502 x201 FAX: 818-332-3418	9899
Donald J. Hine (Retired) AEM Corp 452 W Tenth St Elyria, OH 44035 Telephone: 216-323-2041	3448	William D. Ince Manager Unit Wheel Abrator Coal Services 3505 Olsen Amarillo, TX 79109 Telephone: 806-355-9253	16248		

Galen Joly VP Sheeting Division Poly-Tech Inc 1401 W 94th St Bloomington, MN 55431 Telephone: 612-884-7281 FAX: 612-884-6438	10870	Thomas E. Kirby Retired Rte 3 Box 65C Jackson, GA 30233 Telephone: 404-775-6387	2947	Robert L. Land Inspector of City Anderson Dept of Weights & Measures PO Box 2100, 120 E 8th St Anderson, IN 46011 Telephone: 317-646-9839 FAX: 317-646-5668	187
George E. Jones Director Fuel & Measures Div Georgia Dept of Agriculture Capital Square 19, MLK, Jr. Drive Atlanta, GA 30334 Telephone: 404-656-3606	10624	Paul J. Klein Inspector Weights & Measures St Joseph County 227 West Jefferson Blvd South Bend, IN 46601 Telephone: 219-284-9751	4468	Robert A. LeCaire, Jr. Manager Quality Assurance Presto Products Co 670 N Perkins St Appleton, WI 54914-3133 Telephone: 414-738-1334 FAX: 414-738-1458	9038
Harold D. Jones C. N. Brown Co. South Paris, ME 04218 Telephone:	16246	Chip Kloos Lab Manager-R & D Beatrice/Hunt-Wesson Foods 1645 W Valencia Dr Fullerton, CA 92633-3899 Telephone: 714-680-1098 x1098 FAX: 714-449-5166	3453	Walter G. Leight Acting Deputy Director, OSS Nat'l Inst of Sids & Tech A600 Admin Gaithersburg, MD 20899 Telephone: 301-975-4010	4431
E. Jongen Dir Gen, Int Mrkt & Ind Affair Commission of the Euro. Commu. 3, Rond Point Schuman B-1040 Brussels Belgium, Telephone:	15392	Joan A. Koenig Weights & Measures Coordinator Nat'l Inst of Sids & Tech Admin 101, Rm A617 Gaithersburg, MD 20899 Telephone: 301-975-4007 FAX: 301-926-0647	9036	Jerry Levine Director, Corporate Studies Amoco Oil Co 200 E. Randolph Chicago, IL 60601 Telephone: 312-856-2605 FAX: 312-856-7006	13791
Raymond Kalentkowski Supervisor Weights & Measures Division State Office Bldg/Cons Prot Hartford, CT 06106 Telephone: 203-566-4778 FAX: 203-566-7630	7243	Willem Kool OIML SP7/SR2 Berkel PO Box 251 NL 2280 AG Ryswyk The Netherlands, Telephone: 3170 39563000 FAX: 3170 3995623	15332	Raymond J. Lloyd Executive Director Scale Manufacturers Assn 932 Hungerford Dr #36 Rockville, MD 20850 Telephone: 301-738-2448 FAX: 301-738-0076	7
Eugene Keeley Administrator Delaware Weights & Measures 2320 S Dupont Highway Dover, DE 19901 Telephone: 302-736-4811 x37 FAX: 302-697-6287	22	Nelson Kranker Director Dutchess Co Dept of Cons Affrs 22 Market St Poughkeepsie, NY 12602 Telephone: 914-471-6322	9394	Harvey M. Lodge Dunbar Manufacturing Inc 307 Broadway Swanton, OH 43558 Telephone: 419-825-2331 FAX: 419-826-8439	355
Michael J. Keilty Product Mgr-Custody Transfer Micro Motion Inc 7070 Winchester Circle Boulder, CO 80501 Telephone: 303-530-8400 FAX: 303-530-8418	11672	Walter E. Kupper Director Tech & Reg Affairs Mettler Instrument Corp PO Box 71 Hightstown, NJ 08520-0071 Telephone: 609-443-8861 FAX: 609-443-5972	3930	Heliodoro Lopez-Torres Dir Weights & Measures Dept Of Consumer Affairs P O Box 41059 Manillas Station Santurce, PR 00940 Telephone: 809-721-1930 FAX: 809-726-6570	9390
Robert B. Kelley Deputy Director NYC Dept Of Consumer Affairs 80 Lafayette St New York, NY 10013 Telephone: 212-566-8776 FAX: 212-566-8678	228	Dan Kushnir Sales Manager Seraphin Test Measure 30 Indel Ave Rancocas, NJ 08073 Telephone: 609-267-0922 FAX: 609-261-2546	9902	Forrest Joe Loyd, Jr. Engineer-Scales & Weighing CSX Transportation Inc 500 Water St, Room 907 Jacksonville, FL 32202 Telephone: 904-359-1024 FAX: 904-359-7476	9086
Robert L. Kessler Exec Director - Gen Counsel Western Coal Trans Assn PO Box 176 Denver, CO 80201 Telephone: 303-694-6611 FAX: 303-220-1891	11693	John T. Lacy Chief Scales & Weighing Branch USDA Packers & Stockyards Adm 3414 S 14th & Independence Ave Washington, DC 20250 Telephone: 202-447-3140	246	David Lunceford Northeast Regional Mgr SGS Control Services Inc 20 Lafayette St Carteret, NJ 07008 Telephone: 201-541-7200	94
Brenda K. Kincaid Program Manager II City of Kansas City W&M 701 North 7Th St Kansas City, KS 66101 Telephone: 913-573-5080 FAX: 913-573-5005	9224	Steve Lambert Corp Q A Mgr Frigo Cheese Corporation 1088 Springhurst Dr Green Bay, WI 54304 Telephone: 414-494-2228 x305 FAX: 414-494-7717	6251	James F. Lyles Retired Chief VA Weights & Measures Bur. 7804 Lycoming Rd. Richmond, VA 23229 Telephone: 804-285-0559	57

Dr. John W. Lyons Director National Inst. of Stds & Tech. Quince Orchard & Clopper Roads Gaithersburg, MD 20899 Telephone: 301-975-2300	15321	Bruce Martell Supervisor, Cons. Assur. Div. Vermont Dept of Agriculture 116 State Street SOB Montpelier, VT 05602 Telephone: 802-828-2436 FAX: 802-828-2361	10126	James Melgaard Director Div Commercial Insp & Reg 118 West Capitol Pierre, SD 57501-2080 Telephone: 605-773-3697 FAX: 605-773-4117	39
Melvin L. Lyons Asst Director LA Wts & Measure LA Dept of Agri and Forestry PO Box 3098 Baton Rouge, LA 70821-3098 Telephone: 504-925-3780 FAX: 504-922-1289	8632	Vernon Lee Massey Sealer Shelby County Government 157 Poplar Suite 402 Memphis, TN 38103 Telephone: 901-576-3920	3634	Charles W. Michell, Jr. Sr Loss Control Representative Shell Oil Co PO Box 2463/Rm 2286 One Shell P Houston, TX 77001 Telephone: 713-241-0455	9082
John MacDonald Vice President, Engineering Howe Richardson 680 Van Houten Avenue Clifton, NJ 07003 Telephone: 201-471-3400 FAX: 201-472-7851	7542	Tom Masuyama Software Engineer TEC America Inc 19300 Hamilton Ave, Suite 200 Gardena, CA 90248 Telephone: 213-329-9600 FAX: 213-329-1490	13726	Stanley K. Millay Supervisor ME Dept Agriculture W&M Division of Regulations Station 28 Augusta, ME 04333 Telephone: 207-289-2751 FAX: 207-289-7161	74
James E. Maka Chief Metrologist Div Of Measurement Standards 725 Ilalo St Honolulu, HI 96813-5524 Telephone: 808-548-7168	8069	George E. Mattimoe Retired Admin Measurement Stds 953 Wainiha St Honolulu, HI 96825 Telephone: 808-395-1492 FAX: 808-548-8524	2508	Joan Mindte Training Coordinator National Inst of Stds & Tech A609 Admin Gaithersburg, MD 20899 Telephone: 301-975-4003 FAX: 301-926-0647	12500
Steven A. Malone Director Weights & Measures Division 301 Centennial Mall, S, Box 94757 Lincoln, NE 68509 Telephone: 402-471-4292 x208 FAX: 402-471-3252	554	Arthur L. McCabe Fuel Transportation Administr Consumers Power Co 1945 W Parnall Rd Jackson, MI 49201 Telephone: 517-788-1388	13802	Daniel H. Moenter Manager, Government Affairs Marathon Oil Company 539 South Main Street Findlay, OH 45840 Telephone: 419-422-2121 FAX: 419-422-2121	11212
Renald Marceau Program Officer Consumer & Corporate Affaris 207 Queen St, Ottawa CANADA K1A 0C9, 026 Telephone: 613-952-2633	10211	Robert McCarty Systems Engineer-Industry Stds NCR Corp PO Box 728, 800 Cochran Ave Cambridge, OH 43725 Telephone: 614-439-0579 FAX: 614-439-0249	11686	Charles W. Moore County Inspector Weights & Measures Madison County Govt Center Box 15 Anderson, IN 46011 Telephone: 317-641-9662 FAX: 317-641-9486	2739
Sheryl A. Marcouiller Food & Drug Counsel Kraft General Foods, Inc. Kraft Court Glenview, IL 60025 Telephone: 708-998-7650 FAX: 708-999-6431	16244	T. B. McDonald Manager Resale Facilities Eng. Mobil Oil Corp 8260 Willow Oaks Corp Dr Rm 2M-211 Fairfax, VA 22038 Telephone: 703-849-5320 FAX: 703-849-5074	12456	G. E. Moore VP Technical Liaison Dover Corp OPW Division PO Box 405003 Cincinnati, OH 45240-5003 Telephone: 513-870-3202 FAX: 513-874-1231	584
Patrick Marino Technical Service Manager New Brunswick Internatl Inc 76 Veronica Ave Somerset, NJ 08873 Telephone: 201-828-3633 FAX: 201-828-4884	9366	Sterling McFarlane Supervisor Weights & Measures Dept of Licenses & Cons Aff Room 102, 600 4th Ave Seattle, WA 98104 Telephone: 206-386-1298	8397	Thomas L. Morrow Business Unit Manager TEC America Inc 19300 Hamilton Ave Suite 200 Gardena, CA 90248 Telephone: 213-329-9600 FAX: 213-329-1490	3380
Alan V. Marsh Supervisor Weights & Measures Butler Co Wts & Meas 130 High St Hamilton, OH 45011 Telephone: 513-887-3157	10361	Stephen E. McGuire Metrologist Illinois Dept of Agriculture 801 E Sangamon Ave Springfield, IL 62794-9281 Telephone: 217-785-8480 FAX: 217-524-5960	4000	Ronald D. Murdock Standards Division NC Dept of Agriculture PO Box 27647 Raleigh, NC 27611 Telephone: 919-733-3313	8366
Glen R. Marshall Staff Engineer Shell Oil Co 777 Walker - TSP1130 Houston, TX 77002 Telephone: 713-241-1452 FAX: 713-241-7166	10444	John R. McPherson Senior Staff Engineer Exxon Co USA PO Box 4415, 1200 Smith St Houston, TX 77210 Telephone: 713-656-7757 FAX: 713-656-7789	9392	Larry Murray Chief Engineer Wayne Div-Dresser Industries 124 W College Ave PO Box 1859 Salisbury, MD 21801 Telephone: 301-546-6690 FAX: 301-546-6888	5879

Frank Nagele Weights & Measures Specialist MI Dept Of Agriculture 1006 Britten Ave Lansing, MI 48910-1328 Telephone: 517-372-1784	2470	Claude R. Parent Consultant Private 7 Eastwood Drive Orinda, CA 94563 Telephone: 415-376-5697	610	Richard L. Philmon Program Coordinator Illinois Dept of Agric 801 E Sangamon Ave Springfield, IL 62794-9281 Telephone: 217-782-3817	9168
Joseph V. Nagy Sealer of Weights & Measures City of South Bend Indiana 701 W Sample Street South Bend, IN 46618 Telephone: 219-284-9273	2711	Bill B. Paull Standards Engineer Hobart Corp/PMI Food Equip. World Headquarters Troy, OH 45374 Telephone: 513-332-2651 FAX: 513-332-2142	10650	Richard Pierce Ag Engr, Type Approval Group USDA FGIS Box 20285 Kansas City, MO 64195 Telephone: 816-891-8553	13794
Allan M. Nelson Director Weights & Measures Dept of Consumer Protection 165 Capitol Ave, Room G17 Hartford, CT 06106 Telephone: 203-566-4778 FAX: 203-566-7630	2515	James E. Peeples Director Legislative Affairs Information Resources Inc 499 S. Capitol St Suite 400 Washington, DC 20003 Telephone: 202-554-0614	7505	Allen W. Pirlot Deputy Inspector Dept of Weights & Measures City County Bldg Room 1760 Indianapolis, IN 46204 Telephone: 317-236-4272	8171
Gerald H. Nessonson President Valvtect Petroleum Products 3400 Dundee Rd, #330 Northbrook, IL 60062 Telephone: 708-272-2278 FAX: 708-272-4260	14761	H.Steffen Peiser Consultant 638 Blossom Dr Rockville, MD 20850 Telephone: 301-762-6860	3462	Cathryn F. Pittman Technologist TN Department of Agriculture PO Box 40627 Melrose Station Nashville, TN 37204 Telephone: 615-360-0159	2403
Karl Newell Office of Weights & Measures Nat'l Inst of Sids & Tech Admin 101, Rm A617 Gaithersburg, MD 20899 Telephone: 301-975-4013 FAX: 301-926-0647	9879	Peter R. Perino President Revere Transducers Inc 14030 Bolsa Lane Cerritos, CA 90701 Telephone: 714-739-1991 FAX: 714-522-0931	3894	Alan Porter Technical Unit Supervisor Wisconsin Dept of Agriculture 801 W Badger Rd, Box 8911 Madison, WI 53708 Telephone: 608-266-7244 FAX: 608-266-1300	8752
Glen W. Newton Manager Transportation Arco Coal Company 555 17th St Denver, CO 80202 Telephone: 303-293-7785 FAX: 303-293-4820	9664	Paul L. Peterson Industrial Specialist USDA Packers & Stockyards Adm 14th & Independence, SW, Rm 3414 S Washington, DC 20250 Telephone: 202-447-5841	248	Marian Powell-Tyree President Powell All-Steel Scales Inc Rt 8 Box 432 Curry Road Hwy 257 Jasper, AL 35501 Telephone: 205-387-8647 FAX: 205-384-3805	9414
Patrick E. Nichols Director Weights & Measures Dept of Weights & Measures 333 Fifth Street Oakland, CA 94607-4107 Telephone: 415-268-7287 FAX: 415-444-3879	110	Richard R. Pforr Branch Chief WEB USDA/FGIS 1400 Independence Ave Room 1640 Washington, DC 20250 Telephone: 202-382-0262 FAX: 202-447-4628	2327	Edwin J. Price Enforcement Coordinator Dept of Agriculture PO Box 12847 Austin, TX 78711 Telephone: 512-463-7607 FAX: 512-475-1618	2434
J.W. Noble Department Engineer Silas Mason Co Inc PO Box 30020 Amarillo, TX 79177 Telephone: 806-477-4301	13479	Richard L. Phegley Exxon Co USA PO Box 2180 Houston, TX 77252-2180 Telephone: 713-656-8510	11697	Gale Prince Manager Regulatory Compliance Kroger Co 1014 Vine St Cincinnati, OH 45201 Telephone: 513-762-4209 FAX: 513-762-4372	10651
Henry V. Oppermann General Physical Scientist Nat'l Inst of Sids & Tech Admin 101, Rm A617 Gaithersburg, MD 20899 Telephone: 301-975-4008 FAX: 301-926-0647	3389	DeVern H. Phillips State Sealer Kansas Div of Inspections 2016 SW 37th St Topeka, KS 66611-2570 Telephone: 913-267-4641 FAX: 913-296-2247	10619	John V. Pugh Director Metrology Laboratory S C Dept Of Agriculture PO Box 11280 Columbia, SC 29211 Telephone: 803-253-4052 FAX: 803-734-2192	95
Victor L. Page Director KY Dept of Agric Wts & Meas 106 West 2nd St Frankfort, KY 40601 Telephone: 502-564-4870 FAX: 502-564-6527	3904	Michelle I. Phillips Assistant Administrator Dept of Weights & Measures City County Bldg, Room 1760 Indianapolis, IN 46204 Telephone: 317-236-4272	9076	Patrick Quigg Director of Quality Control General Mills Inc Number One General Mills Blvd Minneapolis, MN 55426 Telephone: 612-540-2354 FAX: 612-540-2109	11118

David W. Quinn Product Manager Fairbanks Scales 69th Ave Industrial Park Meridian, MS 39307 Telephone: 601-483-4311 FAX: 601-483-4311	11509	J.A. Rogers Chief Virginia Weights & Measures 1100 Bank St Richmond, VA 23209 Telephone: 804-786-2476 FAX: 804-371-7793	9374	Brad H. Schumacher National Account Manager Dresser/Wayne 8420 West Bryn Mawr Suite 950 Chicago, IL 60631 Telephone: 312-693-7400 FAX: 312-693-3618	13740
John B. Rabb W & M Laboratory Supervisor Div of Weights & Measures PO Box 3336 Montgomery, AL 36193 Telephone: 205-242-2652	89	Terry Rosfelder Manager of Engineering Project Sun Refining & Marketing Co 1801 Market Street 21st Floor Philadelphia, PA 19103-1699 Telephone: 215-977-6502 FAX: 215-246-8098	9078	H.E. Schumacher V/P Sales & Services Kerr McGee Coal Corp PO Box 25861 Oklahoma City, OK 73125 Telephone: 405-270-3735 FAX: 405-270-2490	9674
Robert A. Reinfried Technical Assistant Scale Manufacturers Assn 932 Hungerford Dr, #36 Rockville, MD 20850 Telephone: 301-738-2448 FAX: 301-738-0076	9388	Thomas P. Ross Retail Analyst Mobil Oil Corp 8280 Willow Oaks Corp Dr, Rm 7W 907 Fairfax, VA 22037 Telephone: 703-849-3834 FAX: 703-849-5831	15336	Richard L. Seitz Manager Mech Petro Engr Veeder-Root Co 125 Powder Forest Dr, POB 2003 Simsbury, CT 06070-2003 Telephone: 203-651-2722 FAX: 203-651-2719	1032
Robert E. Reynolds Downstream Alternatives Inc PO Box 190 Bremen, IN 46506 Telephone: 219-546-4204 FAX: 219-546-5845	10653	Joseph Rothleder Principal State Metrologist CA Div of Measurement Standard 8500 Fruitridge Rd Sacramento, CA 95826 Telephone: 916-366-5119 FAX: 9160366-5179	3495	M. Richard Shockley Program Manager Maryland Dept of Agriculture 50 Harry S Truman Parkway Annapolis, MD 21401 Telephone: 301-841-5790	9057
Sharon Rhoades Administrator Division of Weights & Measures 1330 W Michigan St, Rm 136N Indianapolis, IN 46206 Telephone: 317-633-0350	8157	Albert E. Salerno President Syracuse Scale Co Inc 158 Solar St Syracuse, NY 13204 Telephone: 315-476-9696 FAX: 315-476-3743	12232	Joseph Silvestro Superintendent Gloucester Co Wts & Meas Dept 49 Wood St County Bldg Woodbury, NJ 08096 Telephone: 609-853-3358 FAX: 609-853-2770	2809
Austin T. Rhoads President Northeast Ice Cream Assn P O Box 0510 Fulton, MD 20759-0510 Telephone: 301-953-9117	7521	Martin Scanlon Sr Project Tech Specialist Federal Express Corp 2842 Business Park Dr Memphis, TN 38118-2822 Telephone: 901-369-3085 FAX: 901-797-5202	13778	Kendrick J. Simila Administrator Measmt Sds Div Oregon Dept of Agriculture 635 Capitol St, NE Salem, OR 97310-0110 Telephone: 503-378-3792 FAX: 503-378-5529	2510
Marsha L. Richardson Inspector Gibson County Wts & Meas Courthouse Annex, 800 S Prince St Princeton, IN 47670 Telephone: 812-385-2426	11136	Tom W. Schafer Metrologist Idaho Weights & Measures 2216 Kellogg Lane Boise, ID 83712 Telephone: 208-334-2345 FAX: 208-334-2170	10000	John C. Skuce Manager Mechanical Engineering Smith Meter Inc 1602 Wagner Ave-PO Box 10428 Erie, PA 16514 Telephone: 814-898-5405 FAX: 814-899-8927	10442
Richard L. Rightmyer Senior Staff Engineer VA Power PO Box 26666 Richmond, VA 23236 Telephone: 804-771-3862 FAX: 804-771-3166	11075	Dennis Schaffer Marketing Product Manager TEC America Inc 19300 Hamilton Ave Suite 200 Gardena, CA 90248 Telephone: 213-329-9600 FAX: 213-329-1490	3911	Douglas C. Smith Technical Services Rep William M Wilsons Sons Inc 8th St & Valley Forge Rd Lansdale, PA 19446-0309 Telephone: 215-855-4631 x236 FAX: 215-855-0341	262
Gage Robertson Senior Engineer-Performance Southwestern Public Service Co PO Box 1261 Amarillo, TX 79170 Telephone: 806-378-2722	9686	James Schnitzler Gen Mgr Milk Receiving Sym Accurate Metering Systems Inc 1651 Wilkening Court Schaumburg, IL 60173 Telephone: 708-882-0690 FAX: 708-882-2695	10871	N. David Smith Director Standards Division NC Dept of Agriculture PO Box 27647, Dept SD Raleigh, NC 27611 Telephone: 919-733-3313 FAX: 919-733-0999	2391
John J. Robinson Sr. Assistant Vice President Assn of American Railroads 50 F St NW Washington, DC 20001 Telephone: 202-639-2204 FAX: 202-639-2930	743			Richard N. Smith Retired Tech Coordinator Natl Institute of Std & Tech 1003 Windemere Rd Inwood, WV 25428 Telephone: 304-229-5964	237

Robert A. Smoot Deputy Dir. Weights & Measures Utah Dept of Agriculture 350 North Redwood Rd Salt Lake City, UT 84116 Telephone: 801-538-7158 FAX: 801-538-7126	10657	George W. Strayer National Quality Assurance Mgr Baskin Robbins USA 1201 S Victory Blvd Burbank, CA 91502 Telephone: 818-569-3764 FAX: 818-841-6569	13733	Daryl E. Tonini Technical Director Scale Manufacturers Assn 932 Hungerford Dr, #36 Rockville, MD 20850 Telephone: 301-738-2448 FAX: 301-738-0076	1336
Donald J. Soberg Admin Trade & C.P. Division Wisconsin Dept of Agriculture 801 W Badger Rd, PO Box 8911 Madison, WI 53708 Telephone: 608-266-7220 FAX: 608-266-1300	3478	Chester Szyndrowski Inspector Weights & Measures City of East Chicago 1102 W 151 Street East Chicago, IN 46312 Telephone: 219-397-3409	10302	Jose A. Torres-Ferrer Metrologist/W&M Supervisor Department of Consumer Affairs PO Box 41059 Minillas Station Santurce, PR 00940-1059 Telephone: 809-721-1930 FAX: 809-726-6570	11193
Louis F. Sokol President Emeritus and Editor US Metric Association 255 Mountain Meadows Rd Boulder, CO 80302-9256 Telephone: 303-443-9728	1021	Albert D. Tholen Chief Off of Weights & Measure Natl Inst of Stds & Tech Admin 101, Rm A617 Gaithersburg, MD 20899 Telephone: 301-975-4009 FAX: 301-926-0647	232	Jonas E. Townsend, Jr. Assistant Superintendent Cumberland County 788 E Commerce St Bridgeton, NJ 08302 Telephone: 609-453-2203 x 2205 FAX: 609-451-0967	6068
George R. Spencer Sales & Distribution Mgr. Duraflame Inc 2005 W Washington St Stockton, CA 95203 Telephone: 209-948-2515 FAX: 209-948-2862	11340	Ellen Thomas Manager Regulatory Indus Relns Kraft Inc 5401 Old Orchard Rd Skokie, IL 60077 Telephone: 708-998-2000 x2054 FAX: 708-998-7801	6127	Jon C. Trejo President Trejo Oil Company Inc. Po Box G Caja Grande, AZ 85222 Telephone: 602-836-5352 FAX: 6902-421-022	16247
Thomas M. Stabler Manager-Weights & Measures Toledo Scale Corp PO Box 1705 Columbus, OH 43216 Telephone: 614-438-4548 FAX: 614-438-4646	3119	Aves D. Thompson Chief Div of Measurement Standards 12050 Industry Way PO11686 Anchorage, AK 99511 Telephone: 907-345-7750 FAX: 907-345-2641	10201	James C. Truex Weights & Measures Insp Mgr Ohio Dept of Agriculture 8995 E Main St Reynoldsburg, OH 43068 Telephone: 614-866-6361 FAX: 614-866-4174	2178
Don E. Stagg Director Weights & Measures Division PO Box 3336 Montgomery, AL 36193 Telephone: 205-242-2613 or 2614 FAX: 205-240-3135	3317	E.A. (Hap) Thompson Marketing Department American Petroleum Institute 1220 L Street NW Washington, DC 20005 Telephone: 202-682-8230 FAX: 202-682-8222	715	Richard Tucker Manager Customer Service Tokheim Corp 1602 Wabash Ave Ft Wayne, IN 46801 Telephone: 219-425-2552 FAX: 219-484-4887	9070
Fred J. Staudinger Business Manager Pitney Bowes Walter H Wheeler Jr Drive Loc 2700 Stamford, CT 06926 Telephone: 203-925-5235 FAX: 203-925-5140	3177	Merrill S. Thompson Merrill S. Thompson, P.C. Arnold & Porter PO Box 8500 Bridgeton, IN 47836 Telephone: 317-548-2202	590	Ann H. Turner Conference Coordinator Natl Conf on Wts & Meas PO Box 4025 Gaithersburg, MD 20885 Telephone: 301-975-4012 FAX: 301-926-0647	236
Michael K. Stephenson Inspector Michigan Dept of Agriculture 244 Marshall St Allegan, MI 49010 Telephone: 616-673-8812	4471	Kathleen A. Thuner Agric Comm Sealer Wts & Meas Dept of Agric Wts & Meas 5555 Overland Ave, Bldg 3 San Diego, CA 92123-1292 Telephone: 619-694-2741 FAX: 619-565-7046	5869	Eric A. Vadelund Senior Standards Specialist Natl Institute of Stds & Tech Admin Bldg Rm A625 Gaithersburg, MD 20899 Telephone: 301-975-4028	3388
Louis E. Straub Program Manager Weights & Measures Section 50 Harry S Truman Parkway Annapolis, MD 21401 Telephone: 301-841-5790 FAX: 301-841-5999	6248	Walter Tkachuk Senior Loss Control Specialist Shell Oil Co 17919 Fireside Dr Spring, TX 77379 Telephone: 713-251-0327	7543	Calvin F. Vance Chief Enforcement Officer AZ Dept of Weights & Measures 1951 W North Lane Phoenix, AZ 85021 Telephone: 602-255-5211 FAX: 602-255-1950	7607
		Guy J. Tommasi Sealer of Weights & Measures City of Middletown City Hall-245 Dekoven Drive Middletown, CT 06457 Telephone: 203-344-3492 x492 FAX: 203-344-0136	214	Lester C. Venable Area Supervisor Tenn Dept Of Agriculture 4735 Waynesboro Highway Lawrenceburg, TN 38464 Telephone: 615-360-0160	8800

Gilles Vinet Program Officer Weights & Meas CANADA Legal Met Branch 207 Queen St, 2nd Fl, Ottawa CANADA K1A 0C9, Telephone: 613-952-2632 FAX: 613-952-1736	11941	Raymond R. Wells President Sensitive Measurement Inc 200 SMI W Hampton St, PO Box 72 Pemberton, NJ 08068 Telephone: 609-894-2292 FAX: 609-894-0387	3484	Paul Zalon Director Regulatory Affairs Nestle Foods Corp 100 Manhattanville Rd Purchase, NY 10577 Telephone: 914-251-3487 FAX: 914-251-2961	7312
Robert C. Wainscott Senior Vice President Inspectorate America Corp. 5050 Timber Creek Houston, TX 77017 Telephone: 713-944-2000 FAX: 713-947-0300	15661	Richard L. Whipple Senior Regulatory Engineer Gilbarco Inc 7300 W Friendly Ave, PO Box 22087 Greensboro, NC 27420 Telephone: 919-547-5150 FAX: 919-292-8871	3486	Andrew A. Zards Specialist Facilities Engineer Amoco Oil Co 200 E Randolph Dr Chicago, IL 60601 Telephone: 312-856-4073	1344
Doug Walker Measurement Coordinator Marathon Petroleum Co 425 S 20th St Tampa, FL 33605 Telephone: 813-248-6730	11688	George Wilson Senior Science Advisor American Meat Institute 2510 Shagbark, SE Grand Rapids, MI 49546 Telephone: 616-956-0507 FAX: 616-956-0507	12814	Joel H. Zimmerman Quality Assurance Systems Mgr ConAgra Frozen Foods Co 5 ConAgra Drive Omaha, NE 68102 Telephone: 402-595-6433	13225
David R. Wallace Chief Meas Standards Section Colorado Dept of Agriculture 3125 Wyandot St Denver, CO 80211 Telephone: 303-866-2845 FAX: 303-480-9236	4475	Kenneth L. Wilson Automation Specialist Arco Products Co 8601 S Garfield Ave South Gate, CA 90280 Telephone: 213-806-4180 FAX: 213-806-4130	1966	H.G. Zinsmeyer President Additive Systems Inc 8500 North Mopac, #825 Austin, TX 78759 Telephone: 512-346-8514	15329
Irene B. Warnlof Retired Wts & Meas Official 9705 Inaugural Way Gaithersburg, MD 20879 Telephone: 301-926-8155	7145	William J. Wilson Director Of Wts & Measures Clinton County W & M 137 Margaret St Plattsburgh, NY 12901 Telephone: 518-565-4600 FAX: 518-565-4616	4493	Harold Zorlen Regional Supervisor MI Dept of Agric Reg VII 23777 Greenfield, 320 Southfield, MI 48075 Telephone: 313-443-0566	9009
Otto K. Warnlof Standards Management Natl Inst of Stds & Tech Admin Bldg A625 Gaithersburg, MD 20899 Telephone: 301-975-4026 FAX: 301-926-0647	233	Randall Wise KY Dept of Agric Wts & Meas 106 West 2nd Street Frankfort, KY 40601 Telephone: 502-564-4870	10293		
Stanley I. Warsaw Acting Director, OSS Natl Institute of Stds & Tech A603 Admin Bldg Gaithersburg, MD 20899 Telephone: 301-975-4001	4426	Robert Wittenberger Metrologist Weights & Measures Laboratory PO Box 630 Jefferson City, MO 65102 Telephone: 314-751-3440	91		
David Watson Consumer Products Supervisor City of Fort Worth Texas 1000 Throckmorton, 5th Floor Fort Worth, TX 76102 Telephone: 817-870-7386 FAX: 817-870-	2656	Theodore H. Yaffe Program Manager US Postal Service 8403 Lee Highway Merrifield, VA 22082-8101 Telephone: 703-641-7055 FAX: 703-280-4541	10872		
Steve M. Watson Marketing Manager Sartorius Corporation 140 Wilbur Place Bohemia, NY 11716 Telephone: 516-563-5120 FAX: 516-563-5065	16216	W. E. Yager Superintendent Cabot-Tuco Inc PO Box 9902 Amarillo, TX 79105-5902 Telephone: 806-371-7341	11671		
Richard H. Weber Metrology Lab 3M Co Bldg 544-1-02, 3M Center St Paul, MN 55144-1000 Telephone: 612-733-2674 FAX: 612-736-7325	684	Arthur L. Young Supervisor Weights And Measures Division American Samoa Government Pago Pago American Samoa, AS 96799 Telephone: 946-633-1663	4112		





